

1 **BILL NO. S-20-06-12**

2 SPECIAL ORDINANCE NO. S- 72-20

3 AN ORDINANCE approving CONSTRUCTION
4 CONTRACT - SPRINGWOOD-ORCHARD WOODS
5 CONCRETE STREET REPAIRS, PHASE 1,
6 RESOLUTION #0419C - \$2,057,777.77 between
7 HIPSKIND CONCRETE and the City of Fort Wayne,
8 Indiana, in connection with the Board of Public Works.

9 **NOW, THEREFORE, BE IT ORDAINED BY THE COMMON**
10 **COUNCIL OF THE CITY OF FORT WAYNE, INDIANA:**

11 **SECTION 1.** That the CONSTRUCTION CONTRACT -
12 SPRINGWOOD-ORCHARD WOODS CONCRETE STREET REPAIRS, PHASE 1,
13 RESOLUTION #0419C - \$2,057,777.77 by and between HIPSKIND CONCRETE
14 and the City of Fort Wayne, Indiana, in connection with the Board of Public Works,
15 is hereby ratified, and affirmed and approved in all respects, respectfully for:

16 All labor, insurance, material, equipment, tools, power,
17 transportation, miscellaneous equipment, etc., necessary for
18 improvement of poor condition concrete streets in the
19 Springwood-Orchard Woods neighborhood by removing and
20 replacing concrete pavement, residential drive approaches,
21 sidewalks and updated ADA Ramps, improve drainage features,
22 and finalize restoration and seeding;

23 involving a total cost of TWO MILLION FIFTY-SEVEN THOUSAND SEVEN
24 HUNDRED SEVENTY-SEVEN AND 77/100 DOLLARS - (\$2,057,777.77). A copy
25 of said Contract is on file with the Office of the City Clerk and made available for
26 public inspection, according to law.
27
28
29
30

Bid Tabulation

Proj: Bid Dat	Springwood-Orchard Woods Concrete Street Repairs Phase 1	RES. NO. / W 0419C		TOTAL: \$2,630,278.00		TOTAL: \$2,057,777.77		TOTAL: \$2,318,400.00		TOTAL: \$2,402,646.00			
	06/04/20	Estimate		BIDDER: Hipskind Concrete		BIDDER: Malott Contracting		BIDDER: Garcia Concrete		% over % under	% over % under	% over % under	% over % under
ITEM NO.	ITEM	PLAN QTY	UNIT	UNIT COST Est (\$)	AMOUNT Est (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)
1	Applewood Road Removal of Concrete	210	SYD	\$10.00	\$2,100.00	\$10.00	\$2,100.00	\$14.45	\$3,034.50	\$13.50	\$2,835.00		
2	Applewood Road Removal of Concrete Pavement	3289	SYD	\$12.00	\$39,468.00	\$10.00	\$32,890.00	\$11.45	\$37,659.05	\$12.50	\$41,112.50		
3	Applewood Road Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,350.00	\$1,350.00	\$1,525.00	\$1,525.00	\$1,050.00	\$1,050.00		
4	Applewood Road Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,400.00	\$4,800.00	\$2,745.00	\$5,490.00	\$1,580.00	\$3,160.00		
5	Applewood Road Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$20.00	\$100.00	\$20.00	\$100.00	\$15.00	\$75.00		
6	Applewood Road Mailbox Remove & Relocate	8	EA	\$120.00	\$960.00	\$25.00	\$200.00	\$110.00	\$880.00	\$75.00	\$600.00		
7	Applewood Road Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	3289	SYD	\$38.00	\$124,982.00	\$29.00	\$95,381.00	\$34.50	\$113,470.50	\$35.00	\$115,115.00		
8	Applewood Road Concrete Sidewalk (4")	138	SYD	\$44.00	\$6,072.00	\$38.00	\$5,244.00	\$45.00	\$6,210.00	\$48.50	\$6,693.00		
9	Applewood Road Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00		
10	Applewood Road Concrete Pavement for Residential Drive (6")	55	SYD	\$75.00	\$4,125.00	\$52.00	\$2,860.00	\$52.00	\$2,860.00	\$65.00	\$3,575.00		
11	Applewood Road Concrete Wingwalk and Ramps (6")	35	SYD	\$150.00	\$5,250.00	\$115.00	\$4,025.00	\$87.00	\$3,045.00	\$115.00	\$4,025.00		
12	Applewood Road ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	5	EA	\$225.00	\$1,125.00	\$225.00	\$1,125.00	\$175.00	\$875.00	\$200.00	\$1,000.00		
13	Applewood Road Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	2205	LFT	\$12.00	\$26,460.00	\$7.50	\$16,537.50	\$8.10	\$17,860.50	\$11.50	\$25,357.50		
14	Applewood Road Type "O" Compacted Aggregate for Base, No. #53	440	TON	\$30.00	\$13,200.00	\$28.00	\$12,320.00	\$25.00	\$11,000.00	\$24.50	\$10,780.00		
15	Applewood Road Recycled Concrete Compacted Aggregate for Base, No. #53	433	TON	\$25.00	\$10,825.00	\$24.00	\$10,392.00	\$24.00	\$10,392.00	\$20.00	\$8,660.00		
16	Applewood Road Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	46	TON	\$25.00	\$1,150.00	\$24.00	\$1,104.00	\$30.00	\$1,380.00	\$20.00	\$920.00		
17	Applewood Road Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$5,700.00	\$5,700.00	\$6,400.00	\$6,400.00	\$7,000.00	\$7,000.00		
18	Applewood Road Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00		
19	Applewood Road 1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50		
20	Applewood Road Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00		
21	Applewood Road Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00		
22	Applewood Road Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00		
23	Applewood Road 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	3	EA	\$150.00	\$450.00	\$250.00	\$750.00	\$195.00	\$585.00	\$300.00	\$900.00		
24	Applewood Road 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00		
25	Applewood Road Sedguard Inlet Protection Device	4	EA	\$80.00	\$320.00	\$25.00	\$100.00	\$60.00	\$240.00	\$30.00	\$120.00		
26	Applewood Road Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00		
27	Applewood Road Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00		
28	Applewood Road TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation Aggregate)	600	SYD	\$14.00	\$8,400.00	\$12.50	\$7,500.00	\$14.00	\$8,400.00	\$15.00	\$9,000.00		
29	Applewood Road Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$5,430.00	\$5,430.00	\$3,500.00	\$3,500.00		
30	Applewood Road Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,750.00	\$5,750.00	\$7,500.00	\$7,500.00		
31	Orangewood Court Removal of Concrete	40	SYD	\$10.00	\$400.00	\$10.00	\$400.00	\$14.60	\$584.00	\$13.50	\$540.00		
32	Orangewood Court Removal of Concrete Pavement	839	SYD	\$12.00	\$10,068.00	\$10.00	\$8,390.00	\$11.45	\$9,606.55	\$12.50	\$10,487.50		
33	Orangewood Court Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,500.00	\$1,500.00	\$1,625.00	\$1,625.00	\$1,050.00	\$1,050.00		
34	Orangewood Court Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	1	EA	\$2,400.00	\$2,400.00	\$2,500.00	\$2,500.00	\$3,025.00	\$3,025.00	\$1,580.00	\$1,580.00		

35	Orangewood Court	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$10.00	\$50.00	\$20.00	\$100.00	\$15.00	\$75.00
36	Orangewood Court	Mailbox Remove & Relocate	7	EA	\$120.00	\$840.00	\$25.00	\$175.00	\$120.00	\$840.00	\$75.00	\$525.00
37	Orangewood Court	Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	839	SYD	\$38.00	\$31,882.00	\$29.00	\$24,331.00	\$34.50	\$28,945.50	\$35.00	\$29,365.00
38	Orangewood Court	Concrete Sidewalk (4')	18	SYD	\$44.00	\$792.00	\$38.00	\$684.00	\$45.00	\$810.00	\$48.50	\$873.00
39	Orangewood Court	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
40	Orangewood Court	Concrete Pavement for Residential Drive (6")	22	SYD	\$75.00	\$1,650.00	\$52.00	\$1,144.00	\$52.00	\$1,144.00	\$65.00	\$1,430.00
41	Orangewood Court	Concrete Wingwalk and Ramps (6")	11	SYD	\$150.00	\$1,650.00	\$115.00	\$1,265.00	\$87.00	\$957.00	\$115.00	\$1,265.00
42	Orangewood Court	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	2	EA	\$225.00	\$450.00	\$225.00	\$450.00	\$175.00	\$350.00	\$200.00	\$400.00
43	Orangewood Court	Underdrain 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	465	LFT	\$12.00	\$5,580.00	\$7.50	\$3,487.50	\$8.15	\$3,789.75	\$11.50	\$5,347.50
44	Orangewood Court	Type "O" Compacted Aggregate for Base, No. #53	120	TON	\$30.00	\$3,600.00	\$28.00	\$3,360.00	\$25.00	\$3,000.00	\$24.50	\$2,940.00
45	Orangewood Court	Recycled Concrete Compacted Aggregate for Base, No. #53	120	TON	\$25.00	\$3,000.00	\$24.00	\$2,880.00	\$24.00	\$2,880.00	\$20.00	\$2,400.00
46	Orangewood Court	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	9	TON	\$25.00	\$225.00	\$24.00	\$216.00	\$30.00	\$270.00	\$20.00	\$180.00
47	Orangewood Court	Restoration, Hydroseeding with Hydrosik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$2,400.00	\$2,400.00	\$2,768.30	\$2,768.30	\$2,100.00	\$2,100.00
48	Orangewood Court	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
49	Orangewood Court	1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50
50	Orangewood Court	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
51	Orangewood Court	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
52	Orangewood Court	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
53	Orangewood Court	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$235.00	\$235.00	\$300.00	\$300.00
54	Orangewood Court	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00
55	Orangewood Court	Sedguard Inlet Protection Device	2	EA	\$80.00	\$160.00	\$25.00	\$50.00	\$60.00	\$120.00	\$30.00	\$60.00
56	Orangewood Court	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
57	Orangewood Court	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
58	Orangewood Court	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	100	SYD	\$14.00	\$1,400.00	\$12.50	\$1,250.00	\$22.50	\$2,250.00	\$15.00	\$1,500.00
59	Orangewood Court	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$4,880.00	\$4,880.00	\$1,250.00	\$1,250.00
60	Orangewood Court	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,500.00	\$5,500.00	\$2,500.00	\$2,500.00
61	Lemonwood Court	Removal of Concrete	155	SYD	\$10.00	\$1,550.00	\$10.00	\$1,550.00	\$12.60	\$1,953.00	\$13.50	\$2,092.50
62	Lemonwood Court	Removal of Concrete Pavement	1946	SYD	\$12.00	\$23,352.00	\$10.00	\$19,460.00	\$11.10	\$21,600.60	\$12.50	\$24,325.00
63	Lemonwood Court	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,310.00	\$1,310.00	\$1,050.00	\$1,050.00
64	Lemonwood Court	Tree Removal, Street Trees, (26" - 42"), "Undistributed" include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,600.00	\$5,200.00	\$3,000.00	\$6,000.00	\$1,580.00	\$3,160.00
65	Lemonwood Court	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$10.00	\$50.00	\$20.00	\$100.00	\$15.00	\$75.00
66	Lemonwood Court	Mailbox Remove & Relocate	13	EA	\$120.00	\$1,560.00	\$25.00	\$325.00	\$120.00	\$1,560.00	\$75.00	\$975.00
67	Lemonwood Court	Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	1946	SYD	\$38.00	\$73,948.00	\$29.00	\$56,434.00	\$34.50	\$67,137.00	\$35.00	\$68,110.00
68	Lemonwood Court	Concrete Sidewalk (4')	120	SYD	\$44.00	\$5,280.00	\$39.00	\$4,680.00	\$45.00	\$5,400.00	\$48.50	\$5,820.00
69	Lemonwood Court	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
70	Lemonwood Court	Concrete Pavement for Residential Drive (6")	35	SYD	\$75.00	\$2,625.00	\$52.00	\$1,820.00	\$52.00	\$1,820.00	\$65.00	\$2,275.00
71	Lemonwood Court	Concrete Wingwalk and Ramps (6")	10	SYD	\$150.00	\$1,500.00	\$115.00	\$1,150.00	\$87.00	\$870.00	\$115.00	\$1,150.00
72	Lemonwood Court	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	2	EA	\$225.00	\$450.00	\$225.00	\$450.00	\$175.00	\$350.00	\$200.00	\$400.00
73	Lemonwood Court	Underdrain 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	1155	LFT	\$12.00	\$13,860.00	\$7.50	\$8,662.50	\$8.75	\$10,106.25	\$11.50	\$13,282.50
74	Lemonwood Court	Type "O" Compacted Aggregate for Base, No. #53	283	TON	\$30.00	\$8,490.00	\$28.00	\$7,924.00	\$25.00	\$7,075.00	\$24.50	\$6,933.50

75	Lemonwood Court	Recycled Concrete Compacted Aggregate for Base, No. #53	283	TON	\$25.00	\$7,075.00	\$24.00	\$6,792.00	\$24.00	\$6,792.00	\$20.00	\$5,660.00
76	Lemonwood Court	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	34	TON	\$25.00	\$850.00	\$24.00	\$816.00	\$30.00	\$1,020.00	\$20.00	\$680.00
77	Lemonwood Court	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$2,100.00	\$2,100.00	\$2,790.00	\$2,790.00	\$4,350.00	\$4,350.00
78	Lemonwood Court	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
79	Lemonwood Court	1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50
80	Lemonwood Court	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
81	Lemonwood Court	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
82	Lemonwood Court	Castings Adjusted to Grade	3	EA	\$350.00	\$1,050.00	\$250.00	\$750.00	\$170.00	\$510.00	\$250.00	\$750.00
83	Lemonwood Court	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$235.00	\$235.00	\$300.00	\$300.00
84	Lemonwood Court	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00
85	Lemonwood Court	Sedguard Inlet Protection Device	2	EA	\$80.00	\$160.00	\$25.00	\$50.00	\$60.00	\$120.00	\$30.00	\$60.00
86	Lemonwood Court	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
87	Lemonwood Court	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
88	Lemonwood Court	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	300	SYD	\$14.00	\$4,200.00	\$12.50	\$3,750.00	\$15.25	\$4,575.00	\$15.00	\$4,500.00
89	Lemonwood Court	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$5,080.00	\$5,080.00	\$2,250.00	\$2,250.00
90	Lemonwood Court	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,500.00	\$5,500.00	\$4,850.00	\$4,850.00
91	Line D - Cherry Blossom Lane	Removal of Concrete	312	SYD	\$10.00	\$3,120.00	\$10.00	\$3,120.00	\$11.75	\$3,666.00	\$13.50	\$4,212.00
92	Line D - Cherry Blossom Lane	Removal of Concrete Pavement	4120	SYD	\$12.00	\$49,440.00	\$10.00	\$41,200.00	\$11.20	\$46,144.00	\$12.50	\$51,500.00
93	Line D - Cherry Blossom Lane	Tree Removal, Street Trees, (12" - 24"), "Undistributed" Include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,340.00	\$1,340.00	\$1,050.00	\$1,050.00
94	Line D - Cherry Blossom Lane	Tree Removal, Street Trees, (25" - 42"), "Undistributed" Include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,400.00	\$4,800.00	\$2,745.00	\$5,490.00	\$1,580.00	\$3,160.00
95	Line D - Cherry Blossom Lane	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$10.00	\$50.00	\$20.00	\$100.00	\$15.00	\$75.00
96	Line D - Cherry Blossom Lane	Mailbox Remove & Relocate	14	EA	\$120.00	\$1,680.00	\$25.00	\$350.00	\$120.00	\$1,680.00	\$75.00	\$1,050.00
97	Line D - Cherry Blossom Lane	Cement Concrete Pavement, Plain, 7 inches, (Includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	4120	SYD	\$38.00	\$156,560.00	\$29.00	\$119,480.00	\$34.50	\$142,140.00	\$35.00	\$144,200.00
98	Line D - Cherry Blossom Lane	Concrete Sidewalk (4")	247	SYD	\$44.00	\$10,868.00	\$39.00	\$9,633.00	\$45.00	\$11,115.00	\$48.50	\$11,979.50
99	Line D - Cherry Blossom Lane	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
100	Line D - Cherry Blossom Lane	Concrete Pavement for Residential Drive (6")	45	SYD	\$75.00	\$3,375.00	\$52.00	\$2,340.00	\$52.00	\$2,340.00	\$65.00	\$2,925.00
101	Line D - Cherry Blossom Lane	Concrete Wingwalk and Ramps (6")	20	SYD	\$150.00	\$3,000.00	\$115.00	\$2,300.00	\$87.00	\$1,740.00	\$115.00	\$2,300.00
102	Line D - Cherry Blossom Lane	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetsel, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
103	Line D - Cherry Blossom Lane	Underdrain, 6" Perforated Plastic, Group K Pipe (Inc. #8 Aggregate Backfill)	2630	LFT	\$12.00	\$31,560.00	\$7.50	\$19,725.00	\$8.30	\$21,829.00	\$11.50	\$30,245.00
104	Line D - Cherry Blossom Lane	Type "O" Compacted Aggregate for Base, No. #53	540	TON	\$30.00	\$16,200.00	\$28.00	\$15,120.00	\$25.00	\$13,500.00	\$24.50	\$13,230.00
105	Line D - Cherry Blossom Lane	Recycled Concrete Compacted Aggregate for Base, No. #53	540	TON	\$25.00	\$13,500.00	\$24.00	\$12,960.00	\$24.00	\$12,960.00	\$20.00	\$10,800.00
106	Line D - Cherry Blossom Lane	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	80	TON	\$25.00	\$2,000.00	\$24.00	\$1,920.00	\$30.00	\$2,400.00	\$20.00	\$1,600.00
107	Line D - Cherry Blossom Lane	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$5,700.00	\$5,700.00	\$6,675.00	\$6,675.00	\$8,500.00	\$8,500.00
108	Line D - Cherry Blossom Lane	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
109	Line D - Cherry Blossom Lane	1" Expansion Joint With Thickened Edge	54	LFT	\$12.00	\$648.00	\$12.00	\$648.00	\$8.00	\$432.00	\$7.50	\$405.00
110	Line D - Cherry Blossom Lane	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
111	Line D - Cherry Blossom Lane	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
112	Line D - Cherry Blossom Lane	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
113	Line D - Cherry Blossom Lane	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	2	EA	\$150.00	\$300.00	\$250.00	\$500.00	\$235.00	\$470.00	\$300.00	\$600.00
114	Line D - Cherry Blossom Lane	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00

115	Line D - Cherry Blossom Lane	Sedguard Inlet Protection Device	4	EA	\$80.00	\$320.00	\$25.00	\$100.00	\$60.00	\$240.00	\$30.00	\$120.00
116	Line D - Cherry Blossom Lane	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
117	Line D - Cherry Blossom Lane	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
118	Line D - Cherry Blossom Lane	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	600	SYD	\$14.00	\$8,400.00	\$12.50	\$7,500.00	\$13.95	\$8,370.00	\$15.00	\$9,000.00
119	Line D - Cherry Blossom Lane	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,861.77	\$2,861.77	\$8,080.00	\$8,080.00	\$4,425.00	\$4,425.00
120	Line D - Cherry Blossom Lane	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,800.00	\$5,800.00	\$8,850.00	\$8,850.00
121	Line E - Raintree Road	Removal of Concrete	315	SYD	\$10.00	\$3,150.00	\$10.00	\$3,150.00	\$12.50	\$3,937.50	\$13.50	\$4,252.50
122	Line E - Raintree Road	Removal of Concrete Pavement	3882	SYD	\$12.00	\$46,584.00	\$10.00	\$38,820.00	\$11.15	\$43,284.30	\$12.50	\$48,525.00
123	Line E - Raintree Road	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,280.00	\$1,280.00	\$1,050.00	\$1,050.00
124	Line E - Raintree Road	Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	1	EA	\$2,400.00	\$2,400.00	\$2,600.00	\$2,600.00	\$2,990.00	\$2,990.00	\$1,580.00	\$1,580.00
125	Line E - Raintree Road	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$10.00	\$50.00	\$20.00	\$100.00	\$15.00	\$75.00
126	Line E - Raintree Road	Mailbox Remove & Relocate	13	EA	\$120.00	\$1,560.00	\$25.00	\$325.00	\$120.00	\$1,560.00	\$75.00	\$975.00
127	Line E - Raintree Road	Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	3882	SYD	\$38.00	\$147,516.00	\$29.00	\$112,578.00	\$34.50	\$133,929.00	\$35.00	\$135,870.00
128	Line E - Raintree Road	Concrete Sidewalk (4')	220	SYD	\$44.00	\$9,680.00	\$39.00	\$8,580.00	\$45.00	\$9,900.00	\$48.50	\$10,670.00
129	Line E - Raintree Road	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
130	Line E - Raintree Road	Concrete Pavement for Residential Drive (6')	45	SYD	\$75.00	\$3,375.00	\$52.00	\$2,340.00	\$52.00	\$2,340.00	\$65.00	\$2,925.00
131	Line E - Raintree Road	Concrete Wingwalk and Ramps (6')	50	SYD	\$150.00	\$7,500.00	\$115.00	\$5,750.00	\$87.00	\$4,350.00	\$115.00	\$5,750.00
132	Line E - Raintree Road	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
133	Line E - Raintree Road	Underdrain 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	2525	LFT	\$12.00	\$30,300.00	\$7.50	\$18,937.50	\$8.60	\$21,715.00	\$11.50	\$29,037.50
134	Line E - Raintree Road	Type "O" Compacted Aggregate for Base, No. #53	540	TON	\$30.00	\$16,200.00	\$28.00	\$15,120.00	\$25.00	\$13,500.00	\$24.50	\$13,230.00
135	Line E - Raintree Road	Recycled Concrete Compacted Aggregate for Base, No. #53	540	TON	\$25.00	\$13,500.00	\$24.00	\$12,960.00	\$24.00	\$12,960.00	\$20.00	\$10,800.00
136	Line E - Raintree Road	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete) Restoration, Hydroseding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2' of Top Soil Included	80	TON	\$25.00	\$2,000.00	\$24.00	\$1,920.00	\$30.00	\$2,400.00	\$20.00	\$1,600.00
137	Line E - Raintree Road	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
139	Line E - Raintree Road	1" Expansion Joint With Thickened Edge	54	LFT	\$12.00	\$648.00	\$12.00	\$648.00	\$8.00	\$432.00	\$7.50	\$405.00
140	Line E - Raintree Road	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
141	Line E - Raintree Road	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
142	Line E - Raintree Road	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
143	Line E - Raintree Road	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	4	EA	\$150.00	\$600.00	\$250.00	\$1,000.00	\$235.00	\$940.00	\$300.00	\$1,200.00
144	Line E - Raintree Road	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00
145	Line E - Raintree Road	Sedguard Inlet Protection Device	4	EA	\$80.00	\$320.00	\$25.00	\$100.00	\$60.00	\$240.00	\$30.00	\$120.00
146	Line E - Raintree Road	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
147	Line E - Raintree Road	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
148	Line E - Raintree Road	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	600	SYD	\$14.00	\$8,400.00	\$12.50	\$7,500.00	\$14.00	\$8,400.00	\$15.00	\$9,000.00
149	Line E - Raintree Road	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$6,180.00	\$6,180.00	\$4,575.00	\$4,575.00
150	Line E - Raintree Road	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,750.00	\$5,750.00	\$9,250.00	\$9,250.00
151	Line F - Blueberry Lane	Removal of Concrete	243	SYD	\$10.00	\$2,430.00	\$10.00	\$2,430.00	\$13.30	\$3,231.90	\$13.50	\$3,280.50
152	Line F - Blueberry Lane	Removal of Concrete Pavement	2442	SYD	\$12.00	\$29,304.00	\$10.00	\$24,420.00	\$11.50	\$28,083.00	\$12.50	\$30,525.00
153	Line F - Blueberry Lane	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,190.00	\$1,190.00	\$1,050.00	\$1,050.00
154	Line F - Blueberry Lane	Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	1	EA	\$2,400.00	\$2,400.00	\$2,400.00	\$2,400.00	\$2,620.00	\$2,620.00	\$1,580.00	\$1,580.00

155	Line F - Blueberry Lane	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$25.00	\$125.00	\$20.00	\$100.00	\$15.00	\$75.00
156	Line F - Blueberry Lane	Mailbox Remove & Relocate	33	EA	\$120.00	\$3,960.00	\$25.00	\$825.00	\$120.00	\$3,960.00	\$75.00	\$2,475.00
157	Line F - Blueberry Lane	Cement Concrete Pavement, Plain, 7 inches, (Includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	2442	SYD	\$38.00	\$92,796.00	\$29.00	\$70,818.00	\$34.50	\$84,249.00	\$35.00	\$85,470.00
158	Line F - Blueberry Lane	Concrete Sidewalk (4")	105	SYD	\$44.00	\$4,620.00	\$39.00	\$4,095.00	\$45.00	\$4,725.00	\$48.50	\$5,092.50
159	Line F - Blueberry Lane	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
160	Line F - Blueberry Lane	Concrete Pavement for Residential Drive (6")	100	SYD	\$75.00	\$7,500.00	\$52.00	\$5,200.00	\$52.00	\$5,200.00	\$65.00	\$6,500.00
161	Line F - Blueberry Lane	Concrete Wingwalk and Ramps (6")	40	SYD	\$150.00	\$6,000.00	\$115.00	\$4,600.00	\$87.00	\$3,480.00	\$115.00	\$4,600.00
162	Line F - Blueberry Lane	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
163	Line F - Blueberry Lane	Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	1774	LFT	\$12.00	\$21,288.00	\$7.50	\$13,305.00	\$8.95	\$15,877.30	\$11.50	\$20,401.00
164	Line F - Blueberry Lane	Type "O" Compacted Aggregate for Base, No. #53	354	TON	\$30.00	\$10,620.00	\$28.00	\$9,912.00	\$25.00	\$8,850.00	\$24.50	\$8,673.00
165	Line F - Blueberry Lane	Recycled Concrete Compacted Aggregate for Base, No. #53	354	TON	\$25.00	\$8,850.00	\$24.00	\$8,496.00	\$24.00	\$8,496.00	\$20.00	\$7,080.00
166	Line F - Blueberry Lane	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	60	TON	\$25.00	\$1,500.00	\$24.00	\$1,440.00	\$30.00	\$1,800.00	\$20.00	\$1,200.00
167	Line F - Blueberry Lane	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$7,000.00	\$7,000.00	\$8,000.00	\$8,000.00	\$5,500.00	\$5,500.00
168	Line F - Blueberry Lane	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
169	Line F - Blueberry Lane	1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50
170	Line F - Blueberry Lane	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
171	Line F - Blueberry Lane	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
172	Line F - Blueberry Lane	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
173	Line F - Blueberry Lane	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	3	EA	\$150.00	\$450.00	\$250.00	\$750.00	\$235.00	\$705.00	\$300.00	\$900.00
174	Line F - Blueberry Lane	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00
175	Line F - Blueberry Lane	Sedijguard Inlet Protection Device	3	EA	\$80.00	\$240.00	\$25.00	\$75.00	\$60.00	\$180.00	\$30.00	\$90.00
176	Line F - Blueberry Lane	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
177	Line F - Blueberry Lane	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
178	Line F - Blueberry Lane	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	300	SYD	\$14.00	\$4,200.00	\$12.50	\$3,750.00	\$15.20	\$4,560.00	\$15.00	\$4,500.00
179	Line F - Blueberry Lane	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$4,340.00	\$4,340.00	\$2,980.00	\$2,980.00
180	Line F - Blueberry Lane	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,500.00	\$5,500.00	\$5,750.00	\$5,750.00
181	Strawberry Drive	Removal of Concrete	373	SYD	\$10.00	\$3,730.00	\$10.00	\$3,730.00	\$12.20	\$4,550.60	\$13.50	\$5,035.50
182	Strawberry Drive	Removal of Concrete Pavement	3562	SYD	\$12.00	\$42,744.00	\$10.00	\$35,620.00	\$11.00	\$39,182.00	\$12.50	\$44,525.00
183	Strawberry Drive	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,220.00	\$1,220.00	\$1,050.00	\$1,050.00
184	Strawberry Drive	Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,400.00	\$4,800.00	\$2,685.00	\$5,370.00	\$1,580.00	\$3,160.00
185	Strawberry Drive	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$25.00	\$125.00	\$20.00	\$100.00	\$15.00	\$75.00
186	Strawberry Drive	Mailbox Remove & Relocate	27	EA	\$120.00	\$3,240.00	\$25.00	\$675.00	\$120.00	\$3,240.00	\$75.00	\$2,025.00
187	Strawberry Drive	Cement Concrete Pavement, Plain, 7 inches, (Includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	3562	SYD	\$38.00	\$135,356.00	\$29.00	\$103,298.00	\$34.50	\$122,889.00	\$35.00	\$124,670.00
188	Strawberry Drive	Concrete Sidewalk (4")	230	SYD	\$44.00	\$10,120.00	\$39.00	\$8,970.00	\$45.00	\$10,350.00	\$48.50	\$11,155.00
189	Strawberry Drive	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
190	Strawberry Drive	Concrete Pavement for Residential Drive (6")	83	SYD	\$75.00	\$6,225.00	\$52.00	\$4,316.00	\$52.00	\$4,316.00	\$65.00	\$5,395.00
191	Strawberry Drive	Concrete Wingwalk and Ramps (6")	60	SYD	\$150.00	\$9,000.00	\$115.00	\$6,900.00	\$87.00	\$5,220.00	\$115.00	\$6,900.00
192	Strawberry Drive	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
193	Strawberry Drive	Underdrain 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	2266	LFT	\$12.00	\$27,432.00	\$7.50	\$17,145.00	\$8.00	\$18,288.00	\$11.50	\$26,289.00
194	Strawberry Drive	Type "O" Compacted Aggregate for Base, No. #53	458	TON	\$30.00	\$13,740.00	\$28.00	\$12,824.00	\$25.00	\$11,450.00	\$24.50	\$11,221.00

195	Strawberry Drive	Recycled Concrete Compacted Aggregate for Base, No. #53	458	TON	\$25.00	\$11,450.00	\$24.00	\$10,992.00	\$24.00	\$10,992.00	\$20.00	\$9,160.00
196	Strawberry Drive	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	80	TON	\$25.00	\$2,000.00	\$24.00	\$1,920.00	\$30.00	\$2,400.00	\$20.00	\$1,600.00
197	Strawberry Drive	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$5,000.00	\$5,000.00	\$5,770.00	\$5,770.00	\$8,150.00	\$8,150.00
198	Strawberry Drive	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
199	Strawberry Drive	1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50
200	Strawberry Drive	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
201	Strawberry Drive	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
202	Strawberry Drive	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
203	Strawberry Drive	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	2	EA	\$150.00	\$300.00	\$250.00	\$500.00	\$235.00	\$470.00	\$300.00	\$600.00
204	Strawberry Drive	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$800.00	\$600.00	\$300.00	\$300.00
205	Strawberry Drive	Sedguard Inlet Protection Device	2	EA	\$80.00	\$160.00	\$25.00	\$50.00	\$60.00	\$120.00	\$30.00	\$60.00
206	Strawberry Drive	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
207	Strawberry Drive	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
208	Strawberry Drive	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	800	SYD	\$14.00	\$11,200.00	\$12.50	\$10,000.00	\$13.80	\$11,040.00	\$15.00	\$12,000.00
209	Strawberry Drive	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$5,830.00	\$5,830.00	\$4,000.00	\$4,000.00
210	Strawberry Drive	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,750.00	\$5,750.00	\$8,500.00	\$8,500.00
211	Springbrook Road	Removal of Concrete	275	SYD	\$10.00	\$2,750.00	\$10.00	\$2,750.00	\$13.75	\$3,781.25	\$13.50	\$3,712.50
212	Springbrook Road	Removal of Concrete Pavement	5838	SYD	\$12.00	\$70,056.00	\$10.00	\$58,380.00	\$11.15	\$65,093.70	\$12.50	\$72,975.00
213	Springbrook Road	Tree Removal, Street Trees, (12" - 24"), "Undistributed" Include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,160.00	\$1,160.00	\$1,050.00	\$1,050.00
214	Springbrook Road	Tree Removal, Street Trees, (25" - 42"), "Undistributed" Include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,400.00	\$4,800.00	\$2,560.00	\$5,120.00	\$1,980.00	\$3,160.00
215	Springbrook Road	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$25.00	\$125.00	\$20.00	\$100.00	\$15.00	\$75.00
216	Springbrook Road	Mailbox Remove & Relocate	30	EA	\$120.00	\$3,600.00	\$25.00	\$750.00	\$120.00	\$3,600.00	\$75.00	\$2,250.00
217	Springbrook Road	Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill Behind Curbs)	5838	SYD	\$38.00	\$221,844.00	\$29.00	\$169,302.00	\$34.50	\$201,411.00	\$35.00	\$204,330.00
218	Springbrook Road	Concrete Sidewalk (4")	227	SYD	\$44.00	\$9,988.00	\$39.00	\$8,853.00	\$45.00	\$10,215.00	\$48.50	\$11,009.50
219	Springbrook Road	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
220	Springbrook Road	Concrete Pavement for Residential Drive (6")	25	SYD	\$75.00	\$1,875.00	\$52.00	\$1,300.00	\$56.00	\$1,400.00	\$65.00	\$1,625.00
221	Springbrook Road	Concrete Wingwalk and Ramps (6")	23	SYD	\$150.00	\$3,450.00	\$115.00	\$2,645.00	\$87.00	\$2,001.00	\$115.00	\$2,645.00
222	Springbrook Road	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
223	Springbrook Road	Underdrain, 8" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	2780	LFT	\$12.00	\$33,360.00	\$7.50	\$20,850.00	\$8.15	\$22,657.00	\$11.50	\$31,970.00
224	Springbrook Road	Type "O" Compacted Aggregate for Base, No. #53	745	TON	\$30.00	\$22,350.00	\$28.00	\$20,860.00	\$25.00	\$18,625.00	\$24.50	\$18,252.50
225	Springbrook Road	Recycled Concrete Compacted Aggregate for Base, No. #53	745	TON	\$25.00	\$18,625.00	\$24.00	\$17,880.00	\$24.00	\$17,880.00	\$20.00	\$14,900.00
226	Springbrook Road	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	60	TON	\$25.00	\$1,500.00	\$24.00	\$1,440.00	\$30.36	\$1,821.60	\$20.00	\$1,200.00
227	Springbrook Road	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$8,000.00	\$8,000.00	\$8,900.00	\$8,900.00	\$9,950.00	\$9,950.00
228	Springbrook Road	Bituminous Mixture for Patching (110# / SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
229	Springbrook Road	1" Expansion Joint With Thickened Edge	54	LFT	\$12.00	\$648.00	\$12.00	\$648.00	\$8.00	\$432.00	\$7.50	\$405.00
230	Springbrook Road	Valve Box Adjusted to Grade	3	EA	\$100.00	\$300.00	\$150.00	\$450.00	\$50.00	\$150.00	\$185.00	\$555.00
231	Springbrook Road	Furnish Valve Box and Adjust to Grade	2	EA	\$150.00	\$300.00	\$150.00	\$300.00	\$165.00	\$330.00	\$295.00	\$590.00
232	Springbrook Road	Castings Adjusted to Grade	2	EA	\$350.00	\$700.00	\$150.00	\$300.00	\$170.00	\$340.00	\$250.00	\$500.00
233	Springbrook Road	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	5	EA	\$150.00	\$750.00	\$250.00	\$1,250.00	\$235.00	\$1,175.00	\$300.00	\$1,500.00
234	Springbrook Road	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00

235	Springbrook Road	Sedguard Inlet Protection Device	5	EA	\$80.00	\$400.00	\$25.00	\$125.00	\$60.00	\$300.00	\$30.00	\$150.00
236	Springbrook Road	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
237	Springbrook Road	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
238	Springbrook Road	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	600	SYD	\$14.00	\$8,400.00	\$12.50	\$7,500.00	\$13.85	\$8,310.00	\$15.00	\$9,000.00
239	Springbrook Road	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$7,080.00	\$7,080.00	\$5,500.00	\$5,500.00
240	Springbrook Road	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,500.00	\$5,500.00	\$11,000.00	\$11,000.00
241	Line I - Grapevine Lane	Removal of Concrete	180	SYD	\$10.00	\$1,600.00	\$10.00	\$1,600.00	\$12.95	\$2,072.00	\$13.50	\$2,160.00
242	Line I - Grapevine Lane	Removal of Concrete Pavement	1972	SYD	\$12.00	\$23,664.00	\$10.00	\$19,720.00	\$11.35	\$22,382.20	\$12.50	\$24,650.00
243	Line I - Grapevine Lane	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,130.00	\$1,130.00	\$1,050.00	\$1,050.00
244	Line I - Grapevine Lane	Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	1	EA	\$2,400.00	\$2,400.00	\$2,400.00	\$2,400.00	\$2,325.00	\$2,325.00	\$1,580.00	\$1,580.00
245	Line I - Grapevine Lane	Removal of Concrete Curb "Undistributed"	5	LFT	\$12.00	\$60.00	\$25.00	\$125.00	\$20.00	\$100.00	\$15.00	\$75.00
246	Line I - Grapevine Lane	Mailbox Remove & Relocate	16	EA	\$120.00	\$1,920.00	\$25.00	\$400.00	\$120.00	\$1,920.00	\$75.00	\$1,200.00
247	Line I - Grapevine Lane	Cement Concrete Pavement, Plain, 7 inches, (Includes Type 1-A curb, #4 bar J-bolt, Common Excavation for Base and Backfill Behind Curbs)	1972	SYD	\$38.00	\$74,936.00	\$29.00	\$57,188.00	\$34.50	\$68,034.00	\$35.00	\$69,020.00
248	Line I - Grapevine Lane	Concrete Sidewalk (4')	95	SYD	\$44.00	\$4,180.00	\$39.00	\$3,705.00	\$45.00	\$4,275.00	\$48.50	\$4,607.50
249	Line I - Grapevine Lane	Concrete Curb All Types "Undistributed"	5	LFT	\$30.00	\$150.00	\$25.00	\$125.00	\$15.00	\$75.00	\$35.00	\$175.00
250	Line I - Grapevine Lane	Concrete Pavement for Residential Drive (6')	10	SYD	\$75.00	\$750.00	\$52.00	\$520.00	\$52.00	\$520.00	\$65.00	\$650.00
251	Line I - Grapevine Lane	Concrete Wingwalk and Ramps (6')	55	SYD	\$150.00	\$8,250.00	\$115.00	\$6,325.00	\$87.00	\$4,785.00	\$115.00	\$6,325.00
252	Line I - Grapevine Lane	ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Brick Red	4	EA	\$225.00	\$900.00	\$225.00	\$900.00	\$175.00	\$700.00	\$200.00	\$800.00
253	Line I - Grapevine Lane	Underdrain 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	1260	LFT	\$12.00	\$15,120.00	\$7.50	\$9,450.00	\$8.15	\$10,269.00	\$11.50	\$14,490.00
254	Line I - Grapevine Lane	Type "O" Compacted Aggregate for Base, No. #53	272	TON	\$30.00	\$8,160.00	\$28.00	\$7,616.00	\$25.00	\$6,800.00	\$24.50	\$6,664.00
255	Line I - Grapevine Lane	Recycled Concrete Compacted Aggregate for Base, No. #53	272	TON	\$25.00	\$6,800.00	\$24.00	\$6,528.00	\$24.00	\$6,528.00	\$20.00	\$5,440.00
256	Line I - Grapevine Lane	Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	32	TON	\$25.00	\$800.00	\$24.00	\$768.00	\$30.00	\$960.00	\$20.00	\$640.00
257	Line I - Grapevine Lane	Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2' of Top Soil Included	1	LSUM	\$5,000.00	\$5,000.00	\$4,300.00	\$4,300.00	\$3,895.00	\$3,895.00	\$5,850.00	\$5,850.00
258	Line I - Grapevine Lane	Bituminous Mixture for Patching (110#/SY / IN)	4	TON	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$500.00	\$225.00	\$900.00
259	Line I - Grapevine Lane	1" Expansion Joint With Thickened Edge	27	LFT	\$12.00	\$324.00	\$12.00	\$324.00	\$8.00	\$216.00	\$7.50	\$202.50
260	Line I - Grapevine Lane	Valve Box Adjusted to Grade	2	EA	\$100.00	\$200.00	\$150.00	\$300.00	\$50.00	\$100.00	\$185.00	\$370.00
261	Line I - Grapevine Lane	Furnish Valve Box and Adjust to Grade	1	EA	\$150.00	\$150.00	\$150.00	\$150.00	\$165.00	\$165.00	\$295.00	\$295.00
262	Line I - Grapevine Lane	Castings Adjusted to Grade	1	EA	\$350.00	\$350.00	\$250.00	\$250.00	\$170.00	\$170.00	\$250.00	\$250.00
263	Line I - Grapevine Lane	2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	2	EA	\$150.00	\$300.00	\$250.00	\$500.00	\$235.00	\$470.00	\$300.00	\$600.00
264	Line I - Grapevine Lane	24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	1	EA	\$150.00	\$150.00	\$250.00	\$250.00	\$600.00	\$600.00	\$300.00	\$300.00
265	Line I - Grapevine Lane	Sedguard Inlet Protection Device	2	EA	\$80.00	\$160.00	\$25.00	\$50.00	\$60.00	\$120.00	\$30.00	\$60.00
266	Line I - Grapevine Lane	Standard Barricade, Type III	2	EA	\$150.00	\$300.00	\$125.00	\$250.00	\$180.00	\$360.00	\$100.00	\$200.00
267	Line I - Grapevine Lane	Construction Signs, Type A	1	EA	\$100.00	\$100.00	\$125.00	\$125.00	\$375.00	\$375.00	\$100.00	\$100.00
268	Line I - Grapevine Lane	TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	200	SYD	\$14.00	\$2,800.00	\$12.50	\$2,500.00	\$15.40	\$3,080.00	\$15.00	\$3,000.00
269	Line I - Grapevine Lane	Maintenance of Traffic	1	LSUM	\$10,000.00	\$10,000.00	\$2,500.00	\$2,500.00	\$5,180.00	\$5,180.00	\$3,000.00	\$3,000.00
270	Line I - Grapevine Lane	Mobilization and Demobilization	1	LSUM	\$10,000.00	\$10,000.00	\$6,500.00	\$6,500.00	\$5,850.00	\$5,850.00	\$6,000.00	\$6,000.00
271	Line J - Cranberry Lane	Removal of Concrete	147	SYD	\$10.00	\$1,470.00	\$10.00	\$1,470.00	\$13.45	\$1,977.15	\$13.50	\$1,984.50
272	Line J - Cranberry Lane	Removal of Concrete Pavement	2080	SYD	\$12.00	\$24,960.00	\$10.00	\$20,800.00	\$11.25	\$23,400.00	\$12.50	\$26,000.00
273	Line J - Cranberry Lane	Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	1	EA	\$1,200.00	\$1,200.00	\$1,200.00	\$1,200.00	\$1,130.00	\$1,130.00	\$1,050.00	\$1,050.00
274	Line J - Cranberry Lane	Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	2	EA	\$2,400.00	\$4,800.00	\$2,400.00	\$4,800.00	\$2,440.00	\$4,880.00	\$1,580.00	\$3,160.00



Notice of Award

6/9/2020

Project: Springwood-Orchard Woods Concrete Street Repairs Phase 1

Owner: City of Fort Wayne Board of Works

Resolution/Work Order #0419C

Bidder: Hipskind Concrete

Bidder's Address: 5502 Mason Dr

Fort Wayne, IN 46809

You are notified that your Bid dated 6/4/2020 for the above Contract has been considered. You are the Successful Bidder and are awarded a Contract for Springwood-Orchard Woods Concrete Street Repairs Phase 1

That it is deemed necessary to improve poor condition concrete streets in the Springwood-Orchard Woods neighborhood by removing and replacing concrete pavement, residential drive approaches, sidewalks and update ADA Ramps, improve drainage features, and finalize restoration and seeding.

The Contract Price of your Contract is \$2,057,777.77.

1 copy of the proposed Construction Contract (except Drawings) accompany this Notice of Award.

You must comply with the following conditions precedent within [10] days of the date you receive this Notice of Award.

1. Deliver to the Owner [1] fully executed counterparts of the Construction Contract.
2. Deliver with the executed Agreement the Contract security [Bonds] as specified in the Instructions to Bidders.
 - a. Performance Bond
 - b. Payment Bond
 - c. Certificates of Insurance
3. Deliver evidence of successful Bidder's Affirmative Action Plan; OR, executed City of Fort Wayne Affirmative Action Program document, pursuant to Article 19 of the Instructions to Bidders.
4. Deliver executed Vendor Disclosure Statement (Must have one on file annually with the City of Fort Wayne).
5. Deliver executed E-Verify Affidavit.
6. Deliver executed Drug Policy Acknowledgement Form.



Notice of Award


Failure to comply with these conditions within the time specified will entitle Owner to consider you in default, annul this Notice of Award, and declare your Bid security forfeited. Contractor will be allowed an additional 11 calendar days to submit Bonds.

Within thirty days after you comply with the above conditions, Owner will return to you one fully executed counterpart of the Agreement.

**CITY OF FORT WAYNE
BOARD OF PUBLIC WORKS**



Shan Gunawardena, Chair



Kumar Menon, Member



Mike Avila, Member

ATTEST:


Michelle Fulk-Vondran, Clerk

Date: 6.9.2020

cc: Project Manager

AGREEMENT BETWEEN OWNER AND CONTRACTOR FOR CONSTRUCTION CONTRACT (STIPULATED PRICE)

RESOLUTION/WORK ORDER # **0419C**

This Agreement is by and between **the City of Fort Wayne – Board of Public Works** (“Owner”) and **Hipskind Concrete** (“Contractor”).

Terms used in this Agreement have the meanings stated in the General Conditions and the Supplementary Conditions.

Owner and Contractor hereby agree as follows:

ARTICLE 1—WORK

1.01 Contractor shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows: **That it is deemed necessary to improve poor condition concrete streets in the Springwood-Orchard Woods neighborhood by removing and replacing concrete pavement, residential drive approaches, sidewalks and update ADA Ramps, improve drainage features, and finalize restoration and seeding.**

ARTICLE 2—THE PROJECT

2.01 The Project, of which the Work under the Contract Documents is a part, is generally described as follows: **Springwood-Orchard Woods Concrete Street Repairs Phase 1**

ARTICLE 3—ENGINEER

3.01 The part of the Project that pertains to the Work has been designed by **Public Works Engineering**.

ARTICLE 4—CONTRACT TIMES

4.01 *Time is of the Essence*

A. All time limits for Milestones, if any, Substantial Completion, and completion and readiness for final payment as stated in the Contract Documents are of the essence of the Contract.

4.02 *Contract Times: Dates*

A. The Work will be substantially complete on or before **5/28/2021**, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions on or before **6/30/2021**.

4.03 *Milestones*

A. Parts of the Work must be substantially completed on or before the following Milestone(s):

1. Milestone 1 [N/A]
2. Milestone 2 [N/A]
3. Milestone 3 [N/A]

4.05 *Liquidated Damages*

- A. Contractor and Owner recognize that time is of the essence as stated in Paragraph 4.01 above and that Owner will suffer financial and other losses if the Work is not completed and Milestones not achieved within the Contract Times, as duly modified. The parties also recognize the delays, expense, and difficulties involved in proving, in a legal or arbitration proceeding, the actual loss suffered by Owner if the Work is not completed on time. Accordingly, instead of requiring any such proof, Owner and Contractor agree that as liquidated damages for delay (but not as a penalty):
1. *Substantial Completion:* Contractor shall pay Owner up to \$1000 for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for Substantial Completion, until the Work is substantially complete.
 2. *Completion of Remaining Work:* After Substantial Completion, if Contractor shall neglect, refuse, or fail to complete the remaining Work within the Contract Times (as duly adjusted pursuant to the Contract) for completion and readiness for final payment, Contractor shall pay Owner up to \$1000 for each day that expires after such time until the Work is completed and ready for final payment.
 3. *Milestones:* Contractor shall pay Owner up to \$1000 for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for achievement of Milestone 1, until Milestone 1 is achieved, or until the time specified for Substantial Completion is reached, at which time the rate indicated in Paragraph 4.05.A.1 will apply, rather than the Milestone rate.
 4. Liquidated damages for failing to timely attain Milestones, Substantial Completion, and final completion are not additive, and will not be imposed concurrently.
- B. If Owner recovers liquidated damages for a delay in completion by Contractor, then such liquidated damages are Owner's sole and exclusive remedy for such delay, and Owner is precluded from recovering any other damages, whether actual, direct, excess, or consequential, for such delay, except for special damages (if any) specified in this Agreement.

ARTICLE 5—CONTRACT PRICE

- 5.01 Owner shall pay Contractor for completion of the Work in accordance with the Contract Documents, the amounts that follow, subject to adjustment under the Contract:
- A. For all Work, at the prices stated in Contractor's Bid, attached hereto as an exhibit.
 - B. Total of all unit prices **\$2,057,777.77**.

ARTICLE 6—PAYMENT PROCEDURES

6.01 *Submittal and Processing of Payments*

- A. Contractor shall submit Applications for Payment in accordance with Article 15 of the General Conditions. Applications for Payment will be processed by Engineer as provided in the General Conditions.

6.02 *Progress Payments; Retainage*

- A. Owner shall make progress payments on the basis of Contractor's Applications for Payment no more often than every 30 days during performance of the Work as provided in Paragraph 6.02.A.1 below, provided that

such Applications for Payment have been submitted in a timely manner and otherwise meet the requirements of the Contract. All such payments will be measured by the Schedule of Values established as provided in the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no Schedule of Values, as provided elsewhere in the Contract.

1. Prior to Substantial Completion, progress payments will be made in an amount equal to the percentage indicated below but, in each case, less the aggregate of payments previously made and less such amounts as Owner may withhold, including but not limited to liquidated damages, in accordance with the Contract.
 - a. 95 percent of the value of the Work completed (with the balance being retainage).
 - b. 95 percent of cost of materials and equipment not incorporated in the Work (with the balance being retainage).

6.03 *Final Payment*

- A. Upon final completion and acceptance of the Work, Owner shall pay the remainder of the Contract Price in accordance with Paragraph 15.06 of the General Conditions.

ARTICLE 7—CONTRACT DOCUMENTS

7.01 *Contents*

- A. The Contract Documents consist of all of the following:
 1. This Agreement.
 2. Bonds:
 - a. Performance bond (together with power of attorney).
 - b. Payment bond (together with power of attorney).
 3. General Conditions.
 4. Supplementary Conditions.
 5. Specifications as listed in the table of contents of the project manual (copy of list attached).
 6. Drawings (not attached but incorporated by reference) consisting of 13 sheets with each sheet bearing the following general title: **SPRINGWOOD - ORCHARD WOODS INTERSTATE 69 TO E. COOK ROAD COLDWATER ROAD TO PEARTREE LANE CONCRETE STREET REPAIRS.**
 7. Addenda (numbers [number] to [number], inclusive).
 8. Exhibits to this Agreement (enumerated as follows):
 - a. Drug Policy Acknowledgement Form (Project Bids under \$150,000.00) or Written copy of Contractors Drug Policy (Project Bids over \$150,000.00)
 - b. E-Verify Affidavit

- c. Escrow account agreement
- 9. The following which may be delivered or issued on or after the Effective Date of the Contract and are not attached hereto:
 - a. Notice to Proceed.
 - b. Work Change Directives.
 - c. Change Orders.
 - d. Field Orders.
 - e. Warranty Bond, if any.
- B. The Contract Documents listed in Paragraph 7.01.A are attached to this Agreement (except as expressly noted otherwise above).
- C. There are no Contract Documents other than those listed above in this Article 7.
- D. The Contract Documents may only be amended, modified, or supplemented as provided in the Contract.

ARTICLE 8—REPRESENTATIONS, CERTIFICATIONS, AND STIPULATIONS

8.01 Contractor's Representations

- A. In order to induce Owner to enter into this Contract, Contractor makes the following representations:
 - 1. Contractor has examined and carefully studied the Contract Documents, including Addenda.
 - 2. Contractor has visited the Site, conducted a thorough visual examination of the Site and adjacent areas, and become familiar with the general, local, and Site conditions that may affect cost, progress, and performance of the Work.
 - 3. Contractor is familiar with all Laws and Regulations that may affect cost, progress, and performance of the Work.
 - 4. Contractor has carefully studied the reports of explorations and tests of subsurface conditions at or adjacent to the Site and the drawings of physical conditions relating to existing surface or subsurface structures at the Site that have been identified in the Supplementary Conditions, with respect to the Technical Data in such reports and drawings.
 - 5. Contractor has carefully studied the reports and drawings relating to Hazardous Environmental Conditions, if any, at or adjacent to the Site that have been identified in the Supplementary Conditions, with respect to Technical Data in such reports and drawings.
 - 6. Contractor has considered the information known to Contractor itself; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Contract Documents; and the Technical Data identified in the Supplementary Conditions or by definition, with respect to the effect of such information, observations, and Technical Data on (a) the cost, progress, and performance of the Work; (b) the means, methods, techniques,

sequences, and procedures of construction to be employed by Contractor; and (c) Contractor's safety precautions and programs.

7. Based on the information and observations referred to in the preceding paragraph, Contractor agrees that no further examinations, investigations, explorations, tests, studies, or data are necessary for the performance of the Work at the Contract Price, within the Contract Times, and in accordance with the other terms and conditions of the Contract.
8. Contractor is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Contract Documents.
9. Contractor has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Contractor has discovered in the Contract Documents, and of discrepancies between Site conditions and the Contract Documents, and the written resolution thereof by Engineer is acceptable to Contractor.
10. The Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.
11. Contractor's entry into this Contract constitutes an incontrovertible representation by Contractor that without exception all prices in the Agreement are premised upon performing and furnishing the Work required by the Contract Documents.

8.02 *Contractor's Certifications*

- A. Contractor certifies that it has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for or in executing the Contract. For the purposes of this Paragraph 8.02:
 1. "corrupt practice" means the offering, giving, receiving, or soliciting of anything of value likely to influence the action of a public official in the bidding process or in the Contract execution;
 2. "fraudulent practice" means an intentional misrepresentation of facts made (a) to influence the bidding process or the execution of the Contract to the detriment of Owner, (b) to establish Bid or Contract prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;
 3. "collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish Bid prices at artificial, non-competitive levels; and
 4. "coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the execution of the Contract.

8.03 *Standard General Conditions*

- A. Owner stipulates that if the General Conditions that are made a part of this Contract are EJCDC® C-700, Standard General Conditions for the Construction Contract (2018), published by the Engineers Joint Contract Documents Committee, and if Owner is the party that has furnished said General Conditions, then Owner has plainly shown all modifications to the standard wording of such published document to the

Contractor, through a process such as highlighting or “track changes” (redline/strikeout), or in the Supplementary Conditions.

ACKNOWLEDGMENT

STATE OF INDIANA)
SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named _____ who being by me first duly sworn upon his oath says that he is the _____ of _____ and as such duly authorized to execute the foregoing instrument and acknowledged the same as the voluntary act and deed of _____ for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

ACKNOWLEDGMENT

STATE OF INDIANA)
SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named **Thomas C. Henry, Shan Gunawardena, Kumar Menon, Mike Avila, and Michelle Fulk-Vondran**, by me personally known, who being by me duly sworn said that they are respectively the **Mayor of the City of Fort Wayne**, and **Chairman, Members, and Clerk of the Board of Public Works of the City of Fort Wayne, Indiana**, and that they signed said instrument on behalf of the City of Fort Wayne, Indiana, with full authority so to do and acknowledge said instrument to be in the voluntary act and deed of said **City** for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

IN WITNESS WHEREOF, Owner and Contractor have signed this Agreement (Contract/Resolution Number **0419C**).

This Agreement will be effective on _____ (which is the Effective Date of the Agreement).

CONTRACTOR

OWNER

Hipskind Concrete

CITY OF FORT WAYNE

BY: _____
PRINT NAME _____

BY: _____
THOMAS C. HENRY, MAYOR

TITLE: _____

BOARD OF PUBLIC WORKS

DATE: _____
(Date signed by Contractor)

BY: _____
SHAN GUNAWARDENA, CHAIR

Address for giving notices:

BY: _____
KUMAR MENON, MEMBER

BY: _____
MIKE AVILA, MEMBER

ATTEST: _____
MICHELLE FULK-VONDRAN, CLERK

DATE: _____
(Date signed by Board)

0419C - Springwood-Orchard Woods Concrete Street Repairs Phase 1 (#7073582)

Owner: Public Works
 Solicitor: Public Works
 06/04/2020 02:00 PM EDT

			HIPSKIND CONCRETE CORP			
Section Title	Line Item	Item Description	UoFM	Quantity	Unit Price	Extension
Springwood-Orchard Woods Concrete Street Repairs Phase 1, 0419C						\$1,977,777.77
	1	Line A - Apj Removal of Concrete	SYD	210	\$10.00	\$2,100.00
	2	Line A - Apj Removal of Concrete Pavement	SYD	3289	\$10.00	\$32,890.00
	3	Line A - Apj Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,350.00	\$1,350.00
	4	Line A - Apj Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,400.00	\$4,800.00
	5	Line A - Apj Removal of Concrete Curb "Undistributed"	LFT	5	\$20.00	\$100.00
	6	Line A - Apj Mailbox Remove & Relocate	EA	8	\$25.00	\$200.00
	7	Line A - Apj Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Bar	SYD	3289	\$29.00	\$95,381.00
	8	Line A - Apj Concrete Sidewalk (4")	SYD	138	\$38.00	\$5,244.00
	9	Line A - Apj Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
	10	Line A - Apj Concrete Pavement for Residential Drive (6")	SYD	55	\$52.00	\$2,860.00
	11	Line A - Apj Concrete Wingwalk and Ramps (6")	SYD	35	\$115.00	\$4,025.00
	12	Line A - Apj ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	5	\$225.00	\$1,125.00
	13	Line A - Apj Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	2205	\$7.50	\$16,537.50
	14	Line A - Apj Type "O" Compacted Aggregate for Base, No. #53	TON	440	\$28.00	\$12,320.00
	15	Line A - Apj Recycled Concrete Compacted Aggregate for Base, No. #53	TON	433	\$24.00	\$10,392.00
	16	Line A - Apj Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	46	\$24.00	\$1,104.00
	17	Line A - Apj Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$5,700.00	\$5,700.00
	18	Line A - Apj Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
	19	Line A - Apj 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
	20	Line A - Apj Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
	21	Line A - Apj Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
	22	Line A - Apj Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
	23	Line A - Apj 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	3	\$250.00	\$750.00
	24	Line A - Apj 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
	25	Line A - Apj Sediguard Inlet Protection Device	EA	4	\$25.00	\$100.00
	26	Line A - Apj Standard Barricade, Type III	EA	2	\$125.00	\$250.00
	27	Line A - Apj Construction Signs, Type A	EA	1	\$125.00	\$125.00
	28	Line A - Apj TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	600	\$12.50	\$7,500.00
	29	Line A - Apj Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
	30	Line A - Apj Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
	31	Line B - Orz Removal of Concrete	SYD	40	\$10.00	\$400.00
	32	Line B - Orz Removal of Concrete Pavement	SYD	839	\$10.00	\$8,390.00
	33	Line B - Orz Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,500.00	\$1,500.00
	34	Line B - Orz Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	1	\$2,500.00	\$2,500.00
	35	Line B - Orz Removal of Concrete Curb "Undistributed"	LFT	5	\$10.00	\$50.00
	36	Line B - Orz Mailbox Remove & Relocate	EA	7	\$25.00	\$175.00
	37	Line B - Orz Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Bar	SYD	839	\$29.00	\$24,331.00
	38	Line B - Orz Concrete Sidewalk (4")	SYD	18	\$38.00	\$684.00
	39	Line B - Orz Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00

40	Line B - Orz Concrete Pavement for Residential Drive (6")	SYD	22	\$52.00	\$1,144.00
41	Line B - Orz Concrete Wingwalk and Ramps (6")	SYD	11	\$115.00	\$1,265.00
42	Line B - Orz ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	2	\$225.00	\$450.00
43	Line B - Orz Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	465	\$7.50	\$3,487.50
44	Line B - Orz Type "O" Compacted Aggregate for Base, No. #53	TON	120	\$28.00	\$3,360.00
45	Line B - Orz Recycled Concrete Compacted Aggregate for Base, No. #53	TON	120	\$24.00	\$2,880.00
46	Line B - Orz Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	9	\$24.00	\$216.00
47	Line B - Orz Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$2,400.00	\$2,400.00
48	Line B - Orz Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
49	Line B - Orz 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
50	Line B - Orz Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
51	Line B - Orz Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
52	Line B - Orz Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
53	Line B - Orz 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
54	Line B - Orz 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
55	Line B - Orz Sediguard Inlet Protection Device	EA	2	\$25.00	\$50.00
56	Line B - Orz Standard Barricade, Type III	EA	2	\$125.00	\$250.00
57	Line B - Orz Construction Signs, Type A	EA	1	\$125.00	\$125.00
58	Line B - Orz TX-160 Geogrid (if-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	100	\$12.50	\$1,250.00
59	Line B - Orz Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
60	Line B - Orz Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
61	Line C - Ler Removal of Concrete	SYD	155	\$10.00	\$1,550.00
62	Line C - Ler Removal of Concrete Pavement	SYD	1946	\$10.00	\$19,460.00
63	Line C - Ler Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
64	Line C - Ler Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,600.00	\$5,200.00
65	Line C - Ler Removal of Concrete Curb "Undistributed"	LFT	5	\$10.00	\$50.00
66	Line C - Ler Mailbox Remove & Relocate	EA	13	\$25.00	\$325.00
67	Line C - Ler Cement Concrete Pavement, Plain, 7 inches, (Includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Bar	SYD	1946	\$29.00	\$56,434.00
68	Line C - Ler Concrete Sidewalk (4")	SYD	120	\$39.00	\$4,680.00
69	Line C - Ler Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
70	Line C - Ler Concrete Pavement for Residential Drive (6")	SYD	35	\$52.00	\$1,820.00
71	Line C - Ler Concrete Wingwalk and Ramps (6")	SYD	10	\$1,153.00	\$11,530.00
72	Line C - Ler ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	2	\$225.00	\$450.00
73	Line C - Ler Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	1155	\$7.50	\$8,662.50
74	Line C - Ler Type "O" Compacted Aggregate for Base, No. #53	TON	283	\$28.00	\$7,924.00
75	Line C - Ler Recycled Concrete Compacted Aggregate for Base, No. #53	TON	283	\$24.00	\$6,792.00
76	Line C - Ler Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	34	\$24.00	\$816.00
77	Line C - Ler Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$2,100.00	\$2,100.00
78	Line C - Ler Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
79	Line C - Ler 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
80	Line C - Ler Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
81	Line C - Ler Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
82	Line C - Ler Castings Adjusted to Grade	EA	3	\$250.00	\$750.00
83	Line C - Ler 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
84	Line C - Ler 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
85	Line C - Ler Sediguard Inlet Protection Device	EA	2	\$25.00	\$50.00
86	Line C - Ler Standard Barricade, Type III	EA	2	\$125.00	\$250.00

87	Line C - Ler Construction Signs, Type A	EA	1	\$125.00	\$125.00
88	Line C - Ler TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	300	\$12.50	\$3,750.00
89	Line C - Ler Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
90	Line C - Ler Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
91	Line D - Ch Removal of Concrete	SYD	312	\$10.00	\$3,120.00
92	Line D - Ch Removal of Concrete Pavement	SYD	4120	\$10.00	\$41,200.00
93	Line D - Ch Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
94	Line D - Ch Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,400.00	\$4,800.00
95	Line D - Ch Removal of Concrete Curb "Undistributed"	LFT	5	\$10.00	\$50.00
96	Line D - Ch Mailbox Remove & Relocate	EA	14	\$25.00	\$350.00
97	Line D - Ch Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Base	SYD	4120	\$29.00	\$119,480.00
98	Line D - Ch Concrete Sidewalk (4")	SYD	247	\$39.00	\$9,633.00
99	Line D - Ch Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
100	Line D - Ch Concrete Pavement for Residential Drive (6")	SYD	45	\$52.00	\$2,340.00
101	Line D - Ch Concrete Wingwalk and Ramps (6")	SYD	20	\$115.00	\$2,300.00
102	Line D - Ch ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
103	Line D - Ch Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	2630	\$7.50	\$19,725.00
104	Line D - Ch Type "O" Compacted Aggregate for Base, No. #53	TON	540	\$28.00	\$15,120.00
105	Line D - Ch Recycled Concrete Compacted Aggregate for Base, No. #53	TON	540	\$24.00	\$12,960.00
106	Line D - Ch Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	80	\$24.00	\$1,920.00
107	Line D - Ch Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$5,700.00	\$5,700.00
108	Line D - Ch Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
109	Line D - Ch 1" Expansion Joint With Thickened Edge	LFT	54	\$12.00	\$648.00
110	Line D - Ch Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
111	Line D - Ch Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
112	Line D - Ch Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
113	Line D - Ch 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	2	\$250.00	\$500.00
114	Line D - Ch 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
115	Line D - Ch Sediguard Inlet Protection Device	EA	4	\$25.00	\$100.00
116	Line D - Ch Standard Barricade, Type III	EA	2	\$125.00	\$250.00
117	Line D - Ch Construction Signs, Type A	EA	1	\$125.00	\$125.00
118	Line D - Ch TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	600	\$12.50	\$7,500.00
119	Line D - Ch Maintenance of Traffic	LSUM	1	\$2,861.77	\$2,861.77
120	Line D - Ch Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
121	Line E - Rai Removal of Concrete	SYD	315	\$10.00	\$3,150.00
122	Line E - Rai Removal of Concrete Pavement	SYD	3882	\$10.00	\$38,820.00
123	Line E - Rai Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
124	Line E - Rai Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	1	\$2,600.00	\$2,600.00
125	Line E - Rai Removal of Concrete Curb "Undistributed"	LFT	5	\$10.00	\$50.00
126	Line E - Rai Mailbox Remove & Relocate	EA	13	\$25.00	\$325.00
127	Line E - Rai Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Base	SYD	3882	\$29.00	\$112,578.00
128	Line E - Rai Concrete Sidewalk (4")	SYD	220	\$39.00	\$8,580.00
129	Line E - Rai Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
130	Line E - Rai Concrete Pavement for Residential Drive (6")	SYD	45	\$52.00	\$2,340.00
131	Line E - Rai Concrete Wingwalk and Ramps (6")	SYD	50	\$115.00	\$5,750.00
132	Line E - Rai ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
133	Line E - Rai Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	2525	\$7.50	\$18,937.50

134	Line E - Rai Type "O" Compacted Aggregate for Base, No. #53	TON	540	\$28.00	\$15,120.00
135	Line E - Rai Recycled Concrete Compacted Aggregate for Base, No. #53	TON	540	\$24.00	\$12,960.00
136	Line E - Rai Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	80	\$24.00	\$1,920.00
137	Line E - Rai Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$5,250.00	\$5,250.00
138	Line E - Rai Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
139	Line E - Rai 1" Expansion Joint With Thickened Edge	LFT	54	\$12.00	\$648.00
140	Line E - Rai Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
141	Line E - Rai Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
142	Line E - Rai Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
143	Line E - Rai 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	4	\$250.00	\$1,000.00
144	Line E - Rai 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
145	Line E - Rai Sediguard Inlet Protection Device	EA	4	\$25.00	\$100.00
146	Line E - Rai Standard Barricade, Type III	EA	2	\$125.00	\$250.00
147	Line E - Rai Construction Signs, Type A	EA	1	\$125.00	\$125.00
148	Line E - Rai TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	600	\$12.50	\$7,500.00
149	Line E - Rai Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
150	Line E - Rai Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
151	Line F - Blu Removal of Concrete	SYD	243	\$10.00	\$2,430.00
152	Line F - Blu Removal of Concrete Pavement	SYD	2442	\$10.00	\$24,420.00
153	Line F - Blu Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
154	Line F - Blu Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	1	\$2,400.00	\$2,400.00
155	Line F - Blu Removal of Concrete Curb "Undistributed"	LFT	5	\$25.00	\$125.00
156	Line F - Blu Mailbox Remove & Relocate	EA	33	\$25.00	\$825.00
157	Line F - Blu Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill)	SYD	2442	\$29.00	\$70,818.00
158	Line F - Blu Concrete Sidewalk (4")	SYD	105	\$39.00	\$4,095.00
159	Line F - Blu Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
160	Line F - Blu Concrete Pavement for Residential Drive (6")	SYD	100	\$52.00	\$5,200.00
161	Line F - Blu Concrete Wingwalk and Ramps (6")	SYD	40	\$115.00	\$4,600.00
162	Line F - Blu ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetsset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
163	Line F - Blu Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	1774	\$7.50	\$13,305.00
164	Line F - Blu Type "O" Compacted Aggregate for Base, No. #53	TON	354	\$28.00	\$9,912.00
165	Line F - Blu Recycled Concrete Compacted Aggregate for Base, No. #53	TON	354	\$24.00	\$8,496.00
166	Line F - Blu Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	60	\$24.00	\$1,440.00
167	Line F - Blu Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$7,000.00	\$7,000.00
168	Line F - Blu Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
169	Line F - Blu 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
170	Line F - Blu Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
171	Line F - Blu Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
172	Line F - Blu Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
173	Line F - Blu 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	3	\$250.00	\$750.00
174	Line F - Blu 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
175	Line F - Blu Sediguard Inlet Protection Device	EA	3	\$25.00	\$75.00
176	Line F - Blu Standard Barricade, Type III	EA	2	\$125.00	\$250.00
177	Line F - Blu Construction Signs, Type A	EA	1	\$125.00	\$125.00
178	Line F - Blu TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	300	\$12.50	\$3,750.00
179	Line F - Blu Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
180	Line F - Blu Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00

181	Line G - Str Removal of Concrete	SYD	373	\$10.00	\$3,730.00
182	Line G - Str Removal of Concrete Pavement	SYD	3562	\$10.00	\$35,620.00
183	Line G - Str Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
184	Line G - Str Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,400.00	\$4,800.00
185	Line G - Str Removal of Concrete Curb "Undistributed"	LFT	5	\$25.00	\$125.00
186	Line G - Str Mailbox Remove & Relocate	EA	27	\$25.00	\$675.00
187	Line G - Str Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Bar	SYD	3562	\$29.00	\$103,298.00
188	Line G - Str Concrete Sidewalk (4")	SYD	230	\$39.00	\$8,970.00
189	Line G - Str Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
190	Line G - Str Concrete Pavement for Residential Drive (6")	SYD	83	\$52.00	\$4,316.00
191	Line G - Str Concrete Wingwalk and Ramps (6")	SYD	60	\$115.00	\$6,900.00
192	Line G - Str ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
193	Line G - Str Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	2286	\$7.50	\$17,145.00
194	Line G - Str Type "O" Compacted Aggregate for Base, No. #53	TON	458	\$28.00	\$12,824.00
195	Line G - Str Recycled Concrete Compacted Aggregate for Base, No. #53	TON	458	\$24.00	\$10,992.00
196	Line G - Str Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	80	\$24.00	\$1,920.00
197	Line G - Str Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$5,000.00	\$5,000.00
198	Line G - Str Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
199	Line G - Str 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
200	Line G - Str Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
201	Line G - Str Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
202	Line G - Str Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
203	Line G - Str 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	2	\$250.00	\$500.00
204	Line G - Str 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
205	Line G - Str Sediguard Inlet Protection Device	EA	2	\$25.00	\$50.00
206	Line G - Str Standard Barricade, Type III	EA	2	\$125.00	\$250.00
207	Line G - Str Construction Signs, Type A	EA	1	\$125.00	\$125.00
208	Line G - Str TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	800	\$12.50	\$10,000.00
209	Line G - Str Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
210	Line G - Str Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
211	Line H - Spr Removal of Concrete	SYD	275	\$10.00	\$2,750.00
212	Line H - Spr Removal of Concrete Pavement	SYD	5838	\$10.00	\$58,380.00
213	Line H - Spr Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
214	Line H - Spr Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,400.00	\$4,800.00
215	Line H - Spr Removal of Concrete Curb "Undistributed"	LFT	5	\$25.00	\$125.00
216	Line H - Spr Mailbox Remove & Relocate	EA	30	\$25.00	\$750.00
217	Line H - Spr Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Bar	SYD	5838	\$29.00	\$169,302.00
218	Line H - Spr Concrete Sidewalk (4")	SYD	227	\$39.00	\$8,853.00
219	Line H - Spr Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
220	Line H - Spr Concrete Pavement for Residential Drive (6")	SYD	25	\$52.00	\$1,300.00
221	Line H - Spr Concrete Wingwalk and Ramps (6")	SYD	23	\$115.00	\$2,645.00
222	Line H - Spr ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
223	Line H - Spr Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	2780	\$7.50	\$20,850.00
224	Line H - Spr Type "O" Compacted Aggregate for Base, No. #53	TON	745	\$28.00	\$20,860.00
225	Line H - Spr Recycled Concrete Compacted Aggregate for Base, No. #53	TON	745	\$24.00	\$17,880.00
226	Line H - Spr Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	60	\$24.00	\$1,440.00
227	Line H - Spr Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$8,000.00	\$8,000.00

228	Line H - Spr Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
229	Line H - Spr 1" Expansion Joint With Thickened Edge	LFT	54	\$12.00	\$648.00
230	Line H - Spr Valve Box Adjusted to Grade	EA	3	\$150.00	\$450.00
231	Line H - Spr Furnish Valve Box and Adjust to Grade	EA	2	\$150.00	\$300.00
232	Line H - Spr Castings Adjusted to Grade	EA	2	\$150.00	\$300.00
233	Line H - Spr 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	5	\$250.00	\$1,250.00
234	Line H - Spr 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
235	Line H - Spr Sediguard Inlet Protection Device	EA	5	\$25.00	\$125.00
236	Line H - Spr Standard Barricade, Type III	EA	2	\$125.00	\$250.00
237	Line H - Spr Construction Signs, Type A	EA	1	\$125.00	\$125.00
238	Line H - Spr TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	600	\$12.50	\$7,500.00
239	Line H - Spr Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
240	Line H - Spr Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
241	Line I - Cra Removal of Concrete	SYD	160	\$10.00	\$1,600.00
242	Line I - Cra Removal of Concrete Pavement	SYD	1972	\$10.00	\$19,720.00
243	Line I - Cra Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
244	Line I - Cra Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	1	\$2,400.00	\$2,400.00
245	Line I - Cra Removal of Concrete Curb "Undistributed"	LFT	5	\$25.00	\$125.00
246	Line I - Cra Mailbox Remove & Relocate	EA	16	\$25.00	\$400.00
247	Line I - Cra Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Backfill)	SYD	1972	\$29.00	\$57,188.00
248	Line I - Cra Concrete Sidewalk (4")	SYD	95	\$39.00	\$3,705.00
249	Line I - Cra Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
250	Line I - Cra Concrete Pavement for Residential Drive (6")	SYD	10	\$52.00	\$520.00
251	Line I - Cra Concrete Wingwalk and Ramps (6")	SYD	55	\$115.00	\$6,325.00
252	Line I - Cra ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	4	\$225.00	\$900.00
253	Line I - Cra Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	1260	\$7.50	\$9,450.00
254	Line I - Cra Type "O" Compacted Aggregate for Base, No. #53	TON	272	\$28.00	\$7,616.00
255	Line I - Cra Recycled Concrete Compacted Aggregate for Base, No. #53	TON	272	\$24.00	\$6,528.00
256	Line I - Cra Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	32	\$24.00	\$768.00
257	Line I - Cra Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$4,300.00	\$4,300.00
258	Line I - Cra Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
259	Line I - Cra 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
260	Line I - Cra Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
261	Line I - Cra Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
262	Line I - Cra Castings Adjusted to Grade	EA	1	\$250.00	\$250.00
263	Line I - Cra 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	2	\$250.00	\$500.00
264	Line I - Cra 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
265	Line I - Cra Sediguard Inlet Protection Device	EA	2	\$25.00	\$50.00
266	Line I - Cra Standard Barricade, Type III	EA	2	\$125.00	\$250.00
267	Line I - Cra Construction Signs, Type A	EA	1	\$125.00	\$125.00
268	Line I - Cra TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	200	\$12.50	\$2,500.00
269	Line I - Cra Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
270	Line I - Cra Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
271	Line J - Cra Removal of Concrete	SYD	147	\$10.00	\$1,470.00
272	Line J - Cra Removal of Concrete Pavement	SYD	2080	\$10.00	\$20,800.00
273	Line J - Cra Tree Removal, Street Trees, (12" - 24"), "Undistributed" include stumping	EA	1	\$1,200.00	\$1,200.00
274	Line J - Cra Tree Removal, Street Trees, (25" - 42"), "Undistributed" include stumping	EA	2	\$2,400.00	\$4,800.00

275	Line J - Crai Removal of Concrete Curb "Undistributed"	LFT	5	\$25.00	\$125.00
276	Line J - Crai Mailbox Remove & Relocate	EA	4	\$25.00	\$100.00
277	Line J - Crai Cement Concrete Pavement, Plain, 7 inches, (includes Type 1-A curb, #4 bar/ J-bolt, Common Excavation for Base and Base	SYD	2080	\$29.00	\$60,320.00
278	Line J - Crai Concrete Sidewalk (4")	SYD	100	\$39.00	\$3,900.00
279	Line J - Crai Concrete Curb All Types "Undistributed"	LFT	5	\$25.00	\$125.00
280	Line J - Crai Concrete Pavement for Residential Drive (6")	SYD	30	\$52.00	\$1,560.00
281	Line J - Crai Concrete Wingwalk and Ramps (6")	SYD	17	\$115.00	\$1,955.00
282	Line J - Crai ADA Solutions, Armor-Tile, or Approved Equal "Replaceable" 2' x 4' Composite, Wetset, Tactile Warning Surface Unit - Br	EA	2	\$225.00	\$450.00
283	Line J - Crai Underdrain, 6" Perforated Plastic, Group K Pipe (inc. #8 Aggregate Backfill)	LFT	1628	\$7.50	\$12,210.00
284	Line J - Crai Type "O" Compacted Aggregate for Base, No. #53	TON	275	\$28.00	\$7,700.00
285	Line J - Crai Recycled Concrete Compacted Aggregate for Base, No. #53	TON	275	\$24.00	\$6,600.00
286	Line J - Crai Bed Course Material, For Sidewalks, Bus Pads (Can use recycled concrete)	TON	30	\$24.00	\$720.00
287	Line J - Crai Restoration, Hydroseeding with Hydrostik or Equivalent Polymer for Erosion and Sediment Control - Straw Covering, 2" o	LSUM	1	\$4,750.00	\$4,750.00
288	Line J - Crai Bituminous Mixture for Patching (110# / SY / IN)	TON	4	\$250.00	\$1,000.00
289	Line J - Crai 1" Expansion Joint With Thickened Edge	LFT	27	\$12.00	\$324.00
290	Line J - Crai Valve Box Adjusted to Grade	EA	2	\$150.00	\$300.00
291	Line J - Crai Furnish Valve Box and Adjust to Grade	EA	1	\$150.00	\$150.00
292	Line J - Crai Castings Adjusted to Grade	EA	1	\$150.00	\$150.00
293	Line J - Crai 2' x 2' Curb and Gutter Casting, Pick up at WPCM Yard & Adjust to Grade	EA	4	\$250.00	\$1,000.00
294	Line J - Crai 24" Sanitary Casting, Pick up at WPCM Yard & Adjust to Grade	EA	1	\$250.00	\$250.00
295	Line J - Crai Sediguard Inlet Protection Device	EA	4	\$25.00	\$100.00
296	Line J - Crai Standard Barricade, Type III	EA	2	\$125.00	\$250.00
297	Line J - Crai Construction Signs, Type A	EA	1	\$125.00	\$125.00
298	Line J - Crai TX-160 Geogrid (If-Ordered, "Undistributed", Including Excavation, Aggregate)	SYD	200	\$12.50	\$2,500.00
299	Line J - Crai Maintenance of Traffic	LSUM	1	\$2,500.00	\$2,500.00
300	Line J - Crai Mobilization and Demobilization	LSUM	1	\$6,500.00	\$6,500.00
Allowance					\$80,000.00
	301 Line A - Lin Work Allowance	LSUM	1	\$80,000.00	\$80,000.00
Base Bid Total:					\$2,057,777.77

CITY OF FORT WAYNE, INDIANA

Hipskind Concrete Corporation
(Vendor Name)

VENDOR DISCLOSURE STATEMENT RELATING TO:

1. **FINANCIAL INTERESTS;**
2. **POTENTIAL CONFLICTS OF INTEREST;**
3. **CURRENT AND PENDING CONTRACTS OR PROCUREMENTS**

Vendors desiring to enter into certain contracts with the City of Fort Wayne, Indiana (the "City") shall disclose their financial interests, potential conflicts of interest and current and pending contract or procurement information as set forth below.

The following disclosures by Vendors are required for all contracts with annual payments by the City in the amount of \$50,000 or more. Vendors shall disclose their financial interests, potential conflicts of interest and other contract and procurement information identified in Sections 1, 2 and 3 below as a prerequisite for consideration for a contract awarded by the City. This Disclosure Statement must be completed and submitted together with the Vendor's contract, bid, proposal or offer.

A publicly traded entity may submit its current 10K disclosure filing in satisfaction of the disclosure requirements set forth in Sections 1 and 2 below.

Section 1: Disclosure of Financial Interest in Vendor

a. If any individuals have either of the following financial interests in Vendor (or its parent), please check all that apply and provide their names and addresses (attach additional pages as necessary):

- (i) Equity ownership exceeding 5%
- (ii) Distributable income share exceeding 5%
- (iii) Not Applicable (If N/A, go to Section 2)

Name: Casey Hipskind 3308 Copper Hill Run, Ft Wayne, 46804 Name: Gary Hipskind
~~Jay Hipskind 8007 Winchester Rd. Ft Wayne, 46819~~

Address: _____ Address: 5514 Mason Dr.
Ft. Wayne,
46809

b. For each individual listed in Section 1a. show his/her type of equity ownership:

sole proprietorship stock
partnership interest units (LLC)
other (explain) _____

c. For each individual listed in Section 1a. show the percentage of ownership interest in Vendor (or its parent):

Name:	<u>Casey Hipskind</u>	<u>33.3</u>	%
	<u>Gary Hipskind</u>	<u>33.3</u>	
	<u>Jay Hipskind</u>	<u>33.3</u>	
Name:	_____	_____	%

Section 2: Disclosure of Potential Conflicts of Interest (not applicable for vendors who file a 10K)

For each individual listed in Section 1a. check "Yes" or "No" to indicate which, if any, of the following potential conflict of interest relationships apply. If "Yes", please describe using space under applicable subsection (attach additional pages as necessary):

- a. City employment, currently or in the previous 3 years, including contractual employment for services:
Yes _____ No X

- b. City employment of "Member of Immediate Family" (defined herein as: Spouse, Child, Step Child, Parent or Step Parent, Father-in-law or Mother-in-law, Brother or Sister, Step Brother or Step Sister, Half Brother or Half Sister, Brother-in-law or Sister-in-law, Son-in-law or Daughter-in-law, Grandparent or Step Grandparent, Grandparent or Step Grandparent of Spouse, Grandchild)
Including contractual employment for services in the previous 3 years:
Yes X No _____

Mother in law of Casey Hipskind works for Street Dept.

- c. Relationship to Member of Immediate Family holding elective City office currently or in the previous 3 years: Yes _____ No X

Section 3: DISCLOSURE OF OTHER CONTRACT AND PROCUREMENT RELATED INFORMATION

- a. Does Vendor have current contracts (including leases) with the City? Yes X No _____

If "Yes", identify each current contract with descriptive information including purchase order or contract reference number, contract date and City contact below (attach additional pages as necessary).

0354C Woodhurst Addition Concrete Street Repairs

- b. Does Vendor have pending contracts (including leases), bids, proposals, or other pending procurement relationship with the City? Yes _____ No X

If "Yes", identify each pending matter with descriptive information including bid or project number, contract date and City contact using space below (attach additional pages as necessary).

c. Does vendor have any existing employees that are also employed by the City of Fort Wayne?

Yes _____ No X

If "Yes", provide the employee's name, current position held at vendor, and employment payment terms (hourly, salaried, commissioned, etc.).

Name / Position / Payment Terms:

Name / Position / Payment Terms:

Name / Position / Payment Terms:

d. Does vendor's representative, agent, broker, dealer or distributor (if applicable) have any existing employees that are also employed by the City of Fort Wayne? For each instance, please provide the name of the representative, agent, broker, dealer or distributor; the name of the City employee, and the payment terms (hourly, salaried, commissioned, etc.).

Company / Name / Payment Terms: _____

Company / Name / Payment Terms: _____

Section 4: CERTIFICATION OF DISCLOSURES

In connection with the disclosures contained in Sections 1, 2 and 3 Vendor hereby certifies that, except as described in attached Schedule A:

- a. Vendor (or its parent) has not, within the five (5) year period preceding the date of this Disclosure Statement, been debarred, suspended, proposed for debarment declared ineligible or voluntarily excluded from any transactions by any federal, state or local unit of government;
- b. No officer or director of Vendor (or its parent) or individual listed in Section 1a. is presently indicted for or otherwise criminally or civilly charged by a governmental entity (federal, state or local) with commission of any offense;
- c. Vendor (or its parent) has not, within the five (5) year period preceding the date of this Disclosure Statement, had one or more public transactions (federal, state or local) terminated for cause or default;
- d. No officer or director of Vendor (or its parent) or individual listed in Section 1a. has, within the five (5) year period preceding the date of this Disclosure Statement, been convicted, adjudged guilty, or found liable in any criminal or civil action instituted by the City, the federal or state government or any other unit of local government; and
- e. Neither Vendor, nor its parent, nor any affiliated entity of Vendor, or any of their respective officers, directors, or individuals listed in Section 1a. is barred from contracting with any unit of any federal, state or local government as a result of engaging in or being convicted of: (i) bid-rigging; (ii) bid-rotating; or (iii) any similar federal or state offense that contains the same


elements as the offense of bid-rigging or bid-rotating

- f. Pursuant to IC 5-22-16.5, Vendor hereby certifies they do NOT provide \$20 million dollars or more in goods or services to the energy sector of Iran. Vendor also certifies it is not a financial institution that extends \$20 million dollars or more in credit that will provide goods or services to the energy sector of Iran or extends \$20 million dollars or more in credit to a person identified on the list as a person engaging in investment activities in Iran.

The disclosures contained Sections 1, 2 and 3 and the foregoing Certifications are submitted by

<u>Hipskind Concrete Corporation</u> (Name of Vendor)	<u>5502 Mason Dr. Ft. Wayne IN, 46809</u> Address <u>(260)747-1340</u> Telephone <u>Hipskindconstruction@gmail.com</u> E-Mail Address
--	--

The individual authorized to sign on behalf of Vendor represents that he/she: (a) is fully informed regarding the matters pertaining to Vendor and its business; (b) has adequate knowledge to make the above representations and disclosures concerning Vendor; and (c) certifies that the foregoing representations and disclosures are true and accurate to the best of his/her knowledge and belief.

Name (Printed) <u>Casey Hipskind</u>	Title <u>President</u>
Signature <u></u>	Date <u>3/13/2020</u>

NOTE: FAILURE TO COMPLETE AND RETURN THIS FORM WITH YOUR DOCUMENTATION MAY RESULT IN YOUR CONTRACT, OFFER, BID OR PROPOSAL BEING DISQUALIFIED FROM CONSIDERATION.



FW PUBLIC WORKS

Board of Public Works

In Your Neighborhood

COMMON COUNCIL DIGEST SHEET – SUPPLEMENTAL

Springwood-Orchard Woods Concrete Street Repairs, Phase 1

Action Requested:

Requesting an Ordinance approving the **Springwood-orchard Woods Concrete Street Repairs, Phase 1** project pursuant to the Board of Public Works Resolution #0419C and an award to **Hipskind Concrete** in the amount of **\$2,057,777.77**.

Note: Hipskind Concrete was the lowest, most responsive bidder among 3 bidders.

Description and Scope of the Work:

That it is deemed necessary to improve poor condition concrete streets in the Springwood-Orchard Woods neighborhood by removing and replacing concrete pavement, residential drive approaches, sidewalks and update ADA Ramps, improve drainage features, and finalize restoration and seeding.

COUNCIL DIGEST SHEET

Enclosed with this introduction form is a tab sheet and related material from the vendor(s) who submitted bid(s). Purchasing Department is providing this information to Council as an overview of this award.

Springwood-Orchard Woods Concrete Street Repairs, Phase 1

RFPs & BIDS

Bid/RFP #	0419C
Awarded To	Hipskind Concrete
Amount	\$2,057,777.77
Conflict of interest on file?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Number of Registrants	6
Number of Bidders	3
Required Attachments	Bid Tabulation, Signed Award, Proposed Contract, Vendor Disclosure, Council Digest Supplemental

EXTENSIONS

Date Last Bid Out	N/A
# Extensions Granted To Date	N/A

SPECIAL PROCUREMENT

Contract #/ID <i>(State, Federal, Piggyback--Authority)</i>	0419C
Sole Source/Compatibility Justification	N/A

BID CRITERIA *(Take Buy Indiana requirements into consideration.)*

Most Responsible, Responsive Lowest	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>If no, explain below</i>
If not lowest, explain	N/A

COUNCIL DIGEST SHEET

COST COMPARISON

<i>Increase/decrease amount from prior years For annual purchase (if available).</i>	N/A
--	-----

DESCRIPTION OF PROJECT / NEED

<i>Identify need for project & describe project; attach supporting documents as necessary.</i>	PLEASE SEE COUNCIL DIGEST SUPPLEMENTAL

REQUEST FOR SUSPENSION OF RULES

<i>Provide justification if prior approval is being requested.</i>	Would like to begin construction as early as possible and this would allow construction to start 2 weeks earlier.

FUNDING SOURCE

<i>Account Information.</i>	
	Surtax

**REPORT OF COMMITTEE ON PUBLIC WORKS
June 23, 2020**

Paul Ensley Chair

Michelle Chambers Co-Chair








All Council Members

An Ordinance approving Construction Contract – Springwood – Orchard Woods Concrete Street Repairs, Phase 1, Resolution #0419C - between Hipkind Concrete and the City of Fort Wayne, Indiana, in connection with the Board of Public Works


Involving a total cost of \$2,057,777.77

This will require a Suspension of the Rules in order to be introduced, discussed, and voted for passage in the same evening, with 2/3 majority in favor to proceed.

COMMITTEE ON REGULATIONS HAVE HAD SAID Ordinance under consideration and beg leave to report back to the Common Council that said Ordinance

<u>COUNCIL MEMBER</u>	<u>DO PASS</u>	<u>DO NOT PASS</u>	<u>ABSTAIN</u>
ARP			
CHAMBERS			
DIDIER			
ENSLEY			
FREISTROFFER			
HINES			
JEHL			
PADDOCK			
TUCKER			

**LANA R. KEESLING
CITY CLERK**



Public Hearing Date: N/A

Read the first time in full and on motion by Councilman Ensley.

Read the second time by title and referred to the Public Works Committee.

Read the third time in full and on motion by Councilman Ensley, placed on passage by the following vote:

<u>TOTAL VOTES</u>	<u>AYES</u>	<u>NAYS</u>	<u>ABSTAINED</u>	<u>ABSENT</u>
ARP	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CHAMBERS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
DIDIER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ENSLEY	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
FREISTROFFER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HINES	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
JEHL	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PADDOCK	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
TUCKER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

DATED: June 23, 2020



LANA R. KEESLING, CITY CLERK

Passed and adopted by the Common Council of the City of Fort Wayne, Indiana, as

Special Ordinance No. S-20-06-12 on the 23rd day of June, 2020

ATTEST:



LANA R. KEESLING
CITY CLERK



PRESIDING OFFICER

Presented by me to the Mayor of the City of Fort Wayne, Indiana, on the 24th of June 2020, at the hour of 10:55 o'clock AM E.S.T.



LANA R. KEESLING, CITY CLERK

Approved and signed by me this 24th day of June 2020, at the hour of 2:00 o'clock PM E.S.T.



THOMAS C. HENRY, MAYOR

