

1 **BILL NO. S-24-06-06**

2 SPECIAL ORDINANCE NO. S-75-24

3
4 **AN ORDINANCE** approving CONSTRUCTION
5 CONTRACT – WOODLAND LAKE CONCRETE
6 STREET REPAIRS PH. II - WORK ORDER #0784C –
7 (\$4,704,948.00) – between HIPSKIND CONCRETE
8 CORP and the City of Fort Wayne, Indiana, by and
9 through its Board of Public Works.

10 **NOW, THEREFORE, BE IT ORDAINED BY THE COMMON
11 COUNCIL OF THE CITY OF FORT WAYNE, INDIANA:**

12 **SECTION 1.** That the CONSTRUCTION CONTRACT -
13 WOODLAND LAKE CONCRETE STREET REPAIRS PH. II - WORK ORDER
14 #0784C – between HIPSKIND CONCRETE CORP and the City of Fort Wayne,
15 Indiana, by and through its Board of Public Works, is hereby ratified, and affirmed
16 and approved in all respects, respectfully for:

17 All labor, insurance, material, equipment, tools, power, transportation,
18 miscellaneous equipment, etc., necessary to IMPROVE THE
19 WOODLAND LAKE NEIGHBORHOOD, NORTHWEST PASSAGE
20 ADDITION, AND STREETS IN FALLEN TIMBERS ADDITION BY
21 REMOVAL AND REPLACEMENT OF DETERIORATED
22 CONCRETE STREETS. ALSO SIDEWALKS AND DRIVE
APPROACHES WILL BE RECONSTRUCTED. NEW
SUBSURFACE DRAINAGE WILL BE INSTALLED AND
ADJUSTMENT OF EXISTING CASTINGS. FINALLY,
RESTORATION OF DISTURBED AREAS;

23 involving a total cost of FOUR MILLION SEVEN HUNDRED FOUR THOUSAND
24 NINE HUNDRED FORTY-EIGHT and 00/100 DOLLARS - (\$4,704,948.00). A
25 copy of said Contract is on file with the Office of the City Clerk and made available
26 for public inspection, according to law.

27
28
29
30

Proj: Bid Date:	WOODLAND LAKE CONCRETE STREET REPAIRS PH. II										TOTAL: \$4,143,677.00		TOTAL: \$4,704,948.00		TOTAL: \$4,992,840.37	
	RES. NO. / W.O 0784C										% over % under		13.55% 0.00%		% over % under	
	LINE NO.	ITEM CODE	ITEM	PLAN QTY	UNIT	Estimate UNIT COST Est. (\$)	AMOUNT Est. (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	
1	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79		
2	202-02240	MOBILIZATION AND DEMOBILIZATION	1	LS	\$15,000.00	\$15,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85		
3	202-02240	PAVEMENT REMOVAL	3333	SYS	\$39,996.00	\$39,996.00	\$14.00	\$46,662.00	\$16.25	\$54,161.25	\$16.25	\$54,161.25	\$16.25	\$54,161.25		
4	202-02240	CONCRETE, REMOVE	105	SYS	\$14.00	\$1,470.00	\$17.00	\$1,785.00	\$23.75	\$2,493.75	\$23.75	\$2,493.75	\$23.75	\$2,493.75		
5	205-06933	TEMPORARY INLET PROTECTION	4	EACH	\$30.00	\$120.00	\$25.00	\$100.00	\$65.00	\$260.00	\$65.00	\$260.00	\$65.00	\$260.00		
6	214-11796	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$6,250.00	\$12.50	\$6,250.00	\$12.50	\$6,250.00		
7	301-FWR03	COMPACTED AGGREGATE NO. 53	925	TON	\$32.00	\$29,600.00	\$32.00	\$29,600.00	\$28.75	\$26,593.75	\$28.75	\$26,593.75	\$28.75	\$26,593.75		
8	502-FWR01	PCCP 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	3333	SYS	\$46.00	\$153,318.00	\$51.00	\$169,983.00	\$56.25	\$187,481.25	\$56.25	\$187,481.25	\$56.25	\$187,481.25		
9	604-06070	SIDEWALK, CONCRETE	20	SYS	\$65.00	\$1,300.00	\$60.00	\$1,200.00	\$78.75	\$1,575.00	\$78.75	\$1,575.00	\$78.75	\$1,575.00		
10	604-06086	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,875.00	\$187.50	\$1,875.00	\$187.50	\$1,875.00		
11	604-FWR01	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$650.00	\$325.00	\$650.00	\$325.00	\$650.00		
12	610-06446	PCCP FOR APPROACHES, 6 IN.	75	SYS	\$70.00	\$5,250.00	\$65.00	\$4,875.00	\$81.25	\$6,093.75	\$81.25	\$6,093.75	\$81.25	\$6,093.75		
13	611-06233	MAILBOX ASSEMBLY, RESET DOUBLE	4	EACH	\$300.00	\$1,200.00	\$250.00	\$1,000.00	\$225.00	\$900.00	\$225.00	\$900.00	\$225.00	\$900.00		
14	621-FWR01	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT	740	SYS	\$5.00	\$3,700.00	\$5.00	\$3,700.00	\$3.25	\$2,405.00	\$3.25	\$2,405.00	\$3.25	\$2,405.00		
15	623-FWR19	POLYMER FOR EROSION CONTROL AND STRAW MULCH	120	TON	\$50.00	\$6,000.00	\$50.00	\$6,000.00	\$38.50	\$4,620.00	\$38.50	\$4,620.00	\$38.50	\$4,620.00		
16	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	2222	LFT	\$10.00	\$22,220.00	\$13.00	\$28,886.00	\$13.25	\$29,441.50	\$13.25	\$29,441.50	\$13.25	\$29,441.50		
17	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	2	EACH	\$200.00	\$400.00	\$250.00	\$500.00	\$125.00	\$250.00	\$125.00	\$250.00	\$125.00	\$250.00		
18	720-FWR30	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00	\$625.00	\$625.00	\$625.00	\$625.00		
19	720-FWR37	CASTING-2x2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00	\$750.00	\$750.00	\$750.00	\$750.00		
20	720-44000	CASTING, ADJUST TO GRADE	4	EACH	\$250.00	\$1,000.00	\$750.00	\$3,000.00	\$125.00	\$500.00	\$125.00	\$500.00	\$125.00	\$500.00		
21	801-FWR01	MAINTENANCE OF TRAFFIC	1	LS	\$13,100.00	\$13,100.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09	\$2,358.09	\$2,358.09	\$2,358.09	\$2,358.09		
22	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79	\$1,315.79		
23	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85	\$13,091.85		
24	202-02240	PAVEMENT REMOVAL	1790	SYS	\$12.00	\$21,480.00	\$14.00	\$25,060.00	\$16.25	\$29,087.50	\$16.25	\$29,087.50	\$16.25	\$29,087.50		
25	202-02240	CONCRETE, REMOVE	170	SYS	\$14.00	\$2,380.00	\$17.00	\$2,890.00	\$23.75	\$4,037.50	\$23.75	\$4,037.50	\$23.75	\$4,037.50		
26	205-06933	TEMPORARY INLET PROTECTION	4	EACH	\$30.00	\$120.00	\$25.00	\$100.00	\$65.00	\$260.00	\$65.00	\$260.00	\$65.00	\$260.00		
27	214-11796	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$6,250.00	\$12.50	\$6,250.00	\$12.50	\$6,250.00		
28	301-FWR03	COMPACTED AGGREGATE NO. 53	630	TON	\$32.00	\$20,160.00	\$32.00	\$20,160.00	\$28.75	\$18,112.50	\$28.75	\$18,112.50	\$28.75	\$18,112.50		
29	502-FWR01	PCCP 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1790	SYS	\$46.00	\$82,340.00	\$51.00	\$91,290.00	\$56.25	\$100,687.50	\$56.25	\$100,687.50	\$56.25	\$100,687.50		
30	604-06070	SIDEWALK, CONCRETE	60	SYS	\$65.00	\$3,900.00	\$60.00	\$3,600.00	\$78.75	\$4,725.00	\$78.75	\$4,725.00	\$78.75	\$4,725.00		
31	604-06086	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,875.00	\$187.50	\$1,875.00	\$187.50	\$1,875.00		
32	604-FWR01	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$650.00	\$325.00	\$650.00	\$325.00	\$650.00		
33	610-06446	PCCP FOR APPROACHES, 6 IN.	100	SYS	\$70.00	\$7,000.00	\$65.00	\$6,500.00	\$81.25	\$8,125.00	\$81.25	\$8,125.00	\$81.25	\$8,125.00		
34	611-06233	MAILBOX ASSEMBLY, RESET DOUBLE	2	EACH	\$300.00	\$600.00	\$250.00	\$500.00	\$225.00	\$450.00	\$225.00	\$450.00	\$225.00	\$450.00		
35	621-FWR01	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT	400	SYS	\$5.00	\$2,000.00	\$5.00	\$2,000.00	\$3.25	\$1,300.00	\$3.25	\$1,300.00	\$3.25	\$1,300.00		
36	623-FWR19	POLYMER FOR EROSION CONTROL AND STRAW MULCH	62	TON	\$50.00	\$3,100.00	\$50.00	\$3,100.00	\$38.50	\$2,387.00	\$38.50	\$2,387.00	\$38.50	\$2,387.00		

37	715-FWR LINE B - SONA MARIE COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1200	LFT	\$10.00	\$12,000.00	\$13.00	\$15,600.00	\$13.25	\$15,600.00	\$15,600.00
38	715-94530 LINE B - SONA MARIE COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$250.00	\$125.00
39	720-FWR30 LINE B - SONA MARIE COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$850.00	\$625.00
40	720-FWR37 LINE B - SONA MARIE COURT	CASTING -2X2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$850.00	\$750.00
41	720-44000 LINE B - SONA MARIE COURT	CASTING, ADJUST TO GRADE	4	EACH	\$250.00	\$1,000.00	\$750.00	\$3,000.00	\$125.00	\$3,000.00	\$500.00
42	801-FWR01 LINE B - SONA MARIE COURT	MAINTENANCE OF TRAFFIC	1	LS	\$8,600.00	\$8,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
43	105-06845 LINE C - CALVERTON PASS	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
44	110-01001 LINE C - CALVERTON PASS	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
45	202-02240 LINE C - CALVERTON PASS	PAVEMENT REMOVAL	4085	SYS	\$12.00	\$49,020.00	\$14.00	\$57,190.00	\$16.25	\$57,190.00	\$66,381.25
46	202-93615 LINE C - CALVERTON PASS	CONCRETE, REMOVE	287	SYS	\$14.00	\$4,018.00	\$17.00	\$4,879.00	\$23.75	\$4,879.00	\$6,816.25
47	205-06933 LINE C - CALVERTON PASS	TEMPORARY INLET PROTECTION	4	EACH	\$30.00	\$120.00	\$25.00	\$100.00	\$65.00	\$100.00	\$260.00
48	214-11796 LINE C - CALVERTON PASS	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	4000	SYS	\$6.00	\$24,000.00	\$1.00	\$4,000.00	\$12.50	\$4,000.00	\$50,000.00
49	301-FWR03 LINE C - CALVERTON PASS	COMPACTED AGGREGATE NO. 53	930	TON	\$32.00	\$29,760.00	\$32.00	\$29,760.00	\$28.75	\$29,760.00	\$26,737.50
50	502-FWR01 LINE C - CALVERTON PASS	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	4085	SYS	\$46.00	\$187,910.00	\$51.00	\$208,335.00	\$56.25	\$208,335.00	\$229,781.25
51	604-06070 LINE C - CALVERTON PASS	SIDEWALK, CONCRETE	62	SYS	\$65.00	\$4,030.00	\$60.00	\$3,720.00	\$78.75	\$3,720.00	\$4,882.50
52	604-06086 LINE C - CALVERTON PASS	CURB RAMP, CONCRETE	25	SYS	\$135.00	\$3,375.00	\$180.00	\$4,500.00	\$187.50	\$4,500.00	\$4,687.50
53	604-FWR01 LINE C - CALVERTON PASS	DETECTABLE WARNING SURFACES	3	EACH	\$450.00	\$1,350.00	\$450.00	\$1,350.00	\$325.00	\$1,350.00	\$875.00
54	610-08446 LINE C - CALVERTON PASS	PCCP FOR APPROACHES, 6 IN.	200	SYS	\$70.00	\$14,000.00	\$65.00	\$13,000.00	\$81.25	\$13,000.00	\$16,250.00
55	611-08233 LINE C - CALVERTON PASS	MAILBOX ASSEMBLY, RESET DOUBLE	3	EACH	\$300.00	\$900.00	\$250.00	\$750.00	\$225.00	\$750.00	\$675.00
56	621-FWR01 LINE C - CALVERTON PASS	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	1000	SYS	\$5.00	\$5,000.00	\$5.00	\$5,000.00	\$3.25	\$5,000.00	\$3,250.00
57	623-FWR19 LINE C - CALVERTON PASS	POLYMER FOR EROSION CONTROL AND STRAW MULCH	200	TON	\$50.00	\$10,000.00	\$50.00	\$10,000.00	\$38.50	\$10,000.00	\$7,700.00
58	715-FWR LINE C - CALVERTON PASS	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	2725	LFT	\$10.00	\$27,250.00	\$13.00	\$35,425.00	\$13.25	\$35,425.00	\$36,106.25
59	715-94530 LINE C - CALVERTON PASS	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	4	EACH	\$200.00	\$800.00	\$250.00	\$1,000.00	\$125.00	\$1,000.00	\$500.00
60	720-FWR30 LINE C - CALVERTON PASS	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$850.00	\$625.00
61	720-FWR37 LINE C - CALVERTON PASS	CASTING -2X2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$850.00	\$750.00
62	720-44000 LINE C - CALVERTON PASS	CASTING, ADJUST TO GRADE	4	EACH	\$250.00	\$1,000.00	\$750.00	\$3,000.00	\$125.00	\$3,000.00	\$500.00
63	801-FWR01 LINE C - CALVERTON PASS	MAINTENANCE OF TRAFFIC	1	LS	\$9,600.00	\$9,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
64	105-06845 LINE D - DARON COURT	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
65	110-01001 LINE D - DARON COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
66	202-02240 LINE D - DARON COURT	PAVEMENT REMOVAL	676	SYS	\$12.00	\$8,112.00	\$14.00	\$9,464.00	\$16.25	\$9,464.00	\$10,985.00
67	202-93615 LINE D - DARON COURT	CONCRETE, REMOVE	50	SYS	\$14.00	\$700.00	\$17.00	\$850.00	\$23.75	\$850.00	\$1,187.50
68	205-06933 LINE D - DARON COURT	TEMPORARY INLET PROTECTION	1	EACH	\$30.00	\$30.00	\$25.00	\$25.00	\$65.00	\$25.00	\$65.00
69	214-11796 LINE D - DARON COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	300	SYS	\$6.00	\$1,800.00	\$1.00	\$300.00	\$12.50	\$300.00	\$3,750.00
70	301-FWR03 LINE D - DARON COURT	COMPACTED AGGREGATE NO. 53	160	TON	\$32.00	\$5,120.00	\$32.00	\$5,120.00	\$28.75	\$5,120.00	\$4,600.00
71	502-FWR01 LINE D - DARON COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	676	SYS	\$46.00	\$31,096.00	\$51.00	\$34,476.00	\$56.25	\$34,476.00	\$38,025.00
72	604-06070 LINE D - DARON COURT	SIDEWALK, CONCRETE	1	SYS	\$65.00	\$65.00	\$60.00	\$60.00	\$78.75	\$60.00	\$78.75
73	604-06086 LINE D - DARON COURT	CURB RAMP, CONCRETE	1	SYS	\$135.00	\$135.00	\$180.00	\$180.00	\$187.50	\$180.00	\$187.50
74	604-FWR01 LINE D - DARON COURT	DETECTABLE WARNING SURFACES	1	EACH	\$450.00	\$450.00	\$450.00	\$450.00	\$325.00	\$450.00	\$325.00
75	610-08446 LINE D - DARON COURT	PCCP FOR APPROACHES, 6 IN.	50	SYS	\$70.00	\$3,500.00	\$65.00	\$3,250.00	\$81.25	\$3,250.00	\$4,062.50
76	611-08233 LINE D - DARON COURT	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$250.00	\$225.00
77	621-FWR01 LINE D - DARON COURT	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	110	SYS	\$5.00	\$550.00	\$5.00	\$550.00	\$3.25	\$550.00	\$357.50
78	623-FWR19 LINE D - DARON COURT	POLYMER FOR EROSION CONTROL AND STRAW MULCH	20	TON	\$50.00	\$1,000.00	\$50.00	\$1,000.00	\$38.50	\$1,000.00	\$770.00

79	715-FWR LINE D - DARON COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	320	LFT	\$10.00	\$3,200.00	\$13.00	\$4,160.00	\$13.25	\$4,240.00
80	715-94530 LINE D - DARON COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$125.00
81	720-FWR30 LINE D - DARON COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00
82	720-FWR37 LINE D - DARON COURT	CASTING -2X2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00
83	720-44000 LINE D - DARON COURT	CASTING, ADJUST TO GRADE	1	EACH	\$250.00	\$250.00	\$750.00	\$750.00	\$125.00	\$125.00
84	801-FWR01 LINE D - DARON COURT	MAINTENANCE OF TRAFFIC	1	LS	\$8,600.00	\$8,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
85	105-06845 LINE E - CALVERTON COURT	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
86	110-01001 LINE E - CALVERTON COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
87	202-02240 LINE E - CALVERTON COURT	PAVEMENT REMOVAL	1662	SYS	\$12.00	\$19,944.00	\$14.00	\$23,268.00	\$16.25	\$27,007.50
88	202-93615 LINE E - CALVERTON COURT	CONCRETE, REMOVE	199	SYS	\$14.00	\$2,786.00	\$17.00	\$3,383.00	\$23.75	\$4,726.25
89	205-06933 LINE E - CALVERTON COURT	TEMPORARY INLET PROTECTION	1	EACH	\$30.00	\$30.00	\$25.00	\$25.00	\$65.00	\$65.00
90	214-11796 LINE E - CALVERTON COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$6,250.00
91	301-FWR03 LINE E - CALVERTON COURT	COMPACTED AGGREGATE NO. 53	400	TON	\$32.00	\$12,800.00	\$32.00	\$12,800.00	\$28.75	\$11,500.00
92	502-FWR01 LINE E - CALVERTON COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1662	SYS	\$46.00	\$76,452.00	\$51.00	\$84,762.00	\$56.25	\$93,487.50
93	604-06070 LINE E - CALVERTON COURT	SIDEWALK, CONCRETE	62	SYS	\$65.00	\$4,030.00	\$60.00	\$3,720.00	\$78.75	\$4,882.50
94	604-08086 LINE E - CALVERTON COURT	CURB RAMP, CONCRETE	12	SYS	\$135.00	\$1,620.00	\$180.00	\$2,160.00	\$187.50	\$2,250.00
95	604-FWR01 LINE E - CALVERTON COURT	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$650.00
96	610-08446 LINE E - CALVERTON COURT	PCCP FOR APPROACHES, 6 IN.	125	SYS	\$70.00	\$8,750.00	\$65.00	\$8,125.00	\$81.25	\$10,156.25
97	611-08233 LINE E - CALVERTON COURT	MAILBOX ASSEMBLY, RESET DOUBLE	2	EACH	\$300.00	\$600.00	\$250.00	\$500.00	\$225.00	\$450.00
98	621-FWR01 LINE E - CALVERTON COURT	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	320	SYS	\$5.00	\$1,600.00	\$5.00	\$1,600.00	\$3.25	\$1,040.00
99	623-FWR19 LINE E - CALVERTON COURT	TOPSOIL	60	TON	\$50.00	\$3,000.00	\$50.00	\$3,000.00	\$38.50	\$2,310.00
100	715-FWR LINE E - CALVERTON COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	950	LFT	\$10.00	\$9,500.00	\$13.00	\$12,350.00	\$13.25	\$12,587.50
101	715-94530 LINE E - CALVERTON COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	2	EACH	\$200.00	\$400.00	\$250.00	\$500.00	\$125.00	\$250.00
102	720-FWR30 LINE E - CALVERTON COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00
103	720-FWR37 LINE E - CALVERTON COURT	CASTING -2X2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00
104	720-44000 LINE E - CALVERTON COURT	CASTING, ADJUST TO GRADE	1	EACH	\$250.00	\$250.00	\$750.00	\$750.00	\$125.00	\$125.00
105	801-FWR01 LINE E - CALVERTON COURT	MAINTENANCE OF TRAFFIC	1	LS	\$8,600.00	\$8,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
106	105-06845 LINE E - CALVERTON COURT	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
107	110-01001 LINE E - WOODLAND CROSSING	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
108	202-02240 LINE F - WOODLAND CROSSING	PAVEMENT REMOVAL	8696	SYS	\$12.00	\$104,352.00	\$14.00	\$121,744.00	\$16.25	\$141,310.00
109	202-93615 LINE F - WOODLAND CROSSING	CONCRETE, REMOVE	450	SYS	\$14.00	\$6,300.00	\$17.00	\$7,650.00	\$23.75	\$10,687.50
110	205-06933 LINE F - WOODLAND CROSSING	TEMPORARY INLET PROTECTION	10	EACH	\$30.00	\$300.00	\$25.00	\$250.00	\$65.00	\$650.00
111	214-11796 LINE F - WOODLAND CROSSING	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	4500	SYS	\$6.00	\$27,000.00	\$1.00	\$4,500.00	\$12.50	\$56,250.00
112	301-FWR03 LINE F - WOODLAND CROSSING	COMPACTED AGGREGATE NO. 53	2100	TON	\$32.00	\$67,200.00	\$32.00	\$67,200.00	\$28.75	\$60,375.00
113	502-FWR01 LINE F - WOODLAND CROSSING	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	8696	SYS	\$46.00	\$400,016.00	\$51.00	\$443,496.00	\$56.25	\$489,150.00
114	604-06070 LINE F - WOODLAND CROSSING	SIDEWALK, CONCRETE	100	SYS	\$65.00	\$6,500.00	\$60.00	\$6,000.00	\$78.75	\$7,875.00
115	604-08086 LINE F - WOODLAND CROSSING	CURB RAMP, CONCRETE	100	SYS	\$135.00	\$13,500.00	\$180.00	\$18,000.00	\$187.50	\$18,750.00
116	604-FWR01 LINE F - WOODLAND CROSSING	DETECTABLE WARNING SURFACES	10	EACH	\$450.00	\$4,500.00	\$450.00	\$4,500.00	\$325.00	\$3,250.00
117	610-08446 LINE F - WOODLAND CROSSING	PCCP FOR APPROACHES, 6 IN.	250	SYS	\$70.00	\$17,500.00	\$65.00	\$16,250.00	\$81.25	\$20,312.50
118	611-08233 LINE F - WOODLAND CROSSING	MAILBOX ASSEMBLY, RESET DOUBLE	5	EACH	\$300.00	\$1,500.00	\$250.00	\$1,250.00	\$225.00	\$1,125.00
119	621-FWR01 LINE F - WOODLAND CROSSING	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	2000	SYS	\$5.00	\$10,000.00	\$5.00	\$10,000.00	\$3.25	\$6,500.00
120	623-FWR19 LINE F - WOODLAND CROSSING	TOPSOIL	320	TON	\$50.00	\$16,000.00	\$50.00	\$16,000.00	\$38.50	\$12,320.00

121	715-FWR LINE F - WOODLAND CROSSING	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	5600	LFT	\$10.00	\$58,000.00	\$13.00	\$75,400.00	\$13.25	\$76,850.00
122	715-94530 LINE F - WOODLAND CROSSING	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	2	EACH	\$200.00	\$400.00	\$250.00	\$500.00	\$125.00	\$250.00
123	720-FWR30 LINE F - WOODLAND CROSSING	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$650.00	\$850.00	\$625.00	\$625.00
124	720-FWR37 LINE F - WOODLAND CROSSING	CASTING -2x2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	5	EACH	\$800.00	\$4,000.00	\$650.00	\$4,250.00	\$750.00	\$3,750.00
125	720-44000 LINE F - WOODLAND CROSSING	CASTING, ADJUST TO GRADE	10	EACH	\$250.00	\$2,500.00	\$750.00	\$7,500.00	\$125.00	\$1,250.00
126	801-FWR01 LINE F - WOODLAND CROSSING	MAINTENANCE OF TRAFFIC	1	LS	\$8,600.00	\$8,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
127	808-10056 LINE F - WOODLAND CROSSING	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	54	LFT	\$5.00	\$270.00	\$100.00	\$5,400.00	\$10.00	\$540.00
128	105-06845 LINE F - WOODLAND CROSSING	CONSTRUCTION ENGINEERING	1	LS	\$7,125.00	\$7,125.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
129	110-01001 LINE G - TALINE COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$10,000.00	\$10,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
130	202-02240 LINE G - TALINE COURT	PAVEMENT REMOVAL	1365	SYS	\$12.00	\$16,380.00	\$14.00	\$19,110.00	\$16.25	\$22,181.25
131	202-93615 LINE G - TALINE COURT	CONCRETE, REMOVE	85	SYS	\$14.00	\$1,190.00	\$17.00	\$1,445.00	\$23.75	\$2,018.75
132	205-06933 LINE G - TALINE COURT	TEMPORARY INLET PROTECTION	2	EACH	\$300.00	\$600.00	\$25.00	\$50.00	\$65.00	\$130.00
133	214-11796 LINE G - TALINE COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$6,250.00
134	301-FWR03 LINE G - TALINE COURT	COMPACTED AGGREGATE NO. 53	320	TON	\$32.00	\$10,240.00	\$32.00	\$10,240.00	\$28.75	\$9,200.00
135	502-FWR01 LINE G - TALINE COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1365	SYS	\$46.00	\$62,790.00	\$51.00	\$69,615.00	\$56.25	\$76,761.25
136	604-06070 LINE G - TALINE COURT	SIDEWALK, CONCRETE	25	SYS	\$65.00	\$1,625.00	\$60.00	\$1,500.00	\$78.75	\$1,968.75
137	604-08086 LINE G - TALINE COURT	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,875.00
138	604-FWR01 LINE G - TALINE COURT	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$650.00
139	610-08446 LINE G - TALINE COURT	PCCP FOR APPROACHES, 6 IN.	50	SYS	\$70.00	\$3,500.00	\$65.00	\$3,250.00	\$81.25	\$4,062.50
140	611-00233 LINE G - TALINE COURT	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00
141	621-FWR01 LINE G - TALINE COURT	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	300	SYS	\$5.00	\$1,500.00	\$5.00	\$1,500.00	\$3.25	\$975.00
142	623-FWR19 LINE G - TALINE COURT	TOPSOIL	40	TON	\$50.00	\$2,000.00	\$50.00	\$2,000.00	\$38.50	\$1,540.00
143	715-FWR LINE G - TALINE COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	720	LFT	\$10.00	\$7,200.00	\$13.00	\$9,360.00	\$13.25	\$9,540.00
144	715-94530 LINE G - TALINE COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$125.00
145	720-FWR30 LINE G - TALINE COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$650.00	\$850.00	\$625.00	\$625.00
146	720-FWR37 LINE G - TALINE COURT	CASTING -2x2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$650.00	\$850.00	\$750.00	\$750.00
147	720-44000 LINE G - TALINE COURT	CASTING, ADJUST TO GRADE	2	EACH	\$250.00	\$500.00	\$750.00	\$1,500.00	\$125.00	\$250.00
148	801-FWR01 LINE H - MARAL COURT	MAINTENANCE OF TRAFFIC	1	LS	\$8,600.00	\$8,600.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
149	105-06845 LINE H - MARAL COURT	CONSTRUCTION ENGINEERING	1	LS	\$3,625.00	\$3,625.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
150	110-01001 LINE H - MARAL COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,000.00	\$3,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
151	202-02240 LINE H - MARAL COURT	PAVEMENT REMOVAL	650	SYS	\$12.00	\$7,800.00	\$14.00	\$9,100.00	\$16.25	\$10,562.50
152	202-93615 LINE H - MARAL COURT	CONCRETE, REMOVE	85	SYS	\$14.00	\$1,190.00	\$17.00	\$1,445.00	\$23.75	\$2,018.75
153	205-06933 LINE H - MARAL COURT	TEMPORARY INLET PROTECTION	2	EACH	\$300.00	\$600.00	\$25.00	\$50.00	\$65.00	\$130.00
154	214-11796 LINE H - MARAL COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	250	SYS	\$6.00	\$1,500.00	\$1.00	\$250.00	\$12.50	\$3,125.00
155	301-FWR03 LINE H - MARAL COURT	COMPACTED AGGREGATE NO. 53	140	TON	\$32.00	\$4,480.00	\$32.00	\$4,480.00	\$28.75	\$4,025.00
156	502-FWR01 LINE H - MARAL COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	650	SYS	\$46.00	\$29,900.00	\$51.00	\$33,150.00	\$56.25	\$36,562.50
157	604-06070 LINE H - MARAL COURT	SIDEWALK, CONCRETE	10	SYS	\$65.00	\$650.00	\$60.00	\$600.00	\$78.75	\$787.50
158	604-08086 LINE H - MARAL COURT	CURB RAMP, CONCRETE	1	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,875.00
159	604-FWR01 LINE H - MARAL COURT	DETECTABLE WARNING SURFACES	1	EACH	\$450.00	\$450.00	\$450.00	\$450.00	\$325.00	\$325.00
160	610-08446 LINE H - MARAL COURT	PCCP FOR APPROACHES, 6 IN.	25	SYS	\$70.00	\$1,750.00	\$65.00	\$1,625.00	\$81.25	\$2,031.25
161	611-00233 LINE H - MARAL COURT	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00
162	621-FWR01 LINE H - MARAL COURT	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	100	SYS	\$5.00	\$500.00	\$5.00	\$500.00	\$3.25	\$325.00

163	623-FWR19 LINE H - MARAL COURT	TOPSOIL	10	TON	\$50.00	\$500.00	\$50.00	\$500.00	\$38.50	\$500.00	\$385.00
164	715-FWR LINE H - MARAL COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	433	LFT	\$10.00	\$4,330.00	\$13.00	\$5,629.00	\$13.25	\$5,629.00	\$5,737.25
165	715-94530 LINE H - MARAL COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$250.00	\$125.00
166	720-FWR30 LINE H - MARAL COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$650.00	\$650.00	\$625.00	\$650.00	\$625.00
167	720-FWR37 LINE H - MARAL COURT	CASTING -2X2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$650.00	\$650.00	\$750.00	\$650.00	\$750.00
168	720-44000 LINE H - MARAL COURT	CASTING, ADJUST TO GRADE	1	EACH	\$250.00	\$250.00	\$750.00	\$750.00	\$125.00	\$750.00	\$125.00
169	801-FWR01 LINE H - MARAL COURT	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
170	105-06845 LINE I - TAMAR TRAIL	CONSTRUCTION ENGINEERING	1	LS	\$6,625.00	\$6,625.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
171	110-01001 LINE I - TAMAR TRAIL	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
172	202-02240 LINE I - TAMAR TRAIL	PAVEMENT REMOVAL	1500	SYS	\$12.00	\$18,000.00	\$14.00	\$21,000.00	\$16.25	\$21,000.00	\$24,375.00
173	202-93615 LINE I - TAMAR TRAIL	CONCRETE, REMOVE	205	SYS	\$14.00	\$2,870.00	\$17.00	\$3,485.00	\$23.75	\$3,485.00	\$4,868.75
174	205-06933 LINE I - TAMAR TRAIL	TEMPORARY INLET PROTECTION	2	EACH	\$30.00	\$60.00	\$25.00	\$50.00	\$65.00	\$50.00	\$130.00
175	214-11796 LINE I - TAMAR TRAIL	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX 160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$500.00	\$6,250.00
176	301-FWR03 LINE I - TAMAR TRAIL	COMPACTED AGGREGATE NO. 53	440	TON	\$32.00	\$14,080.00	\$32.00	\$14,080.00	\$28.75	\$14,080.00	\$12,650.00
177	502-FWR01 LINE I - TAMAR TRAIL	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1500	SYS	\$46.00	\$69,000.00	\$51.00	\$76,500.00	\$56.25	\$76,500.00	\$84,375.00
178	604-06070 LINE I - TAMAR TRAIL	SIDEWALK, CONCRETE	45	SYS	\$65.00	\$2,925.00	\$60.00	\$2,700.00	\$78.75	\$2,700.00	\$3,543.75
179	604-06086 LINE I - TAMAR TRAIL	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,800.00	\$1,875.00
180	604-FWR01 LINE I - TAMAR TRAIL	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$900.00	\$650.00
181	610-09446 LINE I - TAMAR TRAIL	PCCP FOR APPROACHES, 6 IN.	150	SYS	\$70.00	\$10,500.00	\$65.00	\$9,750.00	\$81.25	\$9,750.00	\$12,187.50
182	611-09233 LINE I - TAMAR TRAIL	MAILBOX ASSEMBLY, RESET DOUBLE	2	EACH	\$300.00	\$600.00	\$250.00	\$500.00	\$225.00	\$500.00	\$450.00
183	621-FWR01 LINE I - TAMAR TRAIL	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	350	SYS	\$5.00	\$1,750.00	\$5.00	\$1,750.00	\$3.25	\$1,750.00	\$1,137.50
184	623-FWR19 LINE I - TAMAR TRAIL	TOPSOIL	60	TON	\$50.00	\$3,000.00	\$50.00	\$3,000.00	\$38.50	\$3,000.00	\$2,310.00
185	715-FWR LINE I - TAMAR TRAIL	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1000	LFT	\$10.00	\$10,000.00	\$13.00	\$13,000.00	\$13.25	\$13,000.00	\$13,250.00
186	715-94530 LINE I - TAMAR TRAIL	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	2	EACH	\$200.00	\$400.00	\$250.00	\$500.00	\$125.00	\$500.00	\$250.00
187	720-FWR30 LINE I - TAMAR TRAIL	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$650.00	\$650.00	\$625.00	\$650.00	\$625.00
188	720-FWR37 LINE I - TAMAR TRAIL	CASTING -2X2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$650.00	\$650.00	\$750.00	\$650.00	\$750.00
189	720-44000 LINE I - TAMAR TRAIL	CASTING, ADJUST TO GRADE	6	EACH	\$250.00	\$1,500.00	\$750.00	\$4,500.00	\$125.00	\$4,500.00	\$750.00
190	801-FWR01 LINE I - TAMAR TRAIL	MAINTENANCE OF TRAFFIC	1	LS	\$4,300.00	\$4,300.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
191	105-06845 LINE J - TINA MARIE COURT	CONSTRUCTION ENGINEERING	1	LS	\$6,625.00	\$6,625.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
192	110-01001 LINE J - TINA MARIE COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
193	202-02240 LINE J - TINA MARIE COURT	PAVEMENT REMOVAL	1768	SYS	\$12.00	\$21,216.00	\$14.00	\$24,752.00	\$16.25	\$24,752.00	\$28,730.00
194	202-93615 LINE J - TINA MARIE COURT	CONCRETE, REMOVE	130	SYS	\$14.00	\$1,820.00	\$17.00	\$2,210.00	\$23.75	\$2,210.00	\$3,087.50
195	205-06933 LINE J - TINA MARIE COURT	TEMPORARY INLET PROTECTION	3	EACH	\$30.00	\$90.00	\$25.00	\$75.00	\$65.00	\$75.00	\$195.00
196	214-11796 LINE J - TINA MARIE COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX 160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$500.00	\$6,250.00
197	301-FWR03 LINE J - TINA MARIE COURT	COMPACTED AGGREGATE NO. 53	460	TON	\$32.00	\$14,720.00	\$32.00	\$14,720.00	\$28.75	\$14,720.00	\$13,225.00
198	502-FWR01 LINE J - TINA MARIE COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1768	SYS	\$46.00	\$81,328.00	\$51.00	\$90,168.00	\$56.25	\$90,168.00	\$99,450.00
199	604-06070 LINE J - TINA MARIE COURT	SIDEWALK, CONCRETE	45	SYS	\$65.00	\$2,925.00	\$60.00	\$2,700.00	\$78.75	\$2,700.00	\$3,543.75
200	604-06086 LINE J - TINA MARIE COURT	CURB RAMP, CONCRETE	25	SYS	\$135.00	\$3,375.00	\$180.00	\$4,500.00	\$187.50	\$4,500.00	\$4,687.50
201	604-FWR01 LINE J - TINA MARIE COURT	DETECTABLE WARNING SURFACES	4	EACH	\$450.00	\$1,800.00	\$450.00	\$1,800.00	\$325.00	\$1,800.00	\$1,300.00
202	610-09446 LINE J - TINA MARIE COURT	PCCP FOR APPROACHES, 6 IN.	100	SYS	\$70.00	\$7,000.00	\$65.00	\$6,500.00	\$81.25	\$6,500.00	\$8,125.00
203	611-09233 LINE J - TINA MARIE COURT	MAILBOX ASSEMBLY, RESET DOUBLE	2	EACH	\$300.00	\$600.00	\$250.00	\$500.00	\$225.00	\$500.00	\$450.00
204	621-FWR01 LINE J - TINA MARIE COURT	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	600	SYS	\$5.00	\$3,000.00	\$5.00	\$3,000.00	\$3.25	\$3,000.00	\$1,950.00

205	623-FWR19 LINE J - TINA MARIE COURT	TOPSOIL	100	TON	\$50.00	\$5,000.00	\$50.00	\$5,000.00	\$38.50	\$5,000.00	\$3,850.00
206	715-FWR LINE J - TINA MARIE COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1200	LFT	\$13.00	\$12,000.00	\$13.00	\$12,000.00	\$13.25	\$15,600.00	\$15,900.00
207	715-94530 LINE J - TINA MARIE COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$250.00	\$125.00
208	720-FWR30 LINE J - TINA MARIE COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$850.00	\$625.00
209	720-FWR37 LINE J - TINA MARIE COURT	CASTING -2X2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$850.00	\$750.00
210	720-44000 LINE J - TINA MARIE COURT	CASTING, ADJUST TO GRADE	3	EACH	\$250.00	\$750.00	\$750.00	\$750.00	\$125.00	\$2,250.00	\$375.00
211	801-FWR01 LINE J - TINA MARIE COURT	MAINTENANCE OF TRAFFIC	1	LS	\$4,300.00	\$4,300.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
212	105-06845 LINE K - TAMAR COVE	CONSTRUCTION ENGINEERING	1	LS	\$6,625.00	\$6,625.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
213	110-01001 LINE K - TAMAR COVE	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
214	202-02240 LINE K - TAMAR COVE	PAVEMENT REMOVAL	642	SYS	\$12.00	\$7,704.00	\$14.00	\$9,888.00	\$16.25	\$8,988.00	\$10,432.50
215	202-93615 LINE K - TAMAR COVE	CONCRETE, REMOVE	70	SYS	\$14.00	\$980.00	\$17.00	\$1,190.00	\$23.75	\$1,190.00	\$1,662.50
216	205-06893 LINE K - TAMAR COVE	TEMPORARY INLET PROTECTION	1	EACH	\$30.00	\$30.00	\$25.00	\$25.00	\$65.00	\$25.00	\$65.00
217	214-11796 LINE K - TAMAR COVE	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$2.00	\$1,000.00	\$12.50	\$1,000.00	\$6,250.00
218	301-FWR03 LINE K - TAMAR COVE	COMPACTED AGGREGATE NO. 53	160	TON	\$32.00	\$5,120.00	\$32.00	\$5,120.00	\$28.75	\$5,120.00	\$4,600.00
219	502-FWR01 LINE K - TAMAR COVE	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	642	SYS	\$46.00	\$29,532.00	\$51.00	\$32,742.00	\$56.25	\$32,742.00	\$36,112.50
220	604-06070 LINE K - TAMAR COVE	SIDEWALK, CONCRETE	10	SYS	\$65.00	\$650.00	\$60.00	\$600.00	\$78.75	\$600.00	\$787.50
221	604-08086 LINE K - TAMAR COVE	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,800.00	\$1,875.00
222	604-FWR01 LINE K - TAMAR COVE	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$900.00	\$650.00
223	610-09446 LINE K - TAMAR COVE	PCCP FOR APPROACHES, 6 IN.	50	SYS	\$70.00	\$3,500.00	\$65.00	\$3,250.00	\$81.25	\$3,250.00	\$4,062.50
224	611-09233 LINE K - TAMAR COVE	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$250.00	\$225.00
225	621-FWR01 LINE K - TAMAR COVE	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	110	SYS	\$5.00	\$550.00	\$5.00	\$550.00	\$3.25	\$550.00	\$357.50
226	623-FWR19 LINE K - TAMAR COVE	POLYMER FOR EROSION CONTROL AND STRAW MULCH	20	TON	\$50.00	\$1,000.00	\$50.00	\$1,000.00	\$38.50	\$1,000.00	\$770.00
227	715-FWR LINE K - TAMAR COVE	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	310	LFT	\$10.00	\$3,100.00	\$13.00	\$4,030.00	\$13.25	\$4,030.00	\$4,107.50
228	715-94530 LINE K - TAMAR COVE	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$250.00	\$125.00
229	720-FWR30 LINE K - TAMAR COVE	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$850.00	\$625.00
230	720-FWR37 LINE K - TAMAR COVE	CASTING -2X2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$850.00	\$750.00
231	720-44000 LINE K - TAMAR COVE	CASTING, ADJUST TO GRADE	1	EACH	\$250.00	\$250.00	\$750.00	\$750.00	\$125.00	\$750.00	\$125.00
232	801-FWR01 LINE K - TAMAR COVE	MAINTENANCE OF TRAFFIC	1	LS	\$4,300.00	\$4,300.00	\$9,000.00	\$9,000.00	\$2,358.09	\$9,000.00	\$2,358.09
233	105-06845 LINE L - DEREV COURT	CONSTRUCTION ENGINEERING	1	LS	\$6,625.00	\$6,625.00	\$9,000.00	\$9,000.00	\$1,315.79	\$9,000.00	\$1,315.79
234	110-01001 LINE L - DEREV COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$9,000.00	\$13,091.85
235	202-02240 LINE L - DEREV COURT	PAVEMENT REMOVAL	1100	SYS	\$12.00	\$13,200.00	\$14.00	\$15,400.00	\$16.25	\$15,400.00	\$17,875.00
236	202-93615 LINE L - DEREV COURT	CONCRETE, REMOVE	145	SYS	\$14.00	\$2,030.00	\$17.00	\$2,465.00	\$23.75	\$2,465.00	\$3,443.75
237	205-06893 LINE L - DEREV COURT	TEMPORARY INLET PROTECTION	2	EACH	\$30.00	\$60.00	\$25.00	\$50.00	\$65.00	\$50.00	\$130.00
238	214-11796 LINE L - DEREV COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$500.00	\$12.50	\$500.00	\$6,250.00
239	301-FWR03 LINE L - DEREV COURT	COMPACTED AGGREGATE NO. 53	275	TON	\$32.00	\$8,800.00	\$32.00	\$8,800.00	\$28.75	\$8,800.00	\$7,906.25
240	502-FWR01 LINE L - DEREV COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	1100	SYS	\$46.00	\$50,600.00	\$51.00	\$56,100.00	\$56.25	\$56,100.00	\$61,875.00
241	604-06070 LINE L - DEREV COURT	SIDEWALK, CONCRETE	35	SYS	\$65.00	\$2,275.00	\$60.00	\$2,100.00	\$78.75	\$2,100.00	\$2,756.25
242	604-08086 LINE L - DEREV COURT	CURB RAMP, CONCRETE	10	SYS	\$135.00	\$1,350.00	\$180.00	\$1,800.00	\$187.50	\$1,800.00	\$1,875.00
243	604-FWR01 LINE L - DEREV COURT	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$900.00	\$650.00
244	610-09446 LINE L - DEREV COURT	PCCP FOR APPROACHES, 6 IN.	100	SYS	\$70.00	\$7,000.00	\$65.00	\$6,500.00	\$81.25	\$6,500.00	\$8,125.00
245	611-09233 LINE L - DEREV COURT	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$250.00	\$225.00
246	621-FWR01 LINE L - DEREV COURT	HYDROSEED WITH HYDROSTICK TACKIFIER OR EQUIVALENT	300	SYS	\$5.00	\$1,500.00	\$5.00	\$1,500.00	\$3.25	\$1,500.00	\$975.00

247	623-FWR19 LINE L - DEREV COURT	TOPSOIL	40	TON	\$50.00	\$2,000.00	\$50.00	\$2,000.00	\$38.50	\$1,540.00
248	715-FWR LINE L - DEREV COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. WIAGGREGATE FOR UNDERDRAIN	610	LFT	\$13.00	\$7,930.00	\$13.00	\$7,930.00	\$13.25	\$8,082.50
249	715-94530 LINE L - DEREV COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$250.00	\$250.00	\$250.00	\$250.00	\$125.00	\$125.00
250	720-FWR30 LINE L - DEREV COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$750.00	\$750.00	\$625.00	\$625.00
251	720-FWR37 LINE L - DEREV COURT	CASTING -2x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$850.00	\$850.00	\$850.00	\$850.00	\$750.00	\$750.00
252	720-44000 LINE L - DEREV COURT	CASTING, ADJUST TO GRADE	2	EACH	\$250.00	\$500.00	\$250.00	\$500.00	\$125.00	\$250.00
253	801-FWR01 LINE L - DEREV COURT	MAINTENANCE OF TRAFFIC	1	LS	\$4,300.00	\$4,300.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
254	105-06845 LINE M - NORTHWEST PASSAGE	CONSTRUCTION ENGINEERING	1	LS	\$5,500.00	\$5,500.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
255	110-01001 LINE M - NORTHWEST PASSAGE	MOBILIZATION AND DEMOBILIZATION	1	LS	\$8,500.00	\$8,500.00	\$9,000.00	\$9,000.00	\$13,081.85	\$13,081.85
256	202-02240 LINE M - NORTHWEST PASSAGE	PAVEMENT REMOVAL	8428	SYS	\$12.00	\$101,136.00	\$14.00	\$117,982.00	\$16.25	\$136,955.00
257	202-93615 LINE M - NORTHWEST PASSAGE	CONCRETE, REMOVE	242	SYS	\$14.00	\$3,388.00	\$17.00	\$4,114.00	\$23.75	\$5,747.50
258	205-06833 LINE M - NORTHWEST PASSAGE	TEMPORARY INLET PROTECTION	18	EACH	\$30.00	\$540.00	\$25.00	\$450.00	\$65.00	\$1,170.00
259	214-11786 LINE M - NORTHWEST PASSAGE	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX180)	4000	SYS	\$6.00	\$24,000.00	\$1.00	\$4,000.00	\$12.50	\$50,000.00
260	301-FWR03 LINE M - NORTHWEST PASSAGE	COMPACTED AGGREGATE NO. 53	2100	TON	\$32.00	\$67,200.00	\$32.00	\$67,200.00	\$28.75	\$60,375.00
261	502-FWR01 LINE M - NORTHWEST PASSAGE	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	8428	SYS	\$46.00	\$387,688.00	\$51.00	\$429,828.00	\$56.25	\$474,075.00
262	604-06070 LINE M - NORTHWEST PASSAGE	SIDEWALK, CONCRETE	72	SYS	\$65.00	\$4,680.00	\$60.00	\$4,320.00	\$78.75	\$5,670.00
263	604-06086 LINE M - NORTHWEST PASSAGE	CURB RAMP, CONCRETE	20	SYS	\$135.00	\$2,700.00	\$180.00	\$3,600.00	\$187.50	\$3,750.00
264	604-FWR01 LINE M - NORTHWEST PASSAGE	DETECTABLE WARNING SURFACES	2	EACH	\$450.00	\$900.00	\$450.00	\$900.00	\$325.00	\$650.00
265	610-08446 LINE M - NORTHWEST PASSAGE	PCCP FOR APPROACHES, 6 IN.	150	SYS	\$70.00	\$10,500.00	\$65.00	\$9,750.00	\$81.25	\$12,187.50
266	611-08233 LINE M - NORTHWEST PASSAGE	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00
267	621-FWR01 LINE M - NORTHWEST PASSAGE	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1625	SYS	\$5.00	\$8,125.00	\$5.00	\$8,125.00	\$3.25	\$5,281.25
268	623-FWR19 LINE M - NORTHWEST PASSAGE	TOPSOIL	180	TON	\$50.00	\$9,000.00	\$50.00	\$9,000.00	\$38.50	\$7,315.00
269	715-FWR LINE M - NORTHWEST PASSAGE	PIPE, TYPE 4, CIRCULAR, 6 IN. WIAGGREGATE FOR UNDERDRAIN	4865	LFT	\$13.00	\$63,850.00	\$13.00	\$63,245.00	\$13.25	\$64,461.25
270	715-94530 LINE M - NORTHWEST PASSAGE	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	2	EACH	\$200.00	\$400.00	\$250.00	\$500.00	\$125.00	\$250.00
271	715-FWR13 LINE M - NORTHWEST PASSAGE	PIPE-12" RCP, CLASS III	36	LFT	\$120.00	\$4,320.00	\$195.00	\$7,020.00	\$150.00	\$5,400.00
272	720-FWR15 LINE M - NORTHWEST PASSAGE	INLET- PRECAST 30" ROUND INLET	2	EACH	\$1,400.00	\$2,800.00	\$3,500.00	\$7,000.00	\$2,500.00	\$5,000.00
273	720-FWR30 LINE M - NORTHWEST PASSAGE	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00
274	720-FWR37 LINE M - NORTHWEST PASSAGE	CASTING -2x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	5	EACH	\$800.00	\$4,000.00	\$850.00	\$4,250.00	\$750.00	\$3,750.00
275	720-FWR36 LINE M - NORTHWEST PASSAGE	CASTING-2x2' ALLEY CASTING FURNISH & ADJUST TO GRADE	2	EACH	\$900.00	\$1,800.00	\$1,500.00	\$3,000.00	\$1,250.00	\$2,500.00
276	720-44000 LINE M - NORTHWEST PASSAGE	CASTING, ADJUST TO GRADE	18	EACH	\$250.00	\$4,500.00	\$750.00	\$13,500.00	\$125.00	\$2,250.00

277	801-FWR01 LINE M - NORTHWEST PASSAGE TRAIL	MAINTENANCE OF TRAFFIC	1	LS	\$6,500.00	\$6,500.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
278	805-FWR01 LINE M - NORTHWEST PASSAGE TRAIL	ROADWAY SIGNAL LOOP	8	EACH	\$800.00	\$6,400.00	\$1,500.00	\$12,000.00	\$1,000.00	\$8,000.00
279	805-FWR85 LINE M - NORTHWEST PASSAGE TRAIL	SIGNAL DETECTOR HOUSING	2	EACH	\$450.00	\$900.00	\$3,000.00	\$6,000.00	\$2,000.00	\$4,000.00
280	808-10033 LINE M - NORTHWEST PASSAGE TRAIL	LINE, MULT-COMPONENT, SOLID, WHITE, 4 IN.	60	LFT	\$3.00	\$180.00	\$100.00	\$6,000.00	\$10.00	\$600.00
281	808-10051 LINE M - NORTHWEST PASSAGE TRAIL	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	28	LFT	\$5.00	\$140.00	\$24.00	\$672.00	\$24.00	\$672.00
282	808-10052 LINE M - NORTHWEST PASSAGE TRAIL	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1	EACH	\$250.00	\$250.00	\$1,500.00	\$400.00	\$400.00	\$400.00
283	808-10077 LINE M - NORTHWEST PASSAGE TRAIL	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	1	EACH	\$250.00	\$250.00	\$1,500.00	\$400.00	\$400.00	\$400.00
284	105-06845 LINE N - SHELTER FIELD RUN	CONSTRUCTION ENGINEERING	1	LS	\$500.00	\$500.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
285	110-01001 LINE N - SHELTER FIELD RUN	MOBILIZATION AND DEMOBILIZATION	1	LS	\$1,200.00	\$1,200.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
286	202-02240 LINE N - SHELTER FIELD RUN	PAVEMENT REMOVAL	943	SYS	\$12.00	\$11,316.00	\$14.00	\$13,202.00	\$16.25	\$15,323.75
287	202-93615 LINE N - SHELTER FIELD RUN	CONCRETE, REMOVE	40	SYS	\$14.00	\$560.00	\$17.00	\$680.00	\$23.75	\$950.00
288	205-06933 LINE N - SHELTER FIELD RUN	TEMPORARY INLET PROTECTION	1	EACH	\$30.00	\$30.00	\$25.00	\$25.00	\$65.00	\$65.00
289	214-11796 LINE N - SHELTER FIELD RUN	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	250	SYS	\$6.00	\$1,500.00	\$1.00	\$250.00	\$12.50	\$3,125.00
290	301-FWR03 LINE N - SHELTER FIELD RUN	COMPACTED AGGREGATE NO. 53	240	TON	\$32.00	\$7,680.00	\$32.00	\$7,680.00	\$28.75	\$6,900.00
291	502-FWR01 LINE N - SHELTER FIELD RUN	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	943	SYS	\$46.00	\$43,378.00	\$51.00	\$48,093.00	\$56.25	\$53,043.75
292	604-06070 LINE N - SHELTER FIELD RUN	SIDEWALK, CONCRETE	10	SYS	\$65.00	\$650.00	\$60.00	\$600.00	\$78.75	\$787.50
293	604-06088 LINE N - SHELTER FIELD RUN	CURB RAMP, CONCRETE	1	SYS	\$135.00	\$135.00	\$1.00	\$1.00	\$187.50	\$187.50
294	604-FWR01 LINE N - SHELTER FIELD RUN	DETECTABLE WARNING SURFACES	1	EACH	\$450.00	\$450.00	\$1.00	\$1.00	\$325.00	\$325.00
295	610-04046 LINE N - SHELTER FIELD RUN	PCCP FOR APPROACHES, 6 IN.	30	SYS	\$70.00	\$2,100.00	\$65.00	\$1,950.00	\$81.25	\$2,437.50
296	611-00233 LINE N - SHELTER FIELD RUN	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00
297	621-FWR01 LINE N - SHELTER FIELD RUN	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	200	SYS	\$5.00	\$1,000.00	\$5.00	\$1,000.00	\$3.25	\$650.00
298	623-FWR19 LINE N - SHELTER FIELD RUN	TOPSOIL	20	TON	\$50.00	\$1,000.00	\$50.00	\$1,000.00	\$38.50	\$770.00
299	715-FWR LINE N - SHELTER FIELD RUN	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	500	LFT	\$10.00	\$5,000.00	\$13.00	\$6,500.00	\$13.25	\$6,625.00
300	715-94530 LINE N - SHELTER FIELD RUN	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$125.00
301	720-FWR30 LINE N - SHELTER FIELD RUN	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00
302	720-FWR37 LINE N - SHELTER FIELD RUN	CASTING -2X2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00
303	720-FWR38 LINE N - SHELTER FIELD RUN	CASTING-2X3" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$950.00	\$950.00	\$1,200.00	\$1,200.00	\$1,000.00	\$1,000.00
304	720-44000 LINE N - SHELTER FIELD RUN	CASTING, ADJUST TO GRADE	1	EACH	\$250.00	\$250.00	\$750.00	\$750.00	\$125.00	\$125.00
305	801-FWR01 LINE N - SHELTER FIELD RUN	MAINTENANCE OF TRAFFIC	1	LS	\$900.00	\$900.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
306	105-06845 LINE O - ETHEN COURT	CONSTRUCTION ENGINEERING	1	LS	\$500.00	\$500.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79
307	110-01001 LINE O - ETHEN COURT	MOBILIZATION AND DEMOBILIZATION	1	LS	\$1,000.00	\$1,000.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85
308	202-02240 LINE O - ETHEN COURT	PAVEMENT REMOVAL	665	SYS	\$12.00	\$7,980.00	\$14.00	\$9,310.00	\$16.25	\$10,806.25
309	202-93615 LINE O - ETHEN COURT	CONCRETE, REMOVE	11	SYS	\$14.00	\$154.00	\$17.00	\$187.00	\$23.75	\$261.25
310	205-06933 LINE O - ETHEN COURT	TEMPORARY INLET PROTECTION	1	EACH	\$30.00	\$30.00	\$25.00	\$25.00	\$65.00	\$65.00
311	214-11796 LINE O - ETHEN COURT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	250	SYS	\$6.00	\$1,500.00	\$1.00	\$250.00	\$12.50	\$3,125.00
312	301-FWR03 LINE O - ETHEN COURT	COMPACTED AGGREGATE NO. 53	170	TON	\$32.00	\$5,440.00	\$32.00	\$5,440.00	\$28.75	\$4,887.50
313	502-FWR01 LINE O - ETHEN COURT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	665	SYS	\$46.00	\$30,590.00	\$51.00	\$33,915.00	\$56.25	\$37,406.25
314	604-06070 LINE O - ETHEN COURT	SIDEWALK, CONCRETE	1	SYS	\$65.00	\$65.00	\$1.00	\$1.00	\$78.75	\$78.75

315	604-08086 LINE O - ETHEN COURT	CURB RAMP, CONCRETE	1	SYS	\$135.00	\$135.00	\$1.00	\$1.00	\$187.50	\$187.50	\$187.50
316	604-FWR01 LINE O - ETHEN COURT	DETECTABLE WARNING SURFACES	1	EACH	\$450.00	\$450.00	\$1.00	\$1.00	\$325.00	\$325.00	\$325.00
317	610-08446 LINE O - ETHEN COURT	PCCP FOR APPROACHES, 6 IN.	10	SYS	\$70.00	\$700.00	\$65.00	\$65.00	\$81.25	\$81.25	\$812.50
318	611-08233 LINE O - ETHEN COURT	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00	\$225.00
319	621-FWR01 LINE O - ETHEN COURT	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	115	SYS	\$5.00	\$575.00	\$5.00	\$5.00	\$3.25	\$3.25	\$373.75
320	623-FWR19 LINE O - ETHEN COURT	TOPSOIL	20	TON	\$50.00	\$1,000.00	\$50.00	\$50.00	\$38.50	\$38.50	\$770.00
321	715-FWR LINE O - ETHEN COURT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	345	LFT	\$10.00	\$3,450.00	\$13.00	\$13.00	\$4,485.00	\$13.25	\$4,571.25
322	715-94530 LINE O - ETHEN COURT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$125.00	\$125.00
323	720-FWR30 LINE O - ETHEN COURT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00	\$625.00
324	720-FWR37 LINE O - ETHEN COURT	CASTING -2x2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00	\$750.00
325	720-FWR38 LINE O - ETHEN COURT	CASTING-2x3" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$950.00	\$950.00	\$1,200.00	\$1,200.00	\$1,000.00	\$1,000.00	\$1,000.00
326	720-44000 LINE O - ETHEN COURT	CASTING, ADJUST TO GRADE	2	EACH	\$250.00	\$500.00	\$750.00	\$750.00	\$125.00	\$125.00	\$250.00
327	801-FWR01 LINE O - ETHEN COURT	MAINTENANCE OF TRAFFIC	1	LS	\$900.00	\$900.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09	\$2,358.09
328	105-06845 LINE P - CLARKS PASSAGE	CONSTRUCTION ENGINEERING	1	LS	\$800.00	\$800.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79	\$1,315.79
329	110-01001 LINE P - CLARKS PASSAGE	MOBILIZATION AND DEMOBILIZATION	1	LS	\$500.00	\$500.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85	\$13,091.85
330	202-02240 LINE P - CLARKS PASSAGE	PAVEMENT REMOVAL	1833	SYS	\$12.00	\$21,996.00	\$14.00	\$14.00	\$16.25	\$16.25	\$29,786.25
331	202-93615 LINE P - CLARKS PASSAGE	CONCRETE, REMOVE	62	SYS	\$14.00	\$868.00	\$17.00	\$17.00	\$23.75	\$23.75	\$1,472.50
332	205-06933 LINE P - CLARKS PASSAGE	TEMPORARY INLET PROTECTION	11	EACH	\$30.00	\$330.00	\$25.00	\$25.00	\$65.00	\$65.00	\$715.00
333	214-11796 LINE P - CLARKS PASSAGE	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	500	SYS	\$6.00	\$3,000.00	\$1.00	\$1.00	\$12.50	\$12.50	\$6,250.00
334	301-FWR03 LINE P - CLARKS PASSAGE	COMPACTED AGGREGATE NO. 53	480	TON	\$32.00	\$14,720.00	\$32.00	\$32.00	\$28.75	\$28.75	\$13,225.00
335	502-FWR01 LINE P - CLARKS PASSAGE	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-4 CURB, BACKFILL, AND ASPHALT PATCHING)	1833	SYS	\$46.00	\$84,318.00	\$51.00	\$51.00	\$56.25	\$56.25	\$103,106.25
336	604-06070 LINE P - CLARKS PASSAGE	SIDEWALK, CONCRETE	22	SYS	\$65.00	\$1,430.00	\$60.00	\$60.00	\$78.75	\$78.75	\$1,732.50
337	604-06086 LINE P - CLARKS PASSAGE	CURB RAMP, CONCRETE	1	SYS	\$135.00	\$135.00	\$1.00	\$1.00	\$187.50	\$187.50	\$187.50
338	604-FWR01 LINE P - CLARKS PASSAGE	DETECTABLE WARNING SURFACES	1	EACH	\$450.00	\$450.00	\$1.00	\$1.00	\$325.00	\$325.00	\$325.00
339	610-08446 LINE P - CLARKS PASSAGE	PCCP FOR APPROACHES, 6 IN.	45	SYS	\$70.00	\$3,150.00	\$65.00	\$65.00	\$81.25	\$81.25	\$3,656.25
340	611-08233 LINE P - CLARKS PASSAGE	MAILBOX ASSEMBLY, RESET DOUBLE	1	EACH	\$300.00	\$300.00	\$250.00	\$250.00	\$225.00	\$225.00	\$225.00
341	621-FWR01 LINE P - CLARKS PASSAGE	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	380	SYS	\$5.00	\$1,900.00	\$5.00	\$5.00	\$3.25	\$3.25	\$1,235.00
342	623-FWR19 LINE P - CLARKS PASSAGE	TOPSOIL	50	TON	\$50.00	\$2,500.00	\$50.00	\$50.00	\$38.50	\$38.50	\$1,925.00
343	715-FWR LINE P - CLARKS PASSAGE	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1129	LFT	\$10.00	\$11,290.00	\$13.00	\$13.00	\$14,677.00	\$13.25	\$14,959.25
344	715-94530 LINE P - CLARKS PASSAGE	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$200.00	\$200.00	\$250.00	\$250.00	\$125.00	\$125.00	\$125.00
345	720-FWR30 LINE P - CLARKS PASSAGE	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$850.00	\$850.00	\$625.00	\$625.00	\$625.00
346	720-FWR37 LINE P - CLARKS PASSAGE	CASTING -2x2" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$800.00	\$800.00	\$850.00	\$850.00	\$750.00	\$750.00	\$750.00
347	720-FWR38 LINE P - CLARKS PASSAGE	CASTING-2x3" CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$950.00	\$950.00	\$1,200.00	\$1,200.00	\$1,000.00	\$1,000.00	\$1,000.00
348	720-44000 LINE P - CLARKS PASSAGE	CASTING, ADJUST TO GRADE	2	EACH	\$250.00	\$500.00	\$750.00	\$750.00	\$125.00	\$125.00	\$250.00
349	801-FWR01 LINE P - CLARKS PASSAGE	MAINTENANCE OF TRAFFIC	1	LS	\$900.00	\$900.00	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09	\$2,358.09
350	105-06845 LINE O - MANHATTEN CIRCLE	CONSTRUCTION ENGINEERING	1	LS	\$500.00	\$500.00	\$9,000.00	\$9,000.00	\$1,315.79	\$1,315.79	\$1,315.79
351	110-01001 LINE O - MANHATTEN CIRCLE	MOBILIZATION AND DEMOBILIZATION	1	LS	\$800.00	\$800.00	\$9,000.00	\$9,000.00	\$13,091.85	\$13,091.85	\$13,091.85
352	202-02240 LINE O - MANHATTEN CIRCLE	PAVEMENT REMOVAL	672	SYS	\$12.00	\$8,064.00	\$14.00	\$14.00	\$16.25	\$16.25	\$10,920.00
353	202-93615 LINE O - MANHATTEN CIRCLE	CONCRETE, REMOVE	31	SYS	\$14.00	\$434.00	\$17.00	\$17.00	\$23.75	\$23.75	\$736.25
354	205-06933 LINE O - MANHATTEN CIRCLE	TEMPORARY INLET PROTECTION	2	EACH	\$30.00	\$60.00	\$25.00	\$25.00	\$65.00	\$65.00	\$130.00
355	214-11796 LINE O - MANHATTEN CIRCLE	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	250	SYS	\$6.00	\$1,500.00	\$1.00	\$1.00	\$12.50	\$12.50	\$3,125.00
356	301-FWR03 LINE O - MANHATTEN CIRCLE	COMPACTED AGGREGATE NO. 53	170	TON	\$32.00	\$5,440.00	\$32.00	\$32.00	\$28.75	\$28.75	\$4,887.50

399	202-93615 LINE S - ST. CLAIRS RETREAT	CONCRETE, REMOVE	125	SYS	\$17.00	\$2,125.00	\$23.75	\$2,968.75
400	205-06893 LINE S - ST. CLAIRS RETREAT	TEMPORARY INLET PROTECTION	2	EACH	\$25.00	\$50.00	\$65.00	\$130.00
401	214-11796 LINE S - ST. CLAIRS RETREAT	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	1000	SYS	\$1.00	\$1,000.00	\$12.50	\$12,500.00
402	301-FWR03 LINE S - ST. CLAIRS RETREAT	COMPACTED AGGREGATE NO. 53	500	TON	\$32.00	\$16,000.00	\$28.75	\$14,375.00
403	502-FWR01 LINE S - ST. CLAIRS RETREAT	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	2065	SYS	\$51.00	\$105,315.00	\$56.25	\$116,156.25
404	604-06070 LINE S - ST. CLAIRS RETREAT	SIDEWALK, CONCRETE	1	SYS	\$60.00	\$60.00	\$78.75	\$78.75
405	604-06086 LINE S - ST. CLAIRS RETREAT	CURB RAMP, CONCRETE	1	SYS	\$187.50	\$187.50	\$187.50	\$187.50
406	604-FWR01 LINE S - ST. CLAIRS RETREAT	DETECTABLE WARNING SURFACES	1	EACH	\$1.00	\$1.00	\$325.00	\$325.00
407	610-08446 LINE S - ST. CLAIRS RETREAT	PCCP FOR APPROACHES, 6 IN.	125	SYS	\$65.00	\$8,125.00	\$81.25	\$10,156.25
408	611-08233 LINE S - ST. CLAIRS RETREAT	MAILBOX ASSEMBLY, RESET DOUBLE	2	EACH	\$250.00	\$500.00	\$225.00	\$450.00
409	621-FWR01 LINE S - ST. CLAIRS RETREAT	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	420	SYS	\$5.00	\$2,100.00	\$3.25	\$1,365.00
410	623-FWR19 LINE S - ST. CLAIRS RETREAT	TOPSOIL	60	TON	\$50.00	\$3,000.00	\$38.50	\$2,310.00
411	715-FWR LINE S - ST. CLAIRS RETREAT	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1253	LFT	\$13.00	\$16,289.00	\$13.25	\$16,602.25
412	715-94530 LINE S - ST. CLAIRS RETREAT	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	1	EACH	\$250.00	\$250.00	\$125.00	\$125.00
413	720-FWR30 LINE S - ST. CLAIRS RETREAT	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	2	EACH	\$850.00	\$1,700.00	\$625.00	\$1,250.00
414	720-FWR37 LINE S - ST. CLAIRS RETREAT	CASTING-24X2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$850.00	\$850.00	\$750.00	\$750.00
415	720-FWR38 LINE S - ST. CLAIRS RETREAT	CASTING-24X2' ALLEY CASTING FURNISH & ADJUST TO GRADE	1	EACH	\$1,500.00	\$1,500.00	\$1,250.00	\$1,250.00
416	720-4000 LINE S - ST. CLAIRS RETREAT	CASTING, ADJUST TO GRADE	1	EACH	\$750.00	\$750.00	\$125.00	\$125.00
417	801-FWR01 LINE S - ST. CLAIRS RETREAT	MAINTENANCE OF TRAFFIC	1	LS	\$9,000.00	\$9,000.00	\$2,358.09	\$2,358.09
418	108-04289 LINE A - LINE S	FORCE ACCOUNT	100000	DOL	\$1.00	\$100,000.00	\$1.00	\$100,000.00



Notice of Award

Project: Woodland Lake Concrete Street Repairs Ph. II

Owner: City of Fort Wayne Board of Works

Resolution/Work Order #0784C

Bidder: Hipskind Concrete Corp

Bidder's Address: 5502 Mason Dr

Fort Wayne, IN 46809

You are notified that your Bid dated 5/23/2024 for the above Contract has been considered. You are the Successful Bidder and are awarded a Contract for Woodland Lake Concrete Street Repairs Ph. II

Improve the Woodland Lake neighborhood, Northwest Passage addition, and streets in Fallen Timbers Addition by removal and replacement of deteriorated concrete streets. Also, sidewalks and drive approaches will be reconstructed. New subsurface drainage will be installed and adjustment of existing castings. Finally, restoration of disturbed areas.

The Contract Price of your Contract is \$4,704,948.00 .

1 copy of the proposed Construction Contract (except Drawings) accompany this Notice of Award.

You must comply with the following conditions precedent within **[10]** days of the date you receive this Notice of Award.

1. Deliver to the Owner [1] fully executed counterparts of the Construction Contract.
2. Deliver with the executed Agreement the following documents:
 - a. Performance Bond
 - b. Payment Bond
 - c. Certificate of Insurance
 - d. Executed E-Verify Affidavit.
 - e. Executed Drug Policy Acknowledgement Form.
3. Deliver evidence of successful Bidder's Affirmative Action Plan; OR, executed City of Fort Wayne Affirmative Action Program document to City of Fort Wayne Vendor Compliance, Jessica.Bucher@cityoffortwayne.org.




Notice of Award


Failure to comply with these conditions within the time specified will entitle Owner to consider you in default, annul this Notice of Award, and declare your Bid security forfeited. Contractor will be allowed an additional 11 calendar days to submit Bonds.

Within thirty days after you comply with the above conditions, Owner will return to you one fully executed counterpart of the Agreement.

**CITY OF FORT WAYNE
BOARD OF PUBLIC WORKS**


Shan Gunawardena, Chair


Kumar Menon, Member


Chris Guerrero, Member

ATTEST:


Michelle Fulk-Vondran, Clerk

Date: 6-4-24

cc: Project Manager

AGREEMENT BETWEEN OWNER AND CONTRACTOR FOR CONSTRUCTION CONTRACT (STIPULATED PRICE)

Resolution/Work Order #0784C

This Agreement is by and between the City of Fort Wayne – Board of Public Works (“Owner”) and Hipkind Concrete Corp (“Contractor”).

Terms used in this Agreement have the meanings stated in the General Conditions and the Supplementary Conditions.

Owner and Contractor hereby agree as follows:

ARTICLE 1—WORK

1.01 Contractor shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows: **Improve the Woodland Lake neighborhood, Northwest Passage addition, and streets in Fallen Timbers Addition by removal and replacement of deteriorated concrete streets. Also, sidewalks and drive approaches will be reconstructed. New subsurface drainage will be installed and adjustment of existing castings. Finally, restoration of disturbed areas.**

ARTICLE 2—THE PROJECT

2.01 The Project, of which the Work under the Contract Documents is a part, is generally described as follows: **Woodland Lake Concrete Street Repairs Ph. II**

ARTICLE 3—ENGINEER

3.01 The part of the Project that pertains to the Work has been designed by **TRANSPORTATION ENGINEERING.**

ARTICLE 4—CONTRACT TIMES

4.01 *Time is of the Essence*

A. All time limits for Milestones, if any, Substantial Completion, and completion and readiness for final payment as stated in the Contract Documents are of the essence of the Contract.

4.02 *Contract Times: Dates*

A. The Work will be substantially complete on or before **7/18/2025**, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions on or before **7/25/2025.**

4.03 *Milestones*

- A. Parts of the Work must be substantially completed on or before the following Milestone(s):
1. Milestone 1 **[N/A]**
 2. Milestone 2 **[N/A]**
 3. Milestone 3 **[N/A]**

4.05 *Liquidated Damages*

- A. Contractor and Owner recognize that time is of the essence as stated in Paragraph 4.01 above and that Owner will suffer financial and other losses if the Work is not completed and Milestones not achieved within the Contract Times, as duly modified. The parties also recognize the delays, expense, and difficulties involved in proving, in a legal or arbitration proceeding, the actual loss suffered by Owner if the Work is not completed on time. Accordingly, instead of requiring any such proof, Owner and Contractor agree that as liquidated damages for delay (but not as a penalty):
1. *Substantial Completion:* Contractor shall pay Owner up to **\$1000** for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for Substantial Completion, until the Work is substantially complete.
 2. *Completion of Remaining Work:* After Substantial Completion, if Contractor shall neglect, refuse, or fail to complete the remaining Work within the Contract Times (as duly adjusted pursuant to the Contract) for completion and readiness for final payment, Contractor shall pay Owner up to **\$1000** for each day that expires after such time until the Work is completed and ready for final payment.
 3. *Milestones:* Contractor shall pay Owner up to **\$1000** for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for achievement of Milestone 1, until Milestone 1 is achieved, or until the time specified for Substantial Completion is reached, at which time the rate indicated in Paragraph 4.05.A.1 will apply, rather than the Milestone rate.
 4. Liquidated damages for failing to timely attain Milestones, Substantial Completion, and final completion are not additive, and will not be imposed concurrently.
- B. If Owner recovers liquidated damages for a delay in completion by Contractor, then such liquidated damages are Owner's sole and exclusive remedy for such delay, and Owner is precluded from recovering any other damages, whether actual, direct, excess, or consequential, for such delay, except for special damages (if any) specified in this Agreement.

ARTICLE 5—CONTRACT PRICE

- 5.01 Owner shall pay Contractor for completion of the Work in accordance with the Contract Documents, the amounts that follow, subject to adjustment under the Contract:
- A. For all Work, at the prices stated in Contractor's Bid, attached hereto as an exhibit.
 - B. Total of all unit prices **\$4,704,948.00.**

ARTICLE 6—PAYMENT PROCEDURES

6.01 *Submittal and Processing of Payments*

- A. Contractor shall submit Applications for Payment in accordance with Article 15 of the General Conditions. Applications for Payment will be processed by Engineer as provided in the General Conditions.

6.02 *Progress Payments; Retainage*

- A. Owner shall make progress payments on the basis of Contractor's Applications for Payment no more often than every 30 days during performance of the Work as provided in Paragraph 6.02.A.1 below, provided that such Applications for Payment have been submitted in a timely manner and otherwise meet the requirements of the Contract. All such payments will be measured by the Schedule of Values established as provided in the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no Schedule of Values, as provided elsewhere in the Contract.
 - 1. Prior to Substantial Completion, progress payments will be made in an amount equal to the percentage indicated below but, in each case, less the aggregate of payments previously made and less such amounts as Owner may withhold, including but not limited to liquidated damages, in accordance with the Contract.
 - a. 95 percent of the value of the Work completed (with the balance being retainage).
 - b. 95 percent of cost of materials and equipment not incorporated in the Work (with the balance being retainage).

6.03 *Final Payment*

- A. Upon final completion and acceptance of the Work, Owner shall pay the remainder of the Contract Price in accordance with Paragraph 15.06 of the General Conditions.

ARTICLE 7—CONTRACT DOCUMENTS

7.01 *Contents*

- A. The Contract Documents consist of all of the following:
 - 1. This Agreement.

2. Bonds:
 - a. Performance bond (together with power of attorney).
 - b. Payment bond (together with power of attorney).
 3. General Conditions.
 4. Supplementary Conditions.
 5. Specifications as listed in the table of contents of the project manual (copy of list attached).
 6. Drawings (not attached but incorporated by reference) consisting of **22** sheets with each sheet bearing the following general title: **Woodland Lake Concrete Street Repair, Ph II**
 7. Addenda (numbers **[N/A]** to **[N/A]**, inclusive).
 8. Exhibits to this Agreement (enumerated as follows):
 - a. Drug Policy Acknowledgement Form (Project Bids under \$150,000.00) or Written copy of Contractors Drug Policy (Project Bids over \$150,000.00)
 - b. E-Verify Affidavit
 - c. Escrow account agreement
 9. The following which may be delivered or issued on or after the Effective Date of the Contract and are not attached hereto:
 - a. Notice to Proceed.
 - b. Work Change Directives.
 - c. Change Orders.
 - d. Field Orders.
 - e. Warranty Bond, if any.
- B. The Contract Documents listed in Paragraph 7.01.A are attached to this Agreement (except as expressly noted otherwise above).
- C. There are no Contract Documents other than those listed above in this Article 7.
- D. The Contract Documents may only be amended, modified, or supplemented as provided in the Contract.

ARTICLE 8—REPRESENTATIONS, CERTIFICATIONS, AND STIPULATIONS

8.01 *Contractor's Representations*

- A. In order to induce Owner to enter into this Contract, Contractor makes the following representations:
1. Contractor has examined and carefully studied the Contract Documents, including Addenda.
 2. Contractor has visited the Site, conducted a thorough visual examination of the Site and adjacent areas, and become familiar with the general, local, and Site conditions that may affect cost, progress, and performance of the Work.
 3. Contractor is familiar with all Laws and Regulations that may affect cost, progress, and performance of the Work.
 4. Contractor has carefully studied the reports of explorations and tests of subsurface conditions at or adjacent to the Site and the drawings of physical conditions relating to existing surface or subsurface structures at the Site that have been identified in the Supplementary Conditions, with respect to the Technical Data in such reports and drawings.
 5. Contractor has carefully studied the reports and drawings relating to Hazardous Environmental Conditions, if any, at or adjacent to the Site that have been identified in the Supplementary Conditions, with respect to Technical Data in such reports and drawings.
 6. Contractor has considered the information known to Contractor itself; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Contract Documents; and the Technical Data identified in the Supplementary Conditions or by definition, with respect to the effect of such information, observations, and Technical Data on (a) the cost, progress, and performance of the Work; (b) the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor; and (c) Contractor's safety precautions and programs.
 7. Based on the information and observations referred to in the preceding paragraph, Contractor agrees that no further examinations, investigations, explorations, tests, studies, or data are necessary for the performance of the Work at the Contract Price, within the Contract Times, and in accordance with the other terms and conditions of the Contract.
 8. Contractor is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Contract Documents.

9. Contractor has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Contractor has discovered in the Contract Documents, and of discrepancies between Site conditions and the Contract Documents, and the written resolution thereof by Engineer is acceptable to Contractor.
10. The Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.
11. Contractor's entry into this Contract constitutes an incontrovertible representation by Contractor that without exception all prices in the Agreement are premised upon performing and furnishing the Work required by the Contract Documents.

8.02 *Contractor's Certifications*

- A. Contractor certifies that it has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for or in executing the Contract. For the purposes of this Paragraph 8.02:
 1. "corrupt practice" means the offering, giving, receiving, or soliciting of anything of value likely to influence the action of a public official in the bidding process or in the Contract execution;
 2. "fraudulent practice" means an intentional misrepresentation of facts made (a) to influence the bidding process or the execution of the Contract to the detriment of Owner, (b) to establish Bid or Contract prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;
 3. "collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish Bid prices at artificial, non-competitive levels; and
 4. "coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the execution of the Contract.

8.03 *Standard General Conditions*

- A. Owner stipulates that if the General Conditions that are made a part of this Contract are EJCDC® C-700, Standard General Conditions for the Construction Contract (2018), published by the Engineers Joint Contract Documents Committee, and if Owner is the party that has furnished said General Conditions, then Owner has plainly shown all modifications to the standard wording of such published document to the Contractor, through a process such as highlighting or "track changes" (redline/strikeout), or in the Supplementary Conditions.

ARTICLE 9—MISCELLANEOUS

9.01 Terms

Terms used in this Agreement will have the meanings stated in the General Conditions

9.02 Severability

Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon Owner and Contractor, who agree that the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.

9.03 Emerging Business Enterprise(EBE) Participation

EBE Retainage Requirements – If the Contractor is in compliance with the provisions of the construction Contract the Owner will make payments for such work performed and completed. Pursuant to Executive Order 90-01 (amended 5-8-06); the Owner will retain five percent (5%) of the Contract Price to ensure compliance with the EBE participation requirements. Upon final inspection and acceptance of the Work, and determination by the Fort Wayne Board of Public Works that the Contractor has made a good faith effort to subcontract ten percent (10%) of the Contract Price to emerging business enterprises, the Contractor will be paid in full.

In the event there is a determination that good faith compliance with these EBE participation requirements has not occurred, appropriate reduction in the final payment pursuant to paragraph 9.03.E will be made.

If the Contract Price is in excess of \$200,000, the contract will be subject to the standard Board of Public Works escrow agreement. However, payments to the Contractor are not to exceed 95% of the total Contract Price until the Owner has verified that the Contractor has made good faith efforts to attain the 10% EBE goal stipulated in here within. Payment of the final 5% of the total Contract Price will be dependent upon acceptance of the Work, in accordance with Paragraph 15.06 of the General Conditions, and good faith efforts to comply with these EBE participation requirements; subject to reduction in the event of non-compliance as provided in paragraph 9.03.E.

- A. Request for Waiver – If, at the time final payment application is made, Contractor has not attained the ten percent (10%) EBE goal, Contractor shall file with the final payment application a “Request for Waiver.” Said Request for Waiver shall contain a written description of the efforts taken by Contractor to attain the ten percent (10%) EBE goal.
- B. Determination of Waiver Requests – The Vendor Compliance Department of the City of Fort Wayne shall examine all Requests for Waiver to determine if Contractor’s efforts constitute good faith efforts to attain such goal and shall submit recommendations concerning said requests for Waiver for the final determination of the Board of Public Works of the City of Fort Wayne.
- C. Good Faith Efforts. – In determining whether or not the Contractor used “good faith” efforts, the following shall be considered:

1. Whether the contract can be subdivided as determined by the Engineer and Administrator of Contract Compliance;
 2. Availability of certified EBE businesses to participate as subcontractors;
 3. Non-competitive price quotes received from EBE firms. The Board of Public Works' determination for granting a reduction or waiver of the goal because of higher quotes from EBE firms will be based on factors that include, but are not limited to the following:
 - a. The Engineer's estimate for the work under a specific contract;
 - b. The Contractor's own estimate for the work under the subcontract;
 - c. An average of the valid prices quoted for the subcontract;
 - d. Demonstrated increase in other contract costs as a result of sub-contracting to EBE firm(s).
 4. Documented measures taken by the Contractor to comply with the EBE participation goal;
 5. EBE subcontractor failed to fulfill their obligation in regard to the time delivery of goods and/or services. Also in regards to the quality of the goods and/or services set forth in the bid specifications.
 6. Such other matters as the Board of Public Works deems relevant.
- D. Consequences of Noncompliance – In the event the Board of Public Works approves a recommendation that Contractor failed to make good faith efforts at compliance, the Contract Price shall be reduced by the amount calculated as the difference between the EBE participation goal of 10% and the actual participation level met by the Contractor, but in no case shall it be reduced by more than 5%. Said amount shall be added to the City of Fort Wayne EBE Bond Guarantee Fund and Contractor agrees to accept the reduced amount as full payment under the terms of his/her Contract.
- E. Waiver Approved – In the event the Board of Public Works determines that a good faith effort to comply with these EBE participation requirements has been made, the Contract Price shall not be reduced, and the balance owing to the Contractor shall be paid in full.

ACKNOWLEDGMENT

STATE OF INDIANA)
 SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named _____ who being by me first duly sworn upon his oath says that he is the _____ of _____ and as such duly authorized to execute the foregoing instrument and acknowledged the same as the voluntary act and deed of _____ for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

ACKNOWLEDGMENT

STATE OF INDIANA)
 SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named **Sharon Tucker, Shan Gunawardena, Kumar Menon, Chris Guerrero, and Michelle Fulk-Vondran**, by me personally known, who being by me duly sworn said that they are respectively the **Mayor** of the **City of Fort Wayne**, and **Chairman, Members, and Clerk** of the **Board of Public Works** of the **City of Fort Wayne, Indiana**, and that they signed said instrument on behalf of the City of Fort Wayne, Indiana, with full authority so to do and acknowledge said instrument to be in the voluntary act and deed of said **City** for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

IN WITNESS WHEREOF, Owner and Contractor have signed this Agreement (Contract/Resolution Number **0784C**).

This Agreement will be effective on _____ (which is the Effective Date of the Agreement).

CONTRACTOR

OWNER

Hipskind Concrete Corp

CITY OF FORT WAYNE

BY: _____

BY: _____

Print Name _____

SHARON TUCKER, MAYOR

TITLE: _____

BOARD OF PUBLIC WORKS

DATE: _____

BY: _____

(Date signed by Contractor)

SHAN GUNAWARDENA, CHAIR

Address for giving notices:

BY: _____

KUMAR MENON, MEMBER

BY: _____

CHRIS GUERRERO, MEMBER

ATTEST: _____

MICHELLE FULK-VONDRAN, CLERK

DATE: _____

(Date signed by Board)

0784C - Woodland Lake Concrete Street Repairs Ph. II (#9105987)

Owner: Public Works

Solicitor: Fort Wayne IN, City of

05/23/2024 02:00 PM EDT

				HIPSKIND CONCRETE CORP				
Section	Titl	Line Item	Item Code	Item Description	UofM	Quantity	Unit Price	Extension
WOODLAND LAKE CONCRETE STREET REPAIRS PH. II								\$4,604,948.00
		1	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
		2	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
		3	202-	PAVEMENT REMOVAL	SYS	3333	\$14.00	\$46,662.00
		4	202-	CONCRETE, REMOVE	SYS	105	\$17.00	\$1,785.00
		5	205-	TEMPORARY INLET PROTECTION	EACH	4	\$25.00	\$100.00
		6	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
		7	301-	COMPACTED AGGREGATE NO. 53	TON	925	\$32.00	\$29,600.00
		8	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	3333	\$51.00	\$169,983.00
		9	604-	SIDEWALK, CONCRETE	SYS	20	\$60.00	\$1,200.00
		10	604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
		11	604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
		12	610-	PCCP FOR APPROACHES, 6 IN.	SYS	75	\$65.00	\$4,875.00
		13	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	4	\$250.00	\$1,000.00
		14	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	740	\$5.00	\$3,700.00
		15	623-	TOPSOIL	TON	120	\$50.00	\$6,000.00
		16	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	2222	\$13.00	\$28,886.00
		17	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	2	\$250.00	\$500.00
		18	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		19	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		20	720-	CASTING, ADJUST TO GRADE	EACH	4	\$750.00	\$3,000.00
		21	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
		22	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
		23	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
		24	202-	PAVEMENT REMOVAL	SYS	1790	\$14.00	\$25,060.00
		25	202-	CONCRETE, REMOVE	SYS	170	\$17.00	\$2,890.00
		26	205-	TEMPORARY INLET PROTECTION	EACH	4	\$25.00	\$100.00
		27	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
		28	301-	COMPACTED AGGREGATE NO. 53	TON	630	\$32.00	\$20,160.00
		29	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1790	\$51.00	\$91,290.00
		30	604-	SIDEWALK, CONCRETE	SYS	60	\$60.00	\$3,600.00
		31	604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
		32	604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
		33	610-	PCCP FOR APPROACHES, 6 IN.	SYS	100	\$65.00	\$6,500.00
		34	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	2	\$250.00	\$500.00
		35	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	400	\$5.00	\$2,000.00
		36	623-	TOPSOIL	TON	62	\$50.00	\$3,100.00
		37	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1200	\$13.00	\$15,600.00
		38	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
		39	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		40	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		41	720-	CASTING, ADJUST TO GRADE	EACH	4	\$750.00	\$3,000.00
		42	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
		43	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
		44	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
		45	202-	PAVEMENT REMOVAL	SYS	4085	\$14.00	\$57,190.00
		46	202-	CONCRETE, REMOVE	SYS	287	\$17.00	\$4,879.00
		47	205-	TEMPORARY INLET PROTECTION	EACH	4	\$25.00	\$100.00
		48	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	4000	\$1.00	\$4,000.00
		49	301-	COMPACTED AGGREGATE NO. 53	TON	930	\$32.00	\$29,760.00
		50	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	4085	\$51.00	\$208,335.00
		51	604-	SIDEWALK, CONCRETE	SYS	62	\$60.00	\$3,720.00
		52	604-	CURB RAMP, CONCRETE	SYS	25	\$180.00	\$4,500.00
		53	604-	DETECTABLE WARNING SURFACES	EACH	3	\$450.00	\$1,350.00
		54	610-	PCCP FOR APPROACHES, 6 IN.	SYS	200	\$65.00	\$13,000.00
		55	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	3	\$250.00	\$750.00
		56	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1000	\$5.00	\$5,000.00
		57	623-	TOPSOIL	TON	200	\$50.00	\$10,000.00
		58	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	2725	\$13.00	\$35,425.00
		59	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	4	\$250.00	\$1,000.00
		60	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		61	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
		62	720-	CASTING, ADJUST TO GRADE	EACH	4	\$750.00	\$3,000.00
		63	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
		64	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
		65	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
		66	202-	PAVEMENT REMOVAL	SYS	676	\$14.00	\$9,464.00
		67	202-	CONCRETE, REMOVE	SYS	50	\$17.00	\$850.00
		68	205-	TEMPORARY INLET PROTECTION	EACH	1	\$25.00	\$25.00
		69	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	300	\$1.00	\$300.00
		70	301-	COMPACTED AGGREGATE NO. 53	TON	160	\$32.00	\$5,120.00
		71	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	676	\$51.00	\$34,476.00
		72	604-	SIDEWALK, CONCRETE	SYS	1	\$1.00	\$1.00
		73	604-	CURB RAMP, CONCRETE	SYS	1	\$1.00	\$1.00
		74	604-	DETECTABLE WARNING SURFACES	EACH	1	\$1.00	\$1.00
		75	610-	PCCP FOR APPROACHES, 6 IN.	SYS	50	\$65.00	\$3,250.00
		76	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
		77	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	110	\$5.00	\$550.00
		78	623-	TOPSOIL	TON	20	\$50.00	\$1,000.00
		79	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	320	\$13.00	\$4,160.00

80	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
81	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
82	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
83	720-	CASTING, ADJUST TO GRADE	EACH	1	\$750.00	\$750.00
84	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
85	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
86	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
87	202-	PAVEMENT REMOVAL	SYS	1662	\$14.00	\$23,268.00
88	202-	CONCRETE, REMOVE	SYS	199	\$17.00	\$3,383.00
89	205-	TEMPORARY INLET PROTECTION	EACH	1	\$25.00	\$25.00
90	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
91	301-	COMPACTED AGGREGATE NO. 53	TON	400	\$32.00	\$12,800.00
92	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1662	\$51.00	\$84,762.00
93	604-	SIDEWALK, CONCRETE	SYS	62	\$60.00	\$3,720.00
94	604-	CURB RAMP, CONCRETE	SYS	12	\$180.00	\$2,160.00
95	604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
96	610-	PCCP FOR APPROACHES, 6 IN.	SYS	125	\$65.00	\$8,125.00
97	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	2	\$250.00	\$500.00
98	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	320	\$5.00	\$1,600.00
99	623-	TOPSOIL	TON	60	\$50.00	\$3,000.00
100	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	950	\$13.00	\$12,350.00
101	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	2	\$250.00	\$500.00
102	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
103	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
104	720-	CASTING, ADJUST TO GRADE	EACH	1	\$750.00	\$750.00
105	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
106	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
107	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
108	202-	PAVEMENT REMOVAL	SYS	8696	\$14.00	\$121,744.00
109	202-	CONCRETE, REMOVE	SYS	450	\$17.00	\$7,650.00
110	205-	TEMPORARY INLET PROTECTION	EACH	10	\$25.00	\$250.00
111	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	4500	\$1.00	\$4,500.00
112	301-	COMPACTED AGGREGATE NO. 53	TON	2100	\$32.00	\$67,200.00
113	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	8696	\$51.00	\$443,496.00
114	604-	SIDEWALK, CONCRETE	SYS	100	\$60.00	\$6,000.00
115	604-	CURB RAMP, CONCRETE	SYS	100	\$180.00	\$18,000.00
116	604-	DETECTABLE WARNING SURFACES	EACH	10	\$450.00	\$4,500.00
117	610-	PCCP FOR APPROACHES, 6 IN.	SYS	250	\$65.00	\$16,250.00
118	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	5	\$250.00	\$1,250.00
119	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	2000	\$5.00	\$10,000.00
120	623-	TOPSOIL	TON	320	\$50.00	\$16,000.00
121	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	5800	\$13.00	\$75,400.00
122	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	2	\$250.00	\$500.00
123	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
124	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	5	\$850.00	\$4,250.00
125	720-	CASTING, ADJUST TO GRADE	EACH	10	\$750.00	\$7,500.00
126	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
127	808-	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT	54	\$100.00	\$5,400.00
128	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
129	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
130	202-	PAVEMENT REMOVAL	SYS	1365	\$14.00	\$19,110.00
131	202-	CONCRETE, REMOVE	SYS	85	\$17.00	\$1,445.00
132	205-	TEMPORARY INLET PROTECTION	EACH	2	\$25.00	\$50.00
133	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
134	301-	COMPACTED AGGREGATE NO. 53	TON	320	\$32.00	\$10,240.00
135	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1365	\$51.00	\$69,615.00
136	604-	SIDEWALK, CONCRETE	SYS	25	\$60.00	\$1,500.00
137	604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
138	604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
139	610-	PCCP FOR APPROACHES, 6 IN.	SYS	50	\$65.00	\$3,250.00
140	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
141	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	300	\$5.00	\$1,500.00
142	623-	TOPSOIL	TON	40	\$50.00	\$2,000.00
143	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	720	\$13.00	\$9,360.00
144	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
145	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
146	720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
147	720-	CASTING, ADJUST TO GRADE	EACH	2	\$750.00	\$1,500.00
148	801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
149	105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
150	110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
151	202-	PAVEMENT REMOVAL	SYS	650	\$14.00	\$9,100.00
152	202-	CONCRETE, REMOVE	SYS	85	\$17.00	\$1,445.00
153	205-	TEMPORARY INLET PROTECTION	EACH	2	\$25.00	\$50.00
154	214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	250	\$1.00	\$250.00
155	301-	COMPACTED AGGREGATE NO. 53	TON	140	\$32.00	\$4,480.00
156	502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	650	\$51.00	\$33,150.00
157	604-	SIDEWALK, CONCRETE	SYS	10	\$60.00	\$600.00
158	604-	CURB RAMP, CONCRETE	SYS	1	\$180.00	\$180.00
159	604-	DETECTABLE WARNING SURFACES	EACH	1	\$450.00	\$450.00
160	610-	PCCP FOR APPROACHES, 6 IN.	SYS	25	\$65.00	\$1,625.00
161	611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
162	621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	100	\$5.00	\$500.00
163	623-	TOPSOIL	TON	10	\$50.00	\$500.00
164	715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	433	\$13.00	\$5,629.00
165	715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
166	720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00

167 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
168 720-	CASTING, ADJUST TO GRADE	EACH	1	\$750.00	\$750.00
169 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
170 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
171 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
172 202-	PAVEMENT REMOVAL	SYS	1500	\$14.00	\$21,000.00
173 202-	CONCRETE, REMOVE	SYS	205	\$17.00	\$3,485.00
174 205-	TEMPORARY INLET PROTECTION	EACH	2	\$25.00	\$50.00
175 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
176 301-	COMPACTED AGGREGATE NO. 53	TON	440	\$32.00	\$14,080.00
177 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1500	\$51.00	\$76,500.00
178 604-	SIDEWALK, CONCRETE	SYS	45	\$60.00	\$2,700.00
179 604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
180 604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
181 610-	PCCP FOR APPROACHES, 6 IN.	SYS	150	\$65.00	\$9,750.00
182 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	2	\$250.00	\$500.00
183 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	350	\$5.00	\$1,750.00
184 623-	TOPSOIL	TON	60	\$50.00	\$3,000.00
185 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1000	\$13.00	\$13,000.00
186 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	2	\$250.00	\$500.00
187 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
188 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
189 720-	CASTING, ADJUST TO GRADE	EACH	6	\$750.00	\$4,500.00
190 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
191 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
192 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
193 202-	PAVEMENT REMOVAL	SYS	1768	\$14.00	\$24,752.00
194 202-	CONCRETE, REMOVE	SYS	130	\$17.00	\$2,210.00
195 205-	TEMPORARY INLET PROTECTION	EACH	3	\$25.00	\$75.00
196 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
197 301-	COMPACTED AGGREGATE NO. 53	TON	460	\$32.00	\$14,720.00
198 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1768	\$51.00	\$90,168.00
199 604-	SIDEWALK, CONCRETE	SYS	45	\$60.00	\$2,700.00
200 604-	CURB RAMP, CONCRETE	SYS	25	\$180.00	\$4,500.00
201 604-	DETECTABLE WARNING SURFACES	EACH	4	\$450.00	\$1,800.00
202 610-	PCCP FOR APPROACHES, 6 IN.	SYS	100	\$65.00	\$6,500.00
203 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	2	\$250.00	\$500.00
204 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	600	\$5.00	\$3,000.00
205 623-	TOPSOIL	TON	100	\$50.00	\$5,000.00
206 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1200	\$13.00	\$15,600.00
207 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
208 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
209 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
210 720-	CASTING, ADJUST TO GRADE	EACH	3	\$750.00	\$2,250.00
211 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
212 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
213 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
214 202-	PAVEMENT REMOVAL	SYS	642	\$14.00	\$8,988.00
215 202-	CONCRETE, REMOVE	SYS	70	\$17.00	\$1,190.00
216 205-	TEMPORARY INLET PROTECTION	EACH	1	\$25.00	\$25.00
217 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$2.00	\$1,000.00
218 301-	COMPACTED AGGREGATE NO. 53	TON	160	\$32.00	\$5,120.00
219 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	642	\$51.00	\$32,742.00
220 604-	SIDEWALK, CONCRETE	SYS	10	\$60.00	\$600.00
221 604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
222 604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
223 610-	PCCP FOR APPROACHES, 6 IN.	SYS	50	\$65.00	\$3,250.00
224 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
225 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	110	\$5.00	\$550.00
226 623-	TOPSOIL	TON	20	\$50.00	\$1,000.00
227 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	310	\$13.00	\$4,030.00
228 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
229 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
230 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
231 720-	CASTING, ADJUST TO GRADE	EACH	1	\$750.00	\$750.00
232 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
233 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
234 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
235 202-	PAVEMENT REMOVAL	SYS	1100	\$14.00	\$15,400.00
236 202-	CONCRETE, REMOVE	SYS	145	\$17.00	\$2,465.00
237 205-	TEMPORARY INLET PROTECTION	EACH	2	\$25.00	\$50.00
238 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
239 301-	COMPACTED AGGREGATE NO. 53	TON	275	\$32.00	\$8,800.00
240 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1100	\$51.00	\$56,100.00
241 604-	SIDEWALK, CONCRETE	SYS	35	\$60.00	\$2,100.00
242 604-	CURB RAMP, CONCRETE	SYS	10	\$180.00	\$1,800.00
243 604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
244 610-	PCCP FOR APPROACHES, 6 IN.	SYS	100	\$65.00	\$6,500.00
245 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
246 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	300	\$5.00	\$1,500.00
247 623-	TOPSOIL	TON	40	\$50.00	\$2,000.00
248 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	610	\$13.00	\$7,930.00
249 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
250 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
251 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
252 720-	CASTING, ADJUST TO GRADE	EACH	2	\$750.00	\$1,500.00
253 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00

254 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
255 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
256 202-	PAVEMENT REMOVAL	SYS	8428	\$14.00	\$117,992.00
257 202-	CONCRETE, REMOVE	SYS	242	\$17.00	\$4,114.00
258 205-	TEMPORARY INLET PROTECTION	EACH	18	\$25.00	\$450.00
259 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	4000	\$1.00	\$4,000.00
260 301-	COMPACTED AGGREGATE NO. 53	TON	2100	\$32.00	\$67,200.00
261 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	8428	\$51.00	\$429,828.00
262 604-	SIDEWALK, CONCRETE	SYS	72	\$60.00	\$4,320.00
263 604-	CURB RAMP, CONCRETE	SYS	20	\$180.00	\$3,600.00
264 604-	DETECTABLE WARNING SURFACES	EACH	2	\$450.00	\$900.00
265 610-	PCCP FOR APPROACHES, 6 IN.	SYS	150	\$65.00	\$9,750.00
266 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
267 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1625	\$5.00	\$8,125.00
268 623-	TOPSOIL	TON	190	\$50.00	\$9,500.00
269 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	4865	\$13.00	\$63,245.00
270 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	2	\$250.00	\$500.00
271 715-	PIPE- 12" RCP, CLASS III	LFT	36	\$195.00	\$7,020.00
272 720-	INLET- PRECAST 30" ROUND INLET	EACH	2	\$3,500.00	\$7,000.00
273 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
274 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	5	\$850.00	\$4,250.00
275 720-	CASTING-2'x2' ALLEY CASTING FURNISH & ADJUST TO GRADE	EACH	2	\$1,500.00	\$3,000.00
276 720-	CASTING, ADJUST TO GRADE	EACH	18	\$750.00	\$13,500.00
277 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
278 805-	ROADWAY SIGNAL LOOP	EACH	8	\$1,500.00	\$12,000.00
279 805-	SIGNAL DETECTOR HOUSING	EACH	2	\$3,000.00	\$6,000.00
280 808-	LINE, MULT-COMPONENT, SOLID, WHITE, 4 IN.	LFT	60	\$100.00	\$6,000.00
281 808-	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT	28	\$24.00	\$672.00
282 808-	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH	1	\$1,500.00	\$1,500.00
283 808-	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	EACH	1	\$1,500.00	\$1,500.00
284 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
285 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
286 202-	PAVEMENT REMOVAL	SYS	943	\$14.00	\$13,202.00
287 202-	CONCRETE, REMOVE	SYS	40	\$17.00	\$680.00
288 205-	TEMPORARY INLET PROTECTION	EACH	1	\$25.00	\$25.00
289 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	250	\$1.00	\$250.00
290 301-	COMPACTED AGGREGATE NO. 53	TON	240	\$32.00	\$7,680.00
291 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	943	\$51.00	\$48,093.00
292 604-	SIDEWALK, CONCRETE	SYS	10	\$60.00	\$600.00
293 604-	CURB RAMP, CONCRETE	SYS	1	\$1.00	\$1.00
294 604-	DETECTABLE WARNING SURFACES	EACH	1	\$1.00	\$1.00
295 610-	PCCP FOR APPROACHES, 6 IN.	SYS	30	\$65.00	\$1,950.00
296 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
297 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	200	\$5.00	\$1,000.00
298 623-	TOPSOIL	TON	20	\$50.00	\$1,000.00
299 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	500	\$13.00	\$6,500.00
300 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
301 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
302 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
303 720-	CASTING-2'x3' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$1,200.00	\$1,200.00
304 720-	CASTING, ADJUST TO GRADE	EACH	1	\$750.00	\$750.00
305 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
306 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
307 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
308 202-	PAVEMENT REMOVAL	SYS	665	\$14.00	\$9,310.00
309 202-	CONCRETE, REMOVE	SYS	11	\$17.00	\$187.00
310 205-	TEMPORARY INLET PROTECTION	EACH	1	\$25.00	\$25.00
311 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	250	\$1.00	\$250.00
312 301-	COMPACTED AGGREGATE NO. 53	TON	170	\$32.00	\$5,440.00
313 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	665	\$51.00	\$33,915.00
314 604-	SIDEWALK, CONCRETE	SYS	1	\$1.00	\$1.00
315 604-	CURB RAMP, CONCRETE	SYS	1	\$1.00	\$1.00
316 604-	DETECTABLE WARNING SURFACES	EACH	1	\$1.00	\$1.00
317 610-	PCCP FOR APPROACHES, 6 IN.	SYS	10	\$65.00	\$650.00
318 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00
319 621-	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	115	\$5.00	\$575.00
320 623-	TOPSOIL	TON	20	\$50.00	\$1,000.00
321 715-FWR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	345	\$13.00	\$4,485.00
322 715-	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)	EACH	1	\$250.00	\$250.00
323 720-	CASTING-24" SOLID STORM CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
324 720-	CASTING -2'x2' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$850.00	\$850.00
325 720-	CASTING-2'x3' CURB & GUTTER CASTING FURNISH & ADJUST TO GRADE	EACH	1	\$1,200.00	\$1,200.00
326 720-	CASTING, ADJUST TO GRADE	EACH	2	\$750.00	\$1,500.00
327 801-	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
328 105-	CONSTRUCTION ENGINEERING	LS	1	\$9,000.00	\$9,000.00
329 110-	MOBILIZATION AND DEMOBILIZATION	LS	1	\$9,000.00	\$9,000.00
330 202-	PAVEMENT REMOVAL	SYS	1833	\$14.00	\$25,662.00
331 202-	CONCRETE, REMOVE	SYS	62	\$17.00	\$1,054.00
332 205-	TEMPORARY INLET PROTECTION	EACH	11	\$25.00	\$275.00
333 214-	GEOGRID, TYPE IB (INCLUDES EXCAVATION, TX160)	SYS	500	\$1.00	\$500.00
334 301-	COMPACTED AGGREGATE NO. 53	TON	460	\$32.00	\$14,720.00
335 502-	PCCP, 7 IN. WITH MONOLITHIC CURB (INCLUDE 1-A CURB, BACKFILL, AND ASPHALT PATCHING)	SYS	1833	\$51.00	\$93,483.00
336 604-	SIDEWALK, CONCRETE	SYS	22	\$60.00	\$1,320.00
337 604-	CURB RAMP, CONCRETE	SYS	1	\$1.00	\$1.00
338 604-	DETECTABLE WARNING SURFACES	EACH	1	\$1.00	\$1.00
339 610-	PCCP FOR APPROACHES, 6 IN.	SYS	45	\$65.00	\$2,925.00
340 611-	MAILBOX ASSEMBLY, RESET DOUBLE	EACH	1	\$250.00	\$250.00

Drug Policy Acknowledgement Form

Contractor acknowledges the City of Fort Wayne has in place a Drug and Alcohol Policy that applies to any Contractor doing business with the City. A copy of this policy is available for inspection on the City of Fort Wayne website at: <http://www.cityoffortwayne.org/purchasing-home.html>. As a condition of being awarded any contract, the successful bidder shall sign this Drug Policy Acknowledgement and agree to be bound by those provisions of the policy that may be applicable. A copy of this form will be retained by the City of Fort Wayne.

The undersigned, on behalf of the Contractor deposes and states that the Contractor acknowledges the City of Fort Wayne's Alcohol and Drug Policy.

Name of Company

By: _____

Name and Title

E-Verify Affidavit

Pursuant to Indiana Code 22-5-1.7, Contractor agrees and shall enroll in and verify the work eligibility status of all newly hired employees of the contractor through the E-Verify program. E-Verify means the electronic verification of work authorization program of the Illegal Immigration Reform and Immigration Responsibility Act of 1996 (P.L. 104-208). Division C, Title IV, s.403(a), as amended, operated by the United States Department of Homeland Security or a successor work authorization program designated by the United States Department of Homeland Security or other federal agency authorized to verify the work authorization status of newly hired employees under the Immigration Reform and Control Act of 1986 (P.L. 99-603). Contractor is not required to verify the work eligibility status of all newly hired employees of Contractor through the E-verify program if the E-Verify program no longer exists.

The undersigned, on behalf of the Contractor, being first duly sworn, deposes and states that the Contractor does not knowingly employ an unauthorized alien. The undersigned further affirms that, prior to entering into its contract with the City, the undersigned Contractor will enroll in and agrees to verify the work eligibility status of all its newly hired employees through the E-Verify program.

Name of Company

By: _____
Title

ACKNOWLEDGEMENT

STATE OF INDIANA)
) SS
COUNTY OF ALLEN)

Before me, a Notary Public, in and for said State and County, personally appeared the within named Company by Name, Title, who being first duly sworn upon his/her oath states that he/she is a duly authorized agent of the Contractor, and as such duly authorized to execute the foregoing Declaration, and acknowledged the same as his/her voluntary act and deed.

WITNESS my hand and seal this _____ day of _____, 20_____.

My Commission Expires: _____

Signature of Notary Public

Resident of _____ County

Printed Name

COUNCIL DIGEST SHEET

Enclosed with this introduction form is a tab sheet and related material from the vendor(s) who submitted bid(s). Public Works is providing this information to Council as an overview of this award.

Woodland Lake Concrete Street Repairs Phase II

RFPs & BIDS

Bid/RFP #	0784C
Awarded To	Hipskind Concrete Corp
Amount	\$4,704,948.00
Conflict of interest on file?	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
Number of Registrants	3
Number of Bidders	2
Required Attachments	Council Digest Supplemental, Bid Tabulation, Award, Contract

EXTENSIONS

Date Last Bid Out	N/A
# Extensions Granted To Date	N/A

SPECIAL PROCUREMENT

Contract #/ID (State, Federal, Piggyback--Authority)	0784C
Sole Source/ Compatibility Justification	N/A

BID CRITERIA *(Take Buy Indiana requirements into consideration.)*

Most Responsible, Responsive Lowest	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>If no, explain below</i>
If not lowest, explain	N/A

COUNCIL DIGEST SHEET

COST COMPARISON

<i>Increase/decrease amount from prior years For annual purchase (if available).</i>	N/A
--	-----

DESCRIPTION OF PROJECT / NEED

<i>Identify need for project & describe project; attach supporting documents as necessary.</i>	Please see attached Council Digest Supplemental

REQUEST FOR SUSPENSION OF RULES

<i>Provide justification if prior approval is being requested.</i>	N/A

FUNDING SOURCE

<i>Account Information.</i>	Community Crossing Grant & LIT-ED (CEDIT)



FW PUBLIC WORKS

Board of Public Works

In Your Neighborhood

COMMON COUNCIL DIGEST SHEET – SUPPLEMENTAL

Woodland Lake Concrete Street Repairs Phase II

Action Requested:

Requesting an Ordinance approving the **Woodland Lake Concrete Street Repairs Phase II** project pursuant to the Board of Public Works Resolution #0784C and an award to **Hipskind Concrete Corp** in the amount of **\$4,704,948.00**.

Note: Hipskind Concrete was the lowest, most responsive bidder among the 2 bidders.

Description and Scope of the Work:

Improve the Woodland Lake neighborhood, Northwest Passage addition, and streets in Fallen Timbers Addition by removal and replacement of deteriorated concrete streets. Also, sidewalks and drive approaches will be reconstructed. New subsurface drainage will be installed and adjustment of existing castings. Finally, restoration of disturbed areas.

BILL NO. S-24-06-06

REPORT OF COMMITTEE ON PUBLIC WORKS

June 18, 2024

Geoff Paddock Chair









Nathan Hartman Co-Chair

All Council Members


An Ordinance approving Construction Contract – Woodland Lake Concrete Street Repairs Ph. II - Work Order #0784C – between Hipskind Concrete Corp and the City of Fort Wayne, Indiana, by and through its Board of Public Works

Involving a total cost of \$4,704,948.00

COMMITTEE ON PUBLIC WORKS HAVE HAD SAID Ordinance under consideration and beg leave to report back to the Common Council that said Ordinance

<u>COUNCIL MEMBER</u>	<u>DO PASS</u>	<u>DO NOT PASS</u>	<u>ABSTAIN</u>
<u>BENDER</u>			
<u>BOOKER</u>			
<u>CHAMBERS</u>			
<u>ENSLEY</u>			
<u>FREISTROFFER</u>			
<u>HARTMAN</u>			
<u>JEHL</u>			
<u>MYERS</u>			
<u>PADDOCK</u>			

**LANA R. KEESLING
CITY CLERK**



Public Hearing Date: N/A


Read the first time in full and on motion by Councilperson Paddock.

Read the second time by title and referred to the Public Works Committee.

Read the third time in full and on motion by Councilperson Paddock, placed on passage by the following vote:

<u>TOTAL VOTES</u>	<u>AYES</u>	<u>NAYS</u>	<u>ABSTAINED</u>	<u>ABSENT</u>
BENDER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
BOOKER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CHAMBERS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ENSLEY	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
FREISTROFFER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HARTMAN	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
JEHL	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
MYERS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PADDOCK	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

DATED: June 25, 2024




 LANA R. KEESLING, CITY CLERK

Passed and adopted by the Common Council of the City of Fort Wayne, Indiana, as

Special Ordinance No. S-24-06-06 on the 25th day of June, 2024

ATTEST:



 LANA R. KEESLING
 CITY CLERK



 PRESIDING OFFICER

Presented by me to the Mayor of the City of Fort Wayne, Indiana, on the 26th of June 2024, at the hour of 11:15 o'clock A.M. E.S.T.



 LANA R. KEESLING, CITY CLERK

Approved and signed by me this 26th day of June 2024, at the hour of 4:47 o'clock PM E.S.T.



 SHARON TUCKER, MAYOR

