

1 **BILL NO. S-25-06-07**

2 SPECIAL ORDINANCE NO. S-80-25

3
4 **AN ORDINANCE** approving CONSTRUCTION
5 CONTRACT – COMMUNITY CROSSINGS GRANT
6 2025 - WORK ORDER #0721C – (\$6,680,662.37) –
7 between MALOTT CONTRACTING, INC. and the City
8 of Fort Wayne, Indiana, by and through its Board of
9 Public Works.

10 **NOW, THEREFORE, BE IT ORDAINED BY THE COMMON
11 COUNCIL OF THE CITY OF FORT WAYNE, INDIANA:**

12 **SECTION 1.** That the CONSTRUCTION CONTRACT -
13 COMMUNITY CROSSINGS GRANT 2025 - WORK ORDER #0721C – between
14 MALOTT CONTRACTING, INC. and the City of Fort Wayne, Indiana, by and
15 through its Board of Public Works, is hereby ratified, and affirmed and approved in
16 all respects, respectfully for:

17 All labor, insurance, material, equipment, tools, power, transportation,
18 miscellaneous equipment, etc., necessary to IMPROVE THE
19 WESTCHESTER NEIGHBORHOOD AND S.W. WAYNE DALE
20 NEIGHBORHOOD, BY THE REMOVAL OF THE EXISTING
21 CONCRETE STREETS AND REPLACING WITH NEW CONCRETE
22 STREETS. THE REMOVAL AND REPLACEMENT OF SELECT
23 EXISTING SIDEWALK AND DRIVE APPROACHES. REMOVING
24 EXISTING CURB RAMPS AND REPLACING WITH NEW ADA
25 COMPLIANT CURB RAMPS. THERE WILL BE SUBSURFACE
26 DRAINAGE INSTALLED AND THE REPLACEMENT AND
27 ADJUSTMENT OF EXISTING CASTINGS WITH THE
28 RESTORATION OF DISTURBED AREAS;

29 involving a total cost of SIX MILLION SIX HUNDRED EIGHTY THOUSAND SIX
30 HUNDRED SIXTY-TWO and 37/100 DOLLARS - (\$6,680,662.37). A copy of said
Contract is on file with the Office of the City Clerk and made available for public
inspection, according to law.

TOTAL:		\$6,761,000.00		TOTAL:		\$6,680,662.37		TOTAL:		\$6,733,408.35		TOTAL:		\$8,293,759.92	
						% over % under		0.00% 1.19%		% over % under		0.00% 0.41%		% over % under	
22.67% 0.00%															
Bid Tabulation															
Community Crossings Grant 2025															
RES. NO. / W.C 0721C															
BIDDER: Malott Contracting															
BIDDER: Hipskind Concrete															
BIDDER: Milestone Contract															
LINE NO.	ITEM CODE	ITEM	PLAN QTY	UNIT	UNIT COST Est (\$)	AMOUNT Est (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	UNIT COST (\$)	AMOUNT (\$)	
1	105-05945	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,553.50	\$2,553.50	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78			
2	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$5,693.50	\$5,693.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17			
3	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,359.00	\$1,359.00	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00			
4	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	5	EACH	\$2,400.00	\$12,000.00	\$1,430.00	\$7,150.00	\$2,500.00	\$12,500.00	\$1,950.00	\$9,750.00			
5	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00			
6	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00			
7	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	2180	SYS	\$14.50	\$31,610.00	\$12.71	\$27,707.80	\$11.00	\$23,980.00	\$16.25	\$35,425.00			
8	202-93615	CONCRETE REMOVE	520	SYS	\$16.50	\$8,580.00	\$16.06	\$8,351.20	\$15.00	\$7,800.00	\$15.50	\$8,060.00			
9	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	5	CYS	\$32.00	\$160.00	\$38.67	\$193.35	\$30.00	\$150.00	\$61.00	\$305.00			
10	205-06933	TEMPORARY INLET PROTECTION	1	EACH	\$70.00	\$70.00	\$102.00	\$102.00	\$25.00	\$25.00	\$90.00	\$90.00			
11	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	260	SYS	\$8.00	\$2,080.00	\$8.36	\$2,173.60	\$0.10	\$26.00	\$7.25	\$1,885.00			
12	301-FWR0	COMPATED AGGREGATE NO. 53	734.3	TON	\$28.50	\$20,927.55	\$34.54	\$25,362.72	\$30.00	\$22,029.00	\$32.00	\$23,497.60			
13	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00			
14	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	2180	SYS	\$48.00	\$104,640.00	\$47.00	\$102,460.00	\$48.00	\$104,640.00	\$58.75	\$128,075.00			
15	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$50.00	\$0.00	\$57.50	\$0.00			
16	604-FWR0	DETECTABLE WARNING SURFACES	2	EACH	\$350.00	\$700.00	\$250.00	\$500.00	\$450.00	\$900.00	\$338.00	\$676.00			
17	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	240	SYS	\$57.00	\$13,680.00	\$58.00	\$13,920.00	\$57.00	\$13,680.00	\$79.75	\$19,140.00			
18	604-08086	CURB RAMP, CONCRETE	8	SYS	\$125.00	\$1,000.00	\$110.00	\$880.00	\$150.00	\$1,200.00	\$168.25	\$1,346.00			
19	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00			
20	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00			
21	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	280	SYS	\$65.00	\$18,200.00	\$68.00	\$19,040.00	\$67.00	\$18,760.00	\$90.50	\$25,340.00			
22	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00			
23	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1100	SYS	\$5.00	\$5,500.00	\$2.53	\$2,783.00	\$3.25	\$3,575.00	\$2.25	\$2,475.00			
24	621-FWR1	TOPSOIL	60	TON	\$55.00	\$3,300.00	\$51.00	\$3,060.00	\$45.00	\$2,700.00	\$45.00	\$2,700.00			
25	621-FWR2	PIPE - 12" CMP	30	LFT	\$300.00	\$9,000.00	\$78.71	\$2,361.30	\$100.00	\$3,000.00	\$112.50	\$3,375.00			
26	621-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	1420	LFT	\$12.00	\$17,040.00	\$9.74	\$13,830.80	\$9.00	\$12,780.00	\$16.00	\$22,720.00			
27	621-FWR4	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$203.50	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00			
28	621-FWR5	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$1,200.00	\$0.00	\$660.00	\$0.00	\$850.00	\$0.00	\$669.50	\$0.00			
29	621-FWR6	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	0	EACH	\$500.00	\$0.00	\$868.00	\$0.00	\$750.00	\$0.00	\$747.50	\$0.00			
30	621-FWR7	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07			
31	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.80	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00			
32	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.80	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00			
33	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00			
34	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00			
35	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00			
36	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00			
37	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00			
38	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00			
39	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00			
40	105-08845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,702.00	\$2,702.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78			
41	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,040.00	\$6,040.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17			
42	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,358.50	\$1,358.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00			
43	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,000.00	\$0.00	\$1,950.00	\$0.00			
44	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00			
45	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00			
46	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	5120	SYS	\$14.50	\$74,240.00	\$12.71	\$65,075.20	\$11.00	\$56,320.00	\$16.25	\$83,200.00			
47	202-93615	CONCRETE REMOVE	960	SYS	\$16.50	\$15,840.00	\$17.22	\$16,531.20	\$15.00	\$14,400.00	\$15.50	\$14,880.00			
48	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	10	CYS	\$32.00	\$320.00	\$38.61	\$386.10	\$30.00	\$300.00	\$61.00	\$610.00			
49	205-06933	TEMPORARY INLET PROTECTION	6	EACH	\$70.00	\$420.00	\$102.00	\$612.00	\$25.00	\$150.00	\$90.00	\$540.00			
50	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	2060	SYS	\$8.00	\$16,480.00	\$8.36	\$17,221.60	\$0.10	\$206.00	\$7.25	\$14,935.00			
51	301-FWR0	COMPATED AGGREGATE NO. 53	1418.1	TON	\$28.50	\$40,415.85	\$35.75	\$50,697.08	\$30.00	\$42,543.00	\$32.00	\$45,379.20			
52	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00			
53	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	5120	SYS	\$48.00	\$245,760.00	\$48.00	\$245,760.00	\$48.00	\$245,760.00	\$58.75	\$300,800.00			
54	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00			
55	604-FWR0	DETECTABLE WARNING SURFACES	6	EACH	\$350.00	\$2,100.00	\$250.00	\$1,500.00	\$450.00	\$2,700.00	\$338.00	\$2,028.00			
56	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	580	SYS	\$57.00	\$33,060.00	\$58.00	\$33,640.00	\$57.00	\$33,060.00	\$79.75	\$46,255.00			
57	604-08086	CURB RAMP, CONCRETE	26	SYS	\$125.00	\$3,250.00	\$110.00	\$2,860.00	\$150.00	\$3,900.00	\$168.25	\$4,374.50			
58	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00			
59	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00			
60	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	344	SYS	\$65.00	\$22,360.00	\$68.00	\$23,392.00	\$67.00	\$23,048.00	\$90.50	\$31,132.00			
61	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00			
62	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1500	SYS	\$5.00	\$7,500.00	\$2.53	\$3,795.00	\$3.25	\$4,875.00	\$2.25	\$3,375.00			

64	621-FWR1	TOPSOIL	20	TON	\$55.00	\$1,100.00	\$51.00	\$1,020.00	\$45.00	\$900.00	\$45.00	\$900.00
65	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$78.71	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
66	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	3500	LFT	\$12.00	\$42,000.00	\$9.63	\$33,705.00	\$9.00	\$31,500.00	\$16.00	\$56,000.00
67	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	6	EACH	\$200.00	\$1,200.00	\$203.50	\$1,221.00	\$150.00	\$900.00	\$216.50	\$1,299.00
68	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$500.00	\$1,000.00	\$203.50	\$407.00	\$750.00	\$1,500.00	\$211.50	\$423.00
69	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	4	EACH	\$1,200.00	\$4,800.00	\$660.00	\$2,640.00	\$850.00	\$3,400.00	\$669.50	\$2,678.00
70	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$888.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
71	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$7,000.00	\$7,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
72	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
73	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
74	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
75	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
76	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
77	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
78	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
79	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
80	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
81	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,548.00	\$2,548.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
82	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$5,693.50	\$5,693.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
83	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	2	EACH	\$1,600.00	\$3,200.00	\$1,358.50	\$2,717.00	\$1,500.00	\$3,000.00	\$1,400.00	\$2,800.00
84	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
85	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
86	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
87	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	1300	SYS	\$14.50	\$18,850.00	\$12.71	\$16,523.00	\$11.00	\$14,300.00	\$16.25	\$21,125.00
88	202-93615	CONCRETE REMOVE	270	SYS	\$16.50	\$4,455.00	\$15.73	\$4,247.10	\$15.00	\$4,050.00	\$15.50	\$4,185.00
89	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	5	CYS	\$32.00	\$160.00	\$38.67	\$193.35	\$30.00	\$150.00	\$61.00	\$305.00
90	205-06933	TEMPORARY INLET PROTECTION	0	EACH	\$70.00	\$0.00	\$102.00	\$0.00	\$25.00	\$0.00	\$90.00	\$0.00
91	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	530	SYS	\$8.00	\$4,240.00	\$8.36	\$4,430.80	\$0.10	\$53.00	\$7.25	\$3,842.50
92	301-FWR0	COMPATED AGGREGATE NO. 53	504.1	TON	\$28.50	\$14,366.85	\$33.44	\$16,857.10	\$30.00	\$15,123.00	\$32.00	\$16,131.20
93	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00
94	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	1300	SYS	\$48.00	\$62,400.00	\$48.00	\$62,400.00	\$48.00	\$62,400.00	\$58.75	\$76,375.00
95	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
96	604-FWR0	DETECTABLE WARNING SURFACES	4	EACH	\$350.00	\$1,400.00	\$250.00	\$1,000.00	\$450.00	\$1,800.00	\$338.00	\$1,352.00
97	604-06070	DETECTABLE WARNING SURFACES	130	SYS	\$57.00	\$7,410.00	\$58.00	\$7,540.00	\$57.00	\$7,410.00	\$79.75	\$10,367.50
98	604-06086	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	130	SYS	\$57.00	\$7,410.00	\$58.00	\$7,540.00	\$57.00	\$7,410.00	\$79.75	\$10,367.50
99	605-06120	CURB RAMP, CONCRETE	22	SYS	\$125.00	\$2,750.00	\$110.00	\$2,420.00	\$150.00	\$3,300.00	\$188.25	\$3,701.50
100	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
101	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
102	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	108	SYS	\$65.00	\$7,020.00	\$68.00	\$7,344.00	\$67.00	\$7,236.00	\$90.50	\$9,774.00
103	621-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
104	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	620	SYS	\$5.00	\$3,100.00	\$2.53	\$1,568.60	\$3.25	\$2,015.00	\$2.25	\$1,395.00
105	621-FWR1	TOPSOIL	30	TON	\$55.00	\$1,650.00	\$51.00	\$1,530.00	\$45.00	\$1,350.00	\$45.00	\$1,350.00
106	715-FWR2	PIPE - 12" CMP	30	LFT	\$300.00	\$9,000.00	\$77.00	\$2,310.00	\$100.00	\$3,000.00	\$112.50	\$3,375.00
107	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	830	LFT	\$12.00	\$9,960.00	\$10.18	\$8,448.40	\$9.00	\$7,470.00	\$16.00	\$13,280.00
108	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	2	EACH	\$200.00	\$400.00	\$203.50	\$407.00	\$150.00	\$300.00	\$216.50	\$433.00
109	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$240.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
110	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$1,200.00	\$0.00	\$760.00	\$0.00	\$850.00	\$0.00	\$669.50	\$0.00
111	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$858.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
112	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
113	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
114	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
115	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
116	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
117	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
118	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
119	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
120	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
121	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
122	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,702.00	\$2,702.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
123	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,029.00	\$6,029.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
124	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	12	EACH	\$1,600.00	\$19,200.00	\$1,358.50	\$16,302.00	\$1,500.00	\$18,000.00	\$1,400.00	\$16,800.00
125	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
126	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
127	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
128	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	3770	SYS	\$14.50	\$54,665.00	\$12.65	\$47,690.50	\$11.00	\$41,470.00	\$16.25	\$61,262.50
129	202-93615	CONCRETE REMOVE	1000	SYS	\$16.50	\$16,500.00	\$14.85	\$14,850.00	\$15.00	\$15,000.00	\$15.50	\$15,500.00
130	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	10	CYS	\$32.00	\$320.00	\$38.61	\$386.10	\$30.00	\$300.00	\$61.00	\$610.00
131	205-06933	TEMPORARY INLET PROTECTION	0	EACH	\$70.00	\$0.00	\$102.00	\$0.00	\$25.00	\$0.00	\$90.00	\$0.00
132	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	1500	SYS	\$8.00	\$12,000.00	\$8.36	\$12,540.00	\$0.10	\$150.00	\$7.25	\$10,875.00
133	301-FWR0	COMPATED AGGREGATE NO. 53	1023.3	TON	\$28.50	\$29,164.05	\$36.41	\$37,258.35	\$30.00	\$30,699.00	\$32.00	\$32,745.60

133	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00
134	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	3770	SYS	\$48.00	\$180,960.00	\$48.00	\$180,960.00	\$48.00	\$180,960.00	\$58.75	\$221,487.50
135	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
136	604-FWR0	DETECTABLE WARNING SURFACES	6	EACH	\$350.00	\$2,100.00	\$250.00	\$1,500.00	\$450.00	\$2,700.00	\$338.00	\$2,028.00
137	604-06070	DETECTABLE WARNING SURFACES SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	590	SYS	\$57.00	\$33,630.00	\$58.00	\$34,220.00	\$57.00	\$33,630.00	\$79.75	\$47,052.50
138	604-08086	CURB RAMP, CONCRETE	30	SYS	\$125.00	\$3,750.00	\$110.00	\$3,300.00	\$150.00	\$4,500.00	\$168.25	\$5,047.50
139	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
140	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
141	610-08446	PCCP FOR APPROACHES, 8 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	380	SYS	\$65.00	\$24,700.00	\$68.00	\$25,840.00	\$67.00	\$25,460.00	\$90.50	\$34,390.00
142	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
143	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1500	SYS	\$5.00	\$7,500.00	\$2.53	\$3,795.00	\$3.25	\$4,875.00	\$2.25	\$3,375.00
144	621-FWR1	TOPSOIL	40	TON	\$55.00	\$2,200.00	\$51.00	\$2,040.00	\$45.00	\$1,800.00	\$45.00	\$1,800.00
145	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
146	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	2400	LFT	\$12.00	\$28,800.00	\$9.90	\$23,760.00	\$9.00	\$21,600.00	\$16.00	\$38,400.00
147	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	2	EACH	\$200.00	\$400.00	\$203.50	\$407.00	\$150.00	\$300.00	\$216.50	\$433.00
148	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$500.00	\$1,000.00	\$203.50	\$407.00	\$750.00	\$1,500.00	\$211.50	\$423.00
149	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$1,200.00	\$0.00	\$760.00	\$0.00	\$850.00	\$0.00	\$669.50	\$0.00
150	720-FWR3	CASTING - 2 X 2 CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$858.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
151	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
152	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
153	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
154	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
155	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
156	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
157	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
158	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
159	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
160	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
161	105-08845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,625.00	\$2,625.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
162	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,700.00	\$6,700.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
163	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,358.50	\$1,358.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00
164	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	5	EACH	\$2,400.00	\$12,000.00	\$1,430.00	\$7,150.00	\$2,500.00	\$12,500.00	\$1,960.00	\$9,750.00
165	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
166	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
167	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	4240	SYS	\$14.50	\$61,480.00	\$12.71	\$53,890.40	\$11.00	\$46,640.00	\$16.25	\$68,900.00
168	202-93615	CONCRETE REMOVE	850	SYS	\$16.50	\$14,025.00	\$17.16	\$14,586.00	\$15.00	\$12,750.00	\$15.50	\$13,175.00
169	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	5	CYS	\$32.00	\$160.00	\$38.61	\$193.05	\$30.00	\$150.00	\$61.00	\$305.00
170	205-06933	TEMPORARY INLET PROTECTION	5	EACH	\$70.00	\$350.00	\$102.00	\$510.00	\$25.00	\$125.00	\$90.00	\$450.00
171	214-11796	GRID, TYPE 1B, 8X1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	1690	SYS	\$8.00	\$13,520.00	\$8.36	\$14,128.40	\$0.10	\$169.00	\$7.25	\$12,252.50
172	301-FWR0	COMPATED AGGREGATE NO. 53	1230	TON	\$28.50	\$35,055.00	\$35.09	\$43,160.70	\$30.00	\$36,900.00	\$32.00	\$39,360.00
173	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
174	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	4240	SYS	\$48.00	\$203,520.00	\$48.25	\$204,580.00	\$48.00	\$203,520.00	\$58.75	\$249,100.00
175	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
176	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
177	604-06070	DETECTABLE WARNING SURFACES SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	440	SYS	\$57.00	\$25,080.00	\$58.00	\$25,520.00	\$57.00	\$25,080.00	\$79.75	\$35,090.00
178	604-08086	CURB RAMP, CONCRETE	0	SYS	\$125.00	\$0.00	\$120.00	\$0.00	\$150.00	\$0.00	\$168.25	\$0.00
179	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
180	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
181	610-08446	PCCP FOR APPROACHES, 8 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	410	SYS	\$65.00	\$26,650.00	\$68.00	\$27,880.00	\$67.00	\$27,470.00	\$90.50	\$37,105.00
182	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
183	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	2025	SYS	\$5.00	\$10,125.00	\$2.53	\$5,123.25	\$3.25	\$6,581.25	\$2.25	\$4,556.25
184	621-FWR1	TOPSOIL	80	TON	\$55.00	\$4,400.00	\$51.00	\$4,080.00	\$45.00	\$3,600.00	\$45.00	\$3,600.00
185	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
186	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	2800	LFT	\$12.00	\$33,600.00	\$9.63	\$26,964.00	\$9.00	\$25,200.00	\$16.00	\$44,800.00
187	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	3	EACH	\$200.00	\$600.00	\$203.50	\$610.50	\$150.00	\$450.00	\$216.50	\$649.50
188	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$250.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
189	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$1,200.00	\$0.00	\$760.00	\$0.00	\$850.00	\$0.00	\$669.50	\$0.00
190	720-FWR3	CASTING - 2 X 2 CURB & GUTTER CASTING & ADJUST TO GRADE	5	EACH	\$500.00	\$2,500.00	\$858.00	\$4,290.00	\$850.00	\$4,250.00	\$747.50	\$3,737.50
191	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
192	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
193	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
194	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
195	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
196	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
197	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
198	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
199	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
200	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
201	105-08845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,999.00	\$2,999.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78

202	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$7,376.50	\$7,376.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
203	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	5	EACH	\$1,600.00	\$8,000.00	\$1,368.50	\$6,792.50	\$1,500.00	\$7,500.00	\$1,400.00	\$7,000.00
204	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	2	EACH	\$2,400.00	\$4,800.00	\$1,430.00	\$2,860.00	\$2,500.00	\$5,000.00	\$1,950.00	\$3,900.00
205	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
206	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
207	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	7250	SYS	\$14.50	\$105,125.00	\$12.71	\$92,147.50	\$11.00	\$79,750.00	\$16.25	\$117,812.50
208	202-93615	CONCRETE REMOVE	835	SYS	\$16.50	\$13,777.50	\$17.49	\$14,604.15	\$15.00	\$12,525.00	\$15.50	\$12,942.50
209	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	5	CYS	\$32.00	\$160.00	\$38.67	\$193.35	\$30.00	\$150.00	\$61.00	\$305.00
210	205-06933	TEMPORARY INLET PROTECTION	5	EACH	\$70.00	\$350.00	\$102.00	\$510.00	\$25.00	\$125.00	\$90.00	\$450.00
211	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	1820	SYS	\$8.00	\$14,560.00	\$8.36	\$15,215.20	\$0.10	\$182.00	\$7.25	\$13,195.00
212	301-FWR0	COMPACTED AGGREGATE NO. 53	1905	TON	\$28.50	\$54,292.50	\$36.03	\$68,637.15	\$30.00	\$57,150.00	\$32.00	\$60,960.00
213	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
214	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	7250	SYS	\$48.00	\$348,000.00	\$47.00	\$340,750.00	\$48.00	\$348,000.00	\$58.75	\$425,937.50
215	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
216	604-FWR0	DETECTABLE WARNING SURFACES	2	EACH	\$350.00	\$700.00	\$250.00	\$500.00	\$450.00	\$900.00	\$338.00	\$676.00
217	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	800	SYS	\$57.00	\$45,600.00	\$58.00	\$46,400.00	\$57.00	\$45,600.00	\$79.75	\$63,800.00
218	604-06086	CURB RAMP, CONCRETE	20	SYS	\$125.00	\$2,500.00	\$110.00	\$2,200.00	\$150.00	\$3,000.00	\$168.25	\$3,365.00
219	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
220	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
221	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	375	SYS	\$65.00	\$24,375.00	\$68.00	\$25,500.00	\$67.00	\$25,125.00	\$90.50	\$33,937.50
222	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
223	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	3500	SYS	\$5.00	\$17,500.00	\$2.53	\$8,855.00	\$3.25	\$11,375.00	\$2.25	\$7,875.00
224	621-FWR1	TOPSOIL	100	TON	\$55.00	\$5,500.00	\$51.00	\$5,100.00	\$45.00	\$4,500.00	\$45.00	\$4,500.00
225	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
226	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	4840	LFT	\$12.00	\$58,080.00	\$10.01	\$48,448.40	\$9.00	\$43,560.00	\$16.00	\$77,440.00
227	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	5	EACH	\$200.00	\$1,000.00	\$203.50	\$1,017.50	\$150.00	\$750.00	\$216.50	\$1,062.50
228	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$500.00	\$1,000.00	\$203.50	\$407.00	\$750.00	\$1,500.00	\$211.50	\$423.00
229	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$1,200.00	\$1,200.00	\$660.00	\$660.00	\$850.00	\$850.00	\$669.50	\$669.50
230	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	5	EACH	\$500.00	\$2,500.00	\$858.00	\$4,290.00	\$850.00	\$4,250.00	\$747.50	\$3,737.50
231	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$8,000.00	\$8,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
232	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
233	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
234	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
235	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
236	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
237	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
238	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
239	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
240	10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
241	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,130.00	\$2,130.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
242	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$4,681.50	\$4,681.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
243	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,368.50	\$1,368.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00
244	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
245	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
246	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
247	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	550	SYS	\$14.50	\$7,975.00	\$13.20	\$7,260.00	\$11.00	\$6,050.00	\$16.25	\$8,937.50
248	202-93615	CONCRETE REMOVE	45	SYS	\$16.50	\$742.50	\$15.57	\$700.65	\$15.00	\$675.00	\$15.50	\$697.50
249	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
250	205-06933	TEMPORARY INLET PROTECTION	2	EACH	\$70.00	\$140.00	\$102.00	\$204.00	\$25.00	\$50.00	\$90.00	\$180.00
251	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	130	SYS	\$8.00	\$1,040.00	\$8.36	\$1,086.80	\$0.10	\$13.00	\$7.25	\$942.50
252	301-FWR0	COMPACTED AGGREGATE NO. 53	360.7	TON	\$28.50	\$10,279.95	\$30.69	\$11,069.88	\$30.00	\$10,821.00	\$32.00	\$11,542.40
253	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00
254	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	550	SYS	\$48.00	\$26,400.00	\$47.00	\$25,850.00	\$48.00	\$26,400.00	\$58.75	\$32,312.50
255	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
256	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
257	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	30	SYS	\$57.00	\$1,710.00	\$58.00	\$1,740.00	\$57.00	\$1,710.00	\$79.75	\$2,392.50
258	604-06086	CURB RAMP, CONCRETE	0	SYS	\$125.00	\$0.00	\$120.00	\$0.00	\$150.00	\$0.00	\$168.25	\$0.00
259	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
260	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
261	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	15	SYS	\$65.00	\$975.00	\$68.00	\$1,020.00	\$67.00	\$1,005.00	\$90.50	\$1,357.50
262	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
263	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	100	SYS	\$5.00	\$500.00	\$2.53	\$253.00	\$3.25	\$325.00	\$2.25	\$225.00
264	621-FWR1	TOPSOIL	20	TON	\$55.00	\$1,100.00	\$51.00	\$1,020.00	\$45.00	\$900.00	\$45.00	\$900.00
265	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
266	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	360	LFT	\$12.00	\$4,320.00	\$12.60	\$4,536.00	\$9.00	\$3,240.00	\$16.00	\$5,760.00
267	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	3	EACH	\$200.00	\$600.00	\$203.50	\$610.50	\$150.00	\$450.00	\$216.50	\$649.50
268	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$250.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
269	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$660.00	\$1,320.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
270	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	0	EACH	\$500.00	\$0.00	\$960.00	\$0.00	\$850.00	\$0.00	\$747.50	\$0.00

271	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$5,000.00	\$5,000.00	\$12,000.00	\$12,000.00	\$6,280.17	\$6,280.17
272	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
273	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
274	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
275	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
276	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
277	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
278	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
279	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
280	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
281	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,405.00	\$2,405.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
282	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$5,022.50	\$5,022.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
283	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,358.50	\$1,358.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00
284	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
285	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
286	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
287	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	830	SYS	\$14.50	\$12,035.00	\$12.65	\$10,499.50	\$11.00	\$9,130.00	\$16.25	\$13,487.50
288	202-93615	CONCRETE REMOVE	197.2	SYS	\$16.50	\$3,253.80	\$15.07	\$2,971.80	\$15.00	\$2,958.00	\$15.50	\$3,056.60
289	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
290	205-06933	TEMPORARY INLET PROTECTION	2	EACH	\$70.00	\$140.00	\$102.00	\$204.00	\$25.00	\$50.00	\$90.00	\$180.00
291	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	170	SYS	\$8.00	\$1,360.00	\$8.36	\$1,421.20	\$0.10	\$17.00	\$7.25	\$1,232.50
292	301-FWR0	COMPACTED AGGREGATE NO. 53	423	TON	\$28.50	\$12,055.50	\$32.12	\$13,586.76	\$30.00	\$12,690.00	\$32.00	\$13,536.00
293	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
294	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	830	SYS	\$48.00	\$39,840.00	\$47.00	\$39,010.00	\$48.00	\$39,840.00	\$58.75	\$48,762.50
295	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
296	604-FWR0	DETECTABLE WARNING SURFACES	2	EACH	\$350.00	\$700.00	\$250.00	\$500.00	\$450.00	\$900.00	\$338.00	\$676.00
297	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	117.2	SYS	\$57.00	\$6,680.40	\$58.00	\$6,797.60	\$57.00	\$6,680.40	\$79.75	\$9,346.70
298	604-08086	CURB RAMP, CONCRETE	32	SYS	\$125.00	\$4,000.00	\$110.00	\$3,520.00	\$150.00	\$4,800.00	\$168.25	\$5,384.00
299	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
300	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
301	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	48	SYS	\$65.00	\$3,120.00	\$68.00	\$3,264.00	\$67.00	\$3,216.00	\$90.50	\$4,344.00
302	611-06233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
303	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	100	SYS	\$5.00	\$500.00	\$2.53	\$253.00	\$3.25	\$325.00	\$2.25	\$225.00
304	621-FWR1	TOPSOIL	2	TON	\$55.00	\$110.00	\$51.00	\$102.00	\$45.00	\$90.00	\$45.00	\$90.00
305	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
306	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	400	LFT	\$12.00	\$4,800.00	\$11.44	\$4,576.00	\$9.00	\$3,600.00	\$16.00	\$6,400.00
307	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$250.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
308	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$860.00	\$1,720.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
309	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	1	EACH	\$500.00	\$500.00	\$858.00	\$858.00	\$850.00	\$850.00	\$747.50	\$747.50
310	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
311	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
312	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
313	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
314	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
315	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
316	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
317	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
318	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
319	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
320	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,251.00	\$2,251.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
321	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$4,681.50	\$4,681.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
322	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,358.50	\$1,358.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00
323	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
324	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
325	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
326	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	632	SYS	\$14.50	\$9,164.00	\$12.65	\$7,994.80	\$11.00	\$6,952.00	\$16.25	\$10,270.00
327	202-93615	CONCRETE REMOVE	120	SYS	\$16.50	\$1,980.00	\$15.02	\$1,802.40	\$15.00	\$1,800.00	\$15.50	\$1,860.00
328	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
329	205-06933	TEMPORARY INLET PROTECTION	2	EACH	\$70.00	\$140.00	\$102.00	\$204.00	\$25.00	\$50.00	\$90.00	\$180.00
330	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	150	SYS	\$8.00	\$1,200.00	\$8.36	\$1,254.00	\$0.10	\$15.00	\$7.25	\$1,087.50
331	301-FWR0	COMPACTED AGGREGATE NO. 53	352	TON	\$28.50	\$10,032.00	\$31.63	\$11,133.76	\$30.00	\$10,560.00	\$32.00	\$11,264.00
332	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
333	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	632	SYS	\$48.00	\$30,336.00	\$47.00	\$29,704.00	\$48.00	\$30,336.00	\$58.75	\$37,130.00
334	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
335	604-FWR0	DETECTABLE WARNING SURFACES	2	EACH	\$350.00	\$700.00	\$250.00	\$500.00	\$450.00	\$900.00	\$338.00	\$676.00
336	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	18	SYS	\$57.00	\$1,026.00	\$58.00	\$1,044.00	\$57.00	\$1,026.00	\$79.75	\$1,435.50
337	604-08086	CURB RAMP, CONCRETE	32	SYS	\$125.00	\$4,000.00	\$110.00	\$3,520.00	\$150.00	\$4,800.00	\$168.25	\$5,384.00
338	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00

340	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
341	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	70	SYS	\$65.00	\$4,550.00	\$68.00	\$4,760.00	\$67.00	\$4,690.00	\$90.50	\$6,335.00
342	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
343	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	100	SYS	\$5.00	\$500.00	\$2.53	\$253.00	\$3.25	\$325.00	\$2.25	\$225.00
344	621-FWR1	TOPSOIL	2	TON	\$55.00	\$110.00	\$51.00	\$102.00	\$45.00	\$90.00	\$45.00	\$90.00
345	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
346	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	290	LFT	\$12.00	\$3,480.00	\$11.11	\$3,221.90	\$9.00	\$2,610.00	\$16.00	\$4,640.00
347	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	1	EACH	\$200.00	\$200.00	\$203.50	\$203.50	\$150.00	\$150.00	\$216.50	\$216.50
348	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$250.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
349	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$660.00	\$1,320.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
350	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	1	EACH	\$500.00	\$500.00	\$858.00	\$858.00	\$850.00	\$850.00	\$747.50	\$747.50
351	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$5,000.00	\$5,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
352	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
353	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
354	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
355	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
356	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
357	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
358	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
359	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
360	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
361	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,251.00	\$2,251.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
362	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$3,801.50	\$3,801.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
363	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
364	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
365	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
366	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
367	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	720	SYS	\$14.50	\$10,440.00	\$12.76	\$9,187.20	\$11.00	\$7,920.00	\$16.25	\$11,700.00
368	202-93615	CONCRETE REMOVE	296.3	SYS	\$16.50	\$4,888.95	\$14.58	\$4,320.05	\$15.00	\$4,444.50	\$15.50	\$4,592.65
369	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
370	205-06933	TEMPORARY INLET PROTECTION	1	EACH	\$70.00	\$70.00	\$102.00	\$102.00	\$25.00	\$25.00	\$90.00	\$90.00
371	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	150	SYS	\$8.00	\$1,200.00	\$8.36	\$1,254.00	\$10.10	\$1,150.00	\$7.25	\$1,087.50
372	301-FWR0	COMPACTED AGGREGATE NO. 53	390	TON	\$28.50	\$11,115.00	\$32.34	\$12,612.60	\$30.00	\$11,700.00	\$32.00	\$12,480.00
373	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	1	TON	\$300.00	\$300.00	\$302.50	\$302.50	\$200.00	\$200.00	\$350.00	\$350.00
374	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	720	SYS	\$48.00	\$34,560.00	\$47.00	\$33,840.00	\$48.00	\$34,560.00	\$58.75	\$42,300.00
375	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
376	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
377	604-06370	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	224.5	SYS	\$57.00	\$12,796.50	\$58.00	\$13,021.00	\$57.00	\$12,796.50	\$79.75	\$17,903.88
378	604-06066	CURB RAMP, CONCRETE	32	SYS	\$125.00	\$4,000.00	\$110.00	\$3,520.00	\$150.00	\$4,800.00	\$168.25	\$5,384.00
379	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
380	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
381	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	39.8	SYS	\$65.00	\$2,587.00	\$68.00	\$2,706.40	\$67.00	\$2,666.60	\$90.50	\$3,601.90
382	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
383	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	318	SYS	\$5.00	\$1,590.00	\$2.53	\$804.54	\$3.25	\$1,033.50	\$2.25	\$715.50
384	621-FWR1	TOPSOIL	5	TON	\$55.00	\$275.00	\$51.00	\$255.00	\$45.00	\$225.00	\$45.00	\$225.00
385	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
386	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	474	LFT	\$12.00	\$5,688.00	\$10.62	\$5,033.88	\$9.00	\$4,266.00	\$16.00	\$7,584.00
387	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	3	EACH	\$200.00	\$600.00	\$203.50	\$610.50	\$150.00	\$450.00	\$216.50	\$649.50
388	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$500.00	\$500.00	\$203.50	\$203.50	\$750.00	\$750.00	\$211.50	\$211.50
389	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$1,200.00	\$0.00	\$760.00	\$0.00	\$850.00	\$0.00	\$669.50	\$0.00
390	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$858.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
391	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$4,000.00	\$4,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
392	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
393	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
394	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
395	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
396	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
397	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
398	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
399	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
400	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
401	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,405.00	\$2,405.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
402	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$5,022.50	\$5,022.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
403	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
404	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,400.00	\$2,400.00	\$1,430.00	\$1,430.00	\$2,500.00	\$2,500.00	\$1,950.00	\$1,950.00
405	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
406	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
407	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	804	SYS	\$14.50	\$11,658.00	\$12.82	\$10,307.28	\$11.00	\$8,844.00	\$16.25	\$13,065.00
408	202-93615	CONCRETE REMOVE	79	SYS	\$16.50	\$1,303.50	\$16.28	\$1,286.12	\$15.00	\$1,185.00	\$15.50	\$1,224.50

409	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
410	205-06933	TEMPORARY INLET PROTECTION	1	EACH	\$70.00	\$70.00	\$102.00	\$102.00	\$25.00	\$25.00	\$90.00	\$90.00
411	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	322	SYS	\$8.00	\$2,576.00	\$8.36	\$2,691.92	\$0.10	\$32.20	\$7.25	\$2,334.50
412	301-FWR0	COMPATED AGGREGATE NO. 53	485.5	TON	\$28.50	\$13,836.75	\$31.02	\$15,060.21	\$30.00	\$14,565.00	\$32.00	\$15,536.00
413	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	2	TON	\$300.00	\$600.00	\$302.50	\$605.00	\$200.00	\$400.00	\$350.00	\$700.00
414	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	804	SYS	\$48.00	\$38,592.00	\$48.25	\$38,793.00	\$48.00	\$38,592.00	\$58.75	\$47,235.00
415	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
416	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
417	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	47	SYS	\$57.00	\$2,679.00	\$58.00	\$2,726.00	\$57.00	\$2,679.00	\$79.75	\$3,748.25
418	604-08086	CURB RAMP, CONCRETE	0	SYS	\$125.00	\$0.00	\$120.00	\$0.00	\$150.00	\$0.00	\$168.25	\$0.00
419	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
420	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
421	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	32	SYS	\$65.00	\$2,080.00	\$68.00	\$2,176.00	\$67.00	\$2,144.00	\$90.50	\$2,896.00
422	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	0	EACH	\$150.00	\$0.00	\$250.00	\$0.00	\$250.00	\$0.00	\$254.50	\$0.00
423	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	322	SYS	\$5.00	\$1,610.00	\$2.53	\$814.66	\$3.25	\$1,046.50	\$2.25	\$724.50
424	621-FWR1	TOPSOIL	5	TON	\$55.00	\$275.00	\$51.00	\$256.00	\$45.00	\$225.00	\$45.00	\$225.00
425	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
426	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	488	LFT	\$12.00	\$5,856.00	\$11.22	\$5,475.36	\$9.00	\$4,392.00	\$16.00	\$7,808.00
427	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	0	EACH	\$200.00	\$0.00	\$250.00	\$0.00	\$150.00	\$0.00	\$216.50	\$0.00
428	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$500.00	\$500.00	\$203.50	\$203.50	\$750.00	\$750.00	\$211.50	\$211.50
429	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$1,200.00	\$1,200.00	\$660.00	\$660.00	\$850.00	\$850.00	\$669.50	\$669.50
430	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	0	EACH	\$500.00	\$0.00	\$960.00	\$0.00	\$850.00	\$0.00	\$747.50	\$0.00
431	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$5,000.00	\$5,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
432	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
433	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
434	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
435	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
436	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
437	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
438	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
439	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
440	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
441	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,625.00	\$2,625.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
442	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,370.00	\$6,370.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
443	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$1,600.00	\$1,600.00	\$1,358.50	\$1,358.50	\$1,500.00	\$1,500.00	\$1,400.00	\$1,400.00
444	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
445	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
446	201-02270	TREE 60 IN., REMOVE	1	EACH	\$2,800.00	\$2,800.00	\$3,146.00	\$3,146.00	\$5,000.00	\$5,000.00	\$5,500.00	\$5,500.00
447	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	3864	SYS	\$14.50	\$56,028.00	\$12.76	\$49,304.64	\$11.00	\$42,504.00	\$16.25	\$62,790.00
448	202-93615	CONCRETE REMOVE	739	SYS	\$16.50	\$12,193.50	\$15.68	\$11,587.52	\$11.00	\$11,085.00	\$15.50	\$11,454.50
449	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
450	205-06933	TEMPORARY INLET PROTECTION	8	EACH	\$70.00	\$560.00	\$102.00	\$816.00	\$25.00	\$200.00	\$90.00	\$720.00
451	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	1546	SYS	\$8.00	\$12,368.00	\$8.36	\$12,924.56	\$0.10	\$154.60	\$7.25	\$11,208.50
452	301-FWR0	COMPATED AGGREGATE NO. 53	1130	TON	\$28.50	\$32,205.00	\$35.20	\$39,778.00	\$30.00	\$33,900.00	\$32.00	\$36,160.00
453	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	3	TON	\$300.00	\$900.00	\$302.50	\$907.50	\$200.00	\$600.00	\$350.00	\$1,050.00
454	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	3864	SYS	\$48.00	\$185,472.00	\$48.25	\$186,438.00	\$48.00	\$185,472.00	\$58.75	\$227,010.00
455	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
456	604-FWR0	DETECTABLE WARNING SURFACES	3	EACH	\$350.00	\$1,050.00	\$250.00	\$750.00	\$450.00	\$1,350.00	\$338.00	\$1,014.00
457	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	441	SYS	\$57.00	\$25,137.00	\$58.00	\$25,578.00	\$57.00	\$25,137.00	\$79.75	\$35,169.75
458	604-08086	CURB RAMP, CONCRETE	44	SYS	\$125.00	\$5,500.00	\$110.00	\$4,840.00	\$150.00	\$6,600.00	\$168.25	\$7,403.00
459	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
460	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	30	LFT	\$70.00	\$2,100.00	\$74.00	\$2,220.00	\$80.00	\$2,400.00	\$95.75	\$2,872.50
461	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	224	SYS	\$65.00	\$14,560.00	\$68.00	\$15,232.00	\$67.00	\$15,008.00	\$90.50	\$20,272.00
462	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	14	EACH	\$150.00	\$2,100.00	\$220.00	\$3,080.00	\$250.00	\$3,500.00	\$254.50	\$3,563.00
463	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1727	SYS	\$5.00	\$8,635.00	\$2.53	\$4,369.31	\$3.25	\$5,612.75	\$2.25	\$3,885.75
464	621-FWR1	TOPSOIL	120	TON	\$55.00	\$6,600.00	\$51.00	\$6,120.00	\$45.00	\$5,400.00	\$45.00	\$5,400.00
465	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
466	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	2590	LFT	\$12.00	\$31,080.00	\$10.78	\$27,920.20	\$9.00	\$23,310.00	\$16.00	\$41,440.00
467	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	3	EACH	\$200.00	\$600.00	\$203.50	\$610.50	\$150.00	\$450.00	\$216.50	\$648.50
468	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	0	EACH	\$500.00	\$0.00	\$250.00	\$0.00	\$750.00	\$0.00	\$211.50	\$0.00
469	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$660.00	\$1,320.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
470	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	7	EACH	\$500.00	\$3,500.00	\$858.00	\$6,006.00	\$850.00	\$5,950.00	\$747.50	\$5,232.50
471	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$6,000.00	\$6,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
472	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
473	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
474	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
475	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
476	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
477	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00

478	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
479	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
480	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
481	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,850.50	\$2,850.50	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
482	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,700.00	\$6,700.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
483	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
484	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	3	EACH	\$2,400.00	\$7,200.00	\$1,430.00	\$4,290.00	\$2,500.00	\$7,500.00	\$1,950.00	\$5,850.00
485	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	2	EACH	\$2,600.00	\$5,200.00	\$1,573.00	\$3,146.00	\$3,500.00	\$7,000.00	\$2,800.00	\$5,600.00
486	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
487	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	4728	SYS	\$14.50	\$68,556.00	\$12.71	\$60,092.88	\$11.00	\$52,008.00	\$16.25	\$76,830.00
488	202-93615	CONCRETE REMOVE	570	SYS	\$16.50	\$9,405.00	\$17.38	\$9,906.60	\$15.00	\$8,550.00	\$15.50	\$8,835.00
489	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
490	205-06933	TEMPORARY INLET PROTECTION	7	EACH	\$70.00	\$490.00	\$102.00	\$714.00	\$25.00	\$175.00	\$90.00	\$630.00
491	214-11796	GEOGRID, TYPE 18, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	1900	SYS	\$8.00	\$15,200.00	\$8.36	\$15,884.00	\$0.10	\$190.00	\$7.25	\$13,775.00
492	301-FWR0	COMPATED AGGREGATE NO. 53	1301.4	TON	\$28.50	\$37,089.90	\$35.31	\$45,952.43	\$30.00	\$39,042.00	\$32.00	\$41,644.80
493	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00
494	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	4728	SYS	\$48.00	\$226,944.00	\$48.25	\$228,126.00	\$48.00	\$226,944.00	\$58.75	\$277,770.00
495	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
496	604-FWR0	DETECTABLE WARNING SURFACES	6	EACH	\$350.00	\$2,100.00	\$250.00	\$1,500.00	\$450.00	\$2,700.00	\$338.00	\$2,028.00
497	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	425	SYS	\$57.00	\$24,225.00	\$58.00	\$24,650.00	\$57.00	\$24,225.00	\$79.75	\$33,893.75
498	604-06086	CURB RAMP, CONCRETE	70	SYS	\$125.00	\$8,750.00	\$110.00	\$7,700.00	\$150.00	\$10,500.00	\$168.25	\$11,777.50
499	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
500	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
501	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	75	SYS	\$65.00	\$4,875.00	\$68.00	\$5,100.00	\$67.00	\$5,025.00	\$90.50	\$6,787.50
502	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	6	EACH	\$150.00	\$900.00	\$220.00	\$1,320.00	\$250.00	\$1,500.00	\$254.50	\$1,527.00
503	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	2100	SYS	\$5.00	\$10,500.00	\$2.53	\$5,313.00	\$3.25	\$6,825.00	\$2.25	\$4,725.00
504	621-FWR1	TOPSOIL	150	TON	\$55.00	\$8,250.00	\$51.00	\$7,650.00	\$45.00	\$6,750.00	\$45.00	\$6,750.00
505	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
506	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	3150	LFT	\$12.00	\$37,800.00	\$9.90	\$31,185.00	\$9.00	\$28,350.00	\$16.00	\$50,400.00
507	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	2	EACH	\$200.00	\$400.00	\$203.50	\$407.00	\$150.00	\$300.00	\$216.50	\$433.00
508	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	4	EACH	\$500.00	\$2,000.00	\$203.50	\$814.00	\$750.00	\$3,000.00	\$211.50	\$846.00
509	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	5	EACH	\$1,200.00	\$6,000.00	\$660.00	\$3,300.00	\$850.00	\$4,250.00	\$669.50	\$3,347.50
510	720-FWR3	CASTING - 2 X 2 CURB & GUTTER CASTING & ADJUST TO GRADE	4	EACH	\$500.00	\$2,000.00	\$858.00	\$3,432.00	\$850.00	\$3,400.00	\$747.50	\$2,990.00
511	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$7,000.00	\$7,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
512	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
513	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
514	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
515	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
516	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
517	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
518	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
519	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
520	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
521	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$3,076.00	\$3,076.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
522	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$10,126.50	\$10,126.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
523	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
524	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,400.00	\$2,400.00	\$1,430.00	\$1,430.00	\$2,500.00	\$2,500.00	\$1,950.00	\$1,950.00
525	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,600.00	\$2,600.00	\$1,573.00	\$1,573.00	\$3,500.00	\$3,500.00	\$2,800.00	\$2,800.00
526	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
527	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	7824	SYS	\$14.50	\$113,448.00	\$12.71	\$99,443.04	\$11.00	\$86,064.00	\$16.25	\$127,140.00
528	202-93615	CONCRETE REMOVE	1708.4	SYS	\$16.50	\$28,188.60	\$15.18	\$25,933.51	\$15.00	\$25,626.00	\$15.50	\$26,480.20
529	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
530	205-06933	TEMPORARY INLET PROTECTION	12	EACH	\$70.00	\$840.00	\$102.00	\$1,224.00	\$25.00	\$300.00	\$90.00	\$1,080.00
531	214-11796	GEOGRID, TYPE 18, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	3130	SYS	\$8.00	\$25,040.00	\$8.36	\$26,166.80	\$0.10	\$313.00	\$7.25	\$22,692.50
532	301-FWR0	COMPATED AGGREGATE NO. 53	2005	TON	\$28.50	\$57,142.50	\$36.58	\$73,342.90	\$30.00	\$60,150.00	\$32.00	\$64,160.00
533	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
534	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	4728	SYS	\$48.00	\$226,944.00	\$48.15	\$227,653.20	\$48.00	\$226,944.00	\$58.75	\$277,770.00
535	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
536	604-FWR0	DETECTABLE WARNING SURFACES	22	EACH	\$350.00	\$7,700.00	\$250.00	\$5,500.00	\$450.00	\$9,900.00	\$338.00	\$7,436.00
537	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	713.4	SYS	\$57.00	\$40,663.80	\$58.00	\$41,377.20	\$57.00	\$40,663.80	\$79.75	\$56,893.65
538	604-06086	CURB RAMP, CONCRETE	180	SYS	\$125.00	\$22,500.00	\$110.00	\$19,800.00	\$150.00	\$27,000.00	\$168.25	\$30,285.00
539	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
540	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	100	LFT	\$70.00	\$7,000.00	\$74.00	\$7,400.00	\$80.00	\$8,000.00	\$95.75	\$9,575.00
541	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	715	SYS	\$65.00	\$46,475.00	\$68.00	\$48,620.00	\$67.00	\$47,905.00	\$90.50	\$64,707.50
542	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	1	EACH	\$150.00	\$150.00	\$220.00	\$220.00	\$250.00	\$250.00	\$254.50	\$254.50
543	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	3478	SYS	\$5.00	\$17,390.00	\$2.53	\$8,799.34	\$3.25	\$11,303.50	\$2.25	\$7,825.50
544	621-FWR1	TOPSOIL	200	TON	\$55.00	\$11,000.00	\$51.00	\$10,200.00	\$45.00	\$9,000.00	\$45.00	\$9,000.00
545	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
546	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	5216	LFT	\$12.00	\$62,592.00	\$10.01	\$52,212.16	\$9.00	\$46,944.00	\$16.00	\$83,456.00

547	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	6	EACH	\$200.00	\$1,200.00	\$203.50	\$1,221.00	\$150.00	\$900.00	\$216.50	\$1,299.00
548	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	6	EACH	\$500.00	\$3,000.00	\$203.50	\$1,221.00	\$750.00	\$4,500.00	\$211.50	\$1,269.00
549	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$660.00	\$1,320.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
550	720-FWR3	CASTING - 2" X 2" CURB & GUTTER CASTING & ADJUST TO GRADE	14	EACH	\$500.00	\$7,000.00	\$858.00	\$12,012.00	\$850.00	\$11,900.00	\$747.50	\$10,465.00
551	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$13,000.00	\$13,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
552	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
553	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
554	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
555	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
556	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	27	LFT	\$15.00	\$405.00	\$22.00	\$594.00	\$30.00	\$810.00	\$20.00	\$540.00
557	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
558	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	1	EACH	\$450.00	\$450.00	\$2,000.00	\$2,000.00	\$3,000.00	\$3,000.00	\$1,750.00	\$1,750.00
559	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
560	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
561	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,702.00	\$2,702.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
562	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$6,050.00	\$6,050.00	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
563	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
564	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,400.00	\$2,400.00	\$1,430.00	\$1,430.00	\$2,500.00	\$2,500.00	\$1,950.00	\$1,950.00
565	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,600.00	\$2,600.00	\$1,573.00	\$1,573.00	\$3,500.00	\$3,500.00	\$2,800.00	\$2,800.00
566	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
567	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	2349	SYS	\$14.50	\$34,060.50	\$12.71	\$29,855.79	\$11.00	\$25,839.00	\$16.25	\$38,171.25
568	202-93615	CONCRETE REMOVE	467	SYS	\$16.50	\$7,705.50	\$16.12	\$7,528.04	\$15.00	\$7,005.00	\$15.50	\$7,238.50
569	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
570	205-06933	TEMPORARY INLET PROTECTION	3	EACH	\$70.00	\$210.00	\$102.00	\$306.00	\$25.00	\$75.00	\$90.00	\$270.00
571	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	940	SYS	\$8.00	\$7,520.00	\$8.36	\$7,858.40	\$0.10	\$94.00	\$7.25	\$6,815.00
572	301-FWR0	COMPATED AGGREGATE NO. 53	768	TON	\$28.50	\$21,888.00	\$34.60	\$26,572.80	\$30.00	\$23,040.00	\$32.00	\$24,576.00
573	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	0	TON	\$300.00	\$0.00	\$350.00	\$0.00	\$200.00	\$0.00	\$350.00	\$0.00
574	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	2349	SYS	\$48.00	\$112,752.00	\$47.00	\$110,403.00	\$48.00	\$112,752.00	\$58.75	\$138,003.75
575	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00
576	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
577	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	214	SYS	\$57.00	\$12,198.00	\$58.00	\$12,412.00	\$57.00	\$12,198.00	\$79.75	\$17,066.50
578	604-06086	CURB RAMP, CONCRETE	0	SYS	\$125.00	\$0.00	\$110.00	\$0.00	\$150.00	\$0.00	\$168.25	\$0.00
579	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
580	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	0	LFT	\$70.00	\$0.00	\$80.00	\$0.00	\$80.00	\$0.00	\$95.75	\$0.00
581	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES)	253	SYS	\$65.00	\$16,445.00	\$68.00	\$17,204.00	\$67.00	\$16,951.00	\$90.50	\$22,896.50
582	611-06233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	1	EACH	\$150.00	\$150.00	\$220.00	\$220.00	\$250.00	\$250.00	\$254.50	\$254.50
583	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	1044	SYS	\$5.00	\$5,220.00	\$2.53	\$2,641.32	\$3.25	\$3,393.00	\$2.25	\$2,349.00
584	621-FWR1	TOPSOIL	40	TON	\$55.00	\$2,200.00	\$51.00	\$2,040.00	\$45.00	\$1,800.00	\$45.00	\$1,800.00
585	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
586	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1566	LFT	\$12.00	\$18,792.00	\$9.46	\$14,814.36	\$9.00	\$14,094.00	\$16.00	\$25,056.00
587	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	2	EACH	\$200.00	\$400.00	\$203.50	\$407.00	\$150.00	\$300.00	\$216.50	\$433.00
588	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$500.00	\$500.00	\$203.50	\$203.50	\$750.00	\$750.00	\$211.50	\$211.50
589	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$1,200.00	\$660.00	\$660.00	\$850.00	\$850.00	\$669.50	\$669.50
590	720-FWR3	CASTING - 2" X 2" CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$858.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
591	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$7,000.00	\$7,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
592	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
593	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
594	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
595	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
596	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	0	LFT	\$15.00	\$0.00	\$24.00	\$0.00	\$0.00	\$0.00	\$20.00	\$0.00
597	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
598	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
599	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	0	LFT	\$0.70	\$0.00	\$6.90	\$0.00	\$0.00	\$0.00	\$6.00	\$0.00
600	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
601	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,405.00	\$2,405.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
602	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$8,443.50	\$8,443.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
603	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
604	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,400.00	\$2,400.00	\$1,430.00	\$1,430.00	\$2,500.00	\$2,500.00	\$1,950.00	\$1,950.00
605	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
606	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
607	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	1950	SYS	\$14.50	\$28,275.00	\$12.82	\$24,999.00	\$11.00	\$21,450.00	\$16.25	\$31,687.50
608	202-93615	CONCRETE REMOVE	483	SYS	\$16.50	\$7,969.50	\$15.07	\$7,278.81	\$15.00	\$7,245.00	\$15.50	\$7,486.50
609	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
610	205-06933	TEMPORARY INLET PROTECTION	0	EACH	\$70.00	\$0.00	\$102.00	\$0.00	\$25.00	\$0.00	\$90.00	\$0.00
611	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	780	SYS	\$8.00	\$6,240.00	\$8.36	\$6,528.80	\$0.10	\$78.00	\$7.25	\$6,655.00
612	301-FWR0	COMPATED AGGREGATE NO. 53	670.5	TON	\$28.50	\$19,109.25	\$34.10	\$22,864.05	\$30.00	\$20,115.00	\$32.00	\$21,456.00
613	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	10	TON	\$300.00	\$3,000.00	\$302.50	\$3,025.00	\$200.00	\$2,000.00	\$350.00	\$3,500.00
614	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	1950	SYS	\$48.00	\$93,600.00	\$47.00	\$91,650.00	\$48.00	\$93,600.00	\$58.75	\$114,562.50
615	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$0.00	\$0.00	\$57.50	\$0.00

618	604-FWR0	DETECTABLE WARNING SURFACES	0	EACH	\$350.00	\$0.00	\$300.00	\$0.00	\$450.00	\$0.00	\$338.00	\$0.00
617	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	257	SYS	\$57.00	\$14,649.00	\$58.00	\$14,906.00	\$57.00	\$14,649.00	\$79.75	\$20,496.75
618	604-08086	CURB RAMP, CONCRETE	39	SYS	\$125.00	\$4,875.00	\$110.00	\$4,290.00	\$150.00	\$5,850.00	\$168.25	\$6,561.75
619	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
620	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	141	LFT	\$70.00	\$9,870.00	\$74.00	\$10,434.00	\$80.00	\$11,280.00	\$95.75	\$13,500.75
621	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	46	SYS	\$65.00	\$2,990.00	\$68.00	\$3,128.00	\$67.00	\$3,082.00	\$90.50	\$4,163.00
622	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	1	EACH	\$150.00	\$150.00	\$220.00	\$220.00	\$250.00	\$250.00	\$254.50	\$254.50
623	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	867	SYS	\$5.00	\$4,335.00	\$2.53	\$2,193.51	\$3.25	\$2,817.75	\$2.25	\$1,950.75
624	621-FWR1	TOPSOIL	30	TON	\$55.00	\$1,650.00	\$51.00	\$1,530.00	\$45.00	\$1,350.00	\$45.00	\$1,350.00
625	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
626	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	1900	LFT	\$12.00	\$15,600.00	\$10.34	\$13,442.00	\$9.00	\$11,700.00	\$16.00	\$20,800.00
627	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	5	EACH	\$200.00	\$1,000.00	\$203.50	\$1,017.50	\$150.00	\$750.00	\$216.50	\$1,082.50
628	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$500.00	\$500.00	\$203.50	\$203.50	\$750.00	\$750.00	\$211.50	\$211.50
629	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	2	EACH	\$1,200.00	\$2,400.00	\$660.00	\$1,320.00	\$850.00	\$1,700.00	\$669.50	\$1,339.00
630	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	2	EACH	\$500.00	\$1,000.00	\$858.00	\$1,716.00	\$850.00	\$1,700.00	\$747.50	\$1,495.00
631	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$9,000.00	\$9,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
632	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
633	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
634	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
635	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
636	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	14	LFT	\$15.00	\$210.00	\$22.00	\$308.00	\$30.00	\$420.00	\$20.00	\$280.00
637	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
638	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
639	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	60	LFT	\$0.70	\$42.00	\$6.60	\$396.00	\$20.00	\$1,200.00	\$6.00	\$360.00
640	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
641	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$2,702.00	\$2,702.00	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
642	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$8,168.50	\$8,168.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
643	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$1,600.00	\$0.00	\$1,600.00	\$0.00	\$1,500.00	\$0.00	\$1,400.00	\$0.00
644	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,400.00	\$0.00	\$1,800.00	\$0.00	\$2,500.00	\$0.00	\$1,950.00	\$0.00
645	201-02265	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	0	EACH	\$2,600.00	\$0.00	\$2,200.00	\$0.00	\$3,500.00	\$0.00	\$2,800.00	\$0.00
646	201-02270	TREE 60 IN., REMOVE	0	EACH	\$2,800.00	\$0.00	\$5,000.00	\$0.00	\$5,000.00	\$0.00	\$5,500.00	\$0.00
647	202-02240	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	5805	SYS	\$14.50	\$84,172.50	\$12.76	\$74,071.80	\$11.00	\$63,855.00	\$16.25	\$94,331.25
648	202-93615	CONCRETE REMOVE	1175.4	SYS	\$16.50	\$19,394.10	\$14.96	\$17,583.98	\$15.00	\$17,631.00	\$15.50	\$18,218.70
649	203-02000	EXCAVATION, COMMON (UNDISTRIBUTED)	0	CYS	\$32.00	\$0.00	\$40.00	\$0.00	\$30.00	\$0.00	\$61.00	\$0.00
650	205-06933	TEMPORARY INLET PROTECTION	2	EACH	\$70.00	\$140.00	\$102.00	\$204.00	\$25.00	\$50.00	\$90.00	\$180.00
651	214-11796	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	2322	SYS	\$8.00	\$18,576.00	\$8.36	\$19,411.92	\$0.10	\$232.20	\$7.25	\$16,834.50
652	301-FWR0	COMPATED AGGREGATE NO. 53	1575	TON	\$28.50	\$44,887.50	\$35.64	\$56,133.00	\$30.00	\$47,250.00	\$32.00	\$50,400.00
653	304-07490	HMA PATCHING, TYPE B (UNDISTRIBUTED)	5	TON	\$300.00	\$1,500.00	\$302.50	\$1,512.50	\$200.00	\$1,000.00	\$350.00	\$1,750.00
654	502-FWR0	PCCP, 7" IN. WITH MONOLITHIC CURB	5805	SYS	\$48.00	\$278,640.00	\$47.00	\$272,835.00	\$48.00	\$278,640.00	\$58.75	\$341,043.75
655	502-11564	PCCP, 7 IN. (PAVEMENT)	0	SYS	\$48.00	\$0.00	\$50.00	\$0.00	\$48.00	\$0.00	\$57.50	\$0.00
656	604-FWR0	DETECTABLE WARNING SURFACES	2	EACH	\$350.00	\$700.00	\$250.00	\$500.00	\$450.00	\$900.00	\$338.00	\$676.00
657	604-06070	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	537.4	SYS	\$57.00	\$30,631.80	\$58.00	\$31,169.20	\$57.00	\$30,631.80	\$79.75	\$42,857.65
658	604-08086	CURB RAMP, CONCRETE	113	SYS	\$125.00	\$14,125.00	\$110.00	\$12,430.00	\$150.00	\$16,950.00	\$168.25	\$19,012.25
659	605-06120	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	0	LFT	\$16.00	\$0.00	\$12.50	\$0.00	\$0.00	\$0.00	\$15.75	\$0.00
660	610-07713	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	301	LFT	\$70.00	\$21,070.00	\$74.00	\$22,274.00	\$80.00	\$24,080.00	\$95.75	\$28,820.75
661	610-08446	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	224	SYS	\$65.00	\$14,560.00	\$68.00	\$15,232.00	\$67.00	\$15,008.00	\$90.50	\$20,272.00
662	611-08233	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	3	EACH	\$150.00	\$450.00	\$220.00	\$660.00	\$250.00	\$750.00	\$254.50	\$763.50
663	621-FWR0	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	2580	SYS	\$5.00	\$12,900.00	\$2.53	\$6,527.40	\$3.25	\$8,385.00	\$2.25	\$5,805.00
664	621-FWR1	TOPSOIL	200	TON	\$55.00	\$11,000.00	\$51.00	\$10,200.00	\$45.00	\$9,000.00	\$45.00	\$9,000.00
665	715-FWR2	PIPE - 12" CMP	0	LFT	\$300.00	\$0.00	\$80.00	\$0.00	\$100.00	\$0.00	\$112.50	\$0.00
666	715-FWR3	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	3870	LFT	\$12.00	\$46,440.00	\$10.01	\$38,738.70	\$9.00	\$34,830.00	\$16.00	\$61,920.00
667	715-94530	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	9	EACH	\$200.00	\$1,800.00	\$203.50	\$1,831.50	\$150.00	\$1,350.00	\$216.50	\$1,948.50
668	720-FWR1	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	7	EACH	\$500.00	\$3,500.00	\$203.50	\$1,424.50	\$750.00	\$5,250.00	\$211.50	\$1,480.50
669	720-FWR3	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	1	EACH	\$1,200.00	\$1,200.00	\$660.00	\$660.00	\$850.00	\$850.00	\$669.50	\$669.50
670	720-FWR3	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	6	EACH	\$500.00	\$3,000.00	\$858.00	\$5,148.00	\$850.00	\$5,100.00	\$747.50	\$4,485.00
671	801-FWR0	MAINTENANCE OF TRAFFIC	1	LS	\$3,500.00	\$3,500.00	\$10,000.00	\$10,000.00	\$12,000.00	\$12,000.00	\$6,280.07	\$6,280.07
672	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
673	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	0	LFT	\$0.60	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
674	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	0	LFT	\$0.55	\$0.00	\$1.40	\$0.00	\$0.00	\$0.00	\$1.00	\$0.00
675	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	0	LFT	\$0.75	\$0.00	\$2.50	\$0.00	\$0.00	\$0.00	\$2.00	\$0.00
676	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	13	LFT	\$15.00	\$195.00	\$22.00	\$286.00	\$30.00	\$390.00	\$20.00	\$260.00
677	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	0	EACH	\$300.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
678	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	0	EACH	\$450.00	\$0.00	\$2,000.00	\$0.00	\$0.00	\$0.00	\$1,750.00	\$0.00
679	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	80	LFT	\$0.70	\$56.00	\$6.60	\$528.00	\$20.00	\$1,600.00	\$6.00	\$480.00
680	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	0	EACH	\$250.00	\$0.00	\$350.00	\$0.00	\$0.00	\$0.00	\$250.00	\$0.00
681	105-06845	CONSTRUCTION ENGINEERING	1	LS	\$2,000.00	\$2,000.00	\$3,301.50	\$3,301.50	\$12,000.00	\$12,000.00	\$2,777.78	\$2,777.78
682	110-01001	MOBILIZATION AND DEMOBILIZATION	1	LS	\$4,000.00	\$4,000.00	\$11,226.50	\$11,226.50	\$12,000.00	\$12,000.00	\$23,038.17	\$23,038.17
683	201-02255	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	2	EACH	\$1,600.00	\$3,200.00	\$1,358.50	\$2,717.00	\$1,500.00	\$3,000.00	\$1,400.00	\$2,800.00
684	201-02260	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	1	EACH	\$2,400.00	\$2,400.00	\$1,430.00	\$1,430.00	\$2,500.00	\$2,500.00	\$1,950.00	\$1,950.00



Notice of Award

Project: Community Crossings Grant 2025

Owner: City of Fort Wayne Board of Works

Resolution/Work Order #0721C

Bidder: Malott Contracting, Inc

Bidder's Address: PO Box 292

Kendallville, IN 46755

You are notified that your Bid dated 5/29/2025 for the above Contract has been considered. You are the Successful Bidder and are awarded a Contract for Community Crossings Grant 2025

Improve the Westchester Neighborhood and S.W. Waynedale Neighborhood, by the removal of the existing concrete streets and replacing with new concrete streets. The removal and replacement of select existing sidewalk and drive approaches.

Removing existing curb ramps and replacing with new ADA compliant curb ramps. There will be subsurface drainage installed and the replacement and ad-justment of existing castings with the restoration of disturbed areas.

The Contract Price of your Contract is \$6,680,662.37.

1 copy of the proposed Construction Contract (except Drawings) accompany this Notice of Award.

You must comply with the following conditions precedent within **[10]** days of the date you receive this Notice of Award.

1. Deliver to the Owner [1] fully executed counterparts of the Construction Contract.
2. Deliver with the executed Agreement the following documents:
 - a. Performance Bond
 - b. Payment Bond
 - c. Certificate of Insurance
 - d. Executed E-Verify Affidavit.
 - e. Executed Drug Policy Acknowledgement Form.
3. Deliver evidence of successful Bidder's Affirmative Action Plan; OR, executed City of Fort Wayne Affirmative Action Program document to City of Fort Wayne Vendor Compliance, michelle.metzger@cityoffortwayne.org.



Notice of Award

Failure to comply with these conditions within the time specified will entitle Owner to consider you in default, annul this Notice of Award, and declare your Bid security forfeited. Contractor will be allowed an additional 11 calendar days to submit Bonds.

Within thirty days after you comply with the above conditions, Owner will return to you one fully executed counterpart of the Agreement.

**CITY OF FORT WAYNE
BOARD OF PUBLIC WORKS**

A blue ink signature of Shan Gunawardena, written in a cursive style.

Shan Gunawardena, Chair

A blue ink signature of Kumar Menon, written in a cursive style.

Kumar Menon, Member

A blue ink signature of Chris Guerrero, written in a cursive style.

Chris Guerrero, Member

ATTEST:

A blue ink signature of Michelle Fulk-Vondran, written in a cursive style.

Michelle Fulk-Vondran, Clerk

Date: 6.3.2025

cc: Project Manager

AGREEMENT BETWEEN OWNER AND CONTRACTOR FOR CONSTRUCTION CONTRACT (STIPULATED PRICE)

Resolution/Work Order #0721C

This Agreement is by and between the City of Fort Wayne – Board of Public Works (“Owner”) and Malott Contracting, Inc. (“Contractor”).

Terms used in this Agreement have the meanings stated in the General Conditions and the Supplementary Conditions.

Owner and Contractor hereby agree as follows:

ARTICLE 1—WORK

1.01 Contractor shall complete all Work as specified or indicated in the Contract Documents. The Work is generally described as follows: **Improve the Westchester Neighborhood and S.W. Waynedale Neighborhood, by the removal of the existing concrete streets and replacing with new concrete streets. The removal and replacement of select existing sidewalk and drive approaches. Removing existing curb ramps and replacing with new ADA compliant curb ramps. There will be subsurface drainage installed and the replacement and adjustment of existing castings with the restoration of disturbed areas.**

ARTICLE 2—THE PROJECT

2.01 The Project, of which the Work under the Contract Documents is a part, is generally described as follows: **COMMUNITY CROSSINGS GRANT 2025**

ARTICLE 3—ENGINEER

3.01 The part of the Project that pertains to the Work has been designed by **TRANSPORTATION ENGINEERING.**

ARTICLE 4—CONTRACT TIMES

4.01 *Time is of the Essence*

A. All time limits for Milestones, if any, Substantial Completion, and completion and readiness for final payment as stated in the Contract Documents are of the essence of the Contract.

4.02 *Contract Times: Dates*

A. The Work will be substantially complete on or before **9/14/2026**, and completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions on or before **9/21/2026.**

4.03 *Milestones*

- A. Parts of the Work must be substantially completed on or before the following Milestone(s):
1. Milestone 1 **School will need to be out of session for construction of Elzey Street and a section of McArthur**
 2. Milestone 2 **[N/A]**
 3. Milestone 3 **[N/A]**

4.05 *Liquidated Damages*

- A. Contractor and Owner recognize that time is of the essence as stated in Paragraph 4.01 above and that Owner will suffer financial and other losses if the Work is not completed and Milestones not achieved within the Contract Times, as duly modified. The parties also recognize the delays, expense, and difficulties involved in proving, in a legal or arbitration proceeding, the actual loss suffered by Owner if the Work is not completed on time. Accordingly, instead of requiring any such proof, Owner and Contractor agree that as liquidated damages for delay (but not as a penalty):
1. *Substantial Completion:* Contractor shall pay Owner up to **\$1000** for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for Substantial Completion, until the Work is substantially complete.
 2. *Completion of Remaining Work:* After Substantial Completion, if Contractor shall neglect, refuse, or fail to complete the remaining Work within the Contract Times (as duly adjusted pursuant to the Contract) for completion and readiness for final payment, Contractor shall pay Owner up to **\$1000** for each day that expires after such time until the Work is completed and ready for final payment.
 3. *Milestones:* Contractor shall pay Owner up to **\$1000** for each day that expires after the time (as duly adjusted pursuant to the Contract) specified above for achievement of Milestone 1, until Milestone 1 is achieved, or until the time specified for Substantial Completion is reached, at which time the rate indicated in Paragraph 4.05.A.1 will apply, rather than the Milestone rate.
 4. Liquidated damages for failing to timely attain Milestones, Substantial Completion, and final completion are not additive, and will not be imposed concurrently.
- B. If Owner recovers liquidated damages for a delay in completion by Contractor, then such liquidated damages are Owner's sole and exclusive remedy for such delay, and Owner is precluded from recovering any other damages, whether actual, direct, excess, or consequential, for such delay, except for special damages (if any) specified in this Agreement.

ARTICLE 5—CONTRACT PRICE

- 5.01 Owner shall pay Contractor for completion of the Work in accordance with the Contract Documents, the amounts that follow, subject to adjustment under the Contract:
- A. For all Work, at the prices stated in Contractor's Bid, attached hereto as an exhibit.
 - B. Total of all unit prices **\$6,680,662.37**.

ARTICLE 6—PAYMENT PROCEDURES

6.01 *Submittal and Processing of Payments*

- A. Contractor shall submit Applications for Payment in accordance with Article 15 of the General Conditions. Applications for Payment will be processed by Engineer as provided in the General Conditions.

6.02 *Progress Payments; Retainage*

- A. Owner shall make progress payments on the basis of Contractor's Applications for Payment no more often than every 30 days during performance of the Work as provided in Paragraph 6.02.A.1 below, provided that such Applications for Payment have been submitted in a timely manner and otherwise meet the requirements of the Contract. All such payments will be measured by the Schedule of Values established as provided in the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no Schedule of Values, as provided elsewhere in the Contract.
 - 1. Prior to Substantial Completion, progress payments will be made in an amount equal to the percentage indicated below but, in each case, less the aggregate of payments previously made and less such amounts as Owner may withhold, including but not limited to liquidated damages, in accordance with the Contract.
 - a. 95 percent of the value of the Work completed (with the balance being retainage).
 - b. 95 percent of cost of materials and equipment not incorporated in the Work (with the balance being retainage).

6.03 *Final Payment*

- A. Upon final completion and acceptance of the Work, Owner shall pay the remainder of the Contract Price in accordance with Paragraph 15.06 of the General Conditions.

ARTICLE 7—CONTRACT DOCUMENTS

7.01 *Contents*

- A. The Contract Documents consist of all of the following:
 - 1. This Agreement.

2. Bonds:
 - a. Performance bond (together with power of attorney).
 - b. Payment bond (together with power of attorney).
 3. General Conditions.
 4. Supplementary Conditions.
 5. Specifications as listed in the table of contents of the project manual (copy of list attached).
 6. Drawings (not attached but incorporated by reference) consisting of **35** sheets with each sheet bearing the following general title: **Community Crossing Grant 2025**
 7. Addenda (numbers [**1**] to [**1**], inclusive).
 8. Exhibits to this Agreement (enumerated as follows):
 - a. Drug Policy Acknowledgement Form (Project Bids under \$150,000.00) or Written copy of Contractors Drug Policy (Project Bids over \$150,000.00)
 - b. E-Verify Affidavit
 - c. Escrow account agreement
 9. The following which may be delivered or issued on or after the Effective Date of the Contract and are not attached hereto:
 - a. Notice to Proceed.
 - b. Work Change Directives.
 - c. Change Orders.
 - d. Field Orders.
 - e. Warranty Bond, if any.
- B. The Contract Documents listed in Paragraph 7.01.A are attached to this Agreement (except as expressly noted otherwise above).
- C. There are no Contract Documents other than those listed above in this Article 7.
- D. The Contract Documents may only be amended, modified, or supplemented as provided in the Contract.

ARTICLE 8—REPRESENTATIONS, CERTIFICATIONS, AND STIPULATIONS

8.01 *Contractor's Representations*

- A. In order to induce Owner to enter into this Contract, Contractor makes the following representations:
1. Contractor has examined and carefully studied the Contract Documents, including Addenda.
 2. Contractor has visited the Site, conducted a thorough visual examination of the Site and adjacent areas, and become familiar with the general, local, and Site conditions that may affect cost, progress, and performance of the Work.
 3. Contractor is familiar with all Laws and Regulations that may affect cost, progress, and performance of the Work.
 4. Contractor has carefully studied the reports of explorations and tests of subsurface conditions at or adjacent to the Site and the drawings of physical conditions relating to existing surface or subsurface structures at the Site that have been identified in the Supplementary Conditions, with respect to the Technical Data in such reports and drawings.
 5. Contractor has carefully studied the reports and drawings relating to Hazardous Environmental Conditions, if any, at or adjacent to the Site that have been identified in the Supplementary Conditions, with respect to Technical Data in such reports and drawings.
 6. Contractor has considered the information known to Contractor itself; information commonly known to contractors doing business in the locality of the Site; information and observations obtained from visits to the Site; the Contract Documents; and the Technical Data identified in the Supplementary Conditions or by definition, with respect to the effect of such information, observations, and Technical Data on (a) the cost, progress, and performance of the Work; (b) the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor; and (c) Contractor's safety precautions and programs.
 7. Based on the information and observations referred to in the preceding paragraph, Contractor agrees that no further examinations, investigations, explorations, tests, studies, or data are necessary for the performance of the Work at the Contract Price, within the Contract Times, and in accordance with the other terms and conditions of the Contract.
 8. Contractor is aware of the general nature of work to be performed by Owner and others at the Site that relates to the Work as indicated in the Contract Documents.

9. Contractor has given Engineer written notice of all conflicts, errors, ambiguities, or discrepancies that Contractor has discovered in the Contract Documents, and of discrepancies between Site conditions and the Contract Documents, and the written resolution thereof by Engineer is acceptable to Contractor.
10. The Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.
11. Contractor's entry into this Contract constitutes an incontrovertible representation by Contractor that without exception all prices in the Agreement are premised upon performing and furnishing the Work required by the Contract Documents.

8.02 *Contractor's Certifications*

- A. Contractor certifies that it has not engaged in corrupt, fraudulent, collusive, or coercive practices in competing for or in executing the Contract. For the purposes of this Paragraph 8.02:
 1. "corrupt practice" means the offering, giving, receiving, or soliciting of anything of value likely to influence the action of a public official in the bidding process or in the Contract execution;
 2. "fraudulent practice" means an intentional misrepresentation of facts made (a) to influence the bidding process or the execution of the Contract to the detriment of Owner, (b) to establish Bid or Contract prices at artificial non-competitive levels, or (c) to deprive Owner of the benefits of free and open competition;
 3. "collusive practice" means a scheme or arrangement between two or more Bidders, with or without the knowledge of Owner, a purpose of which is to establish Bid prices at artificial, non-competitive levels; and
 4. "coercive practice" means harming or threatening to harm, directly or indirectly, persons or their property to influence their participation in the bidding process or affect the execution of the Contract.

8.03 *Standard General Conditions*

- A. Owner stipulates that if the General Conditions that are made a part of this Contract are EJCDC® C-700, Standard General Conditions for the Construction Contract (2018), published by the Engineers Joint Contract Documents Committee, and if Owner is the party that has furnished said General Conditions, then Owner has plainly shown all modifications to the standard wording of such published document to the Contractor, through a process such as highlighting or "track changes" (redline/strikeout), or in the Supplementary Conditions.

ARTICLE 9—MISCELLANEOUS

9.01 Terms

Terms used in this Agreement will have the meanings stated in the General Conditions

9.02 Severability

Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon Owner and Contractor, who agree that the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.

9.03 Emerging Business Enterprise(EBE) Participation

EBE Retainage Requirements – If the Contractor is in compliance with the provisions of the construction Contract the Owner will make payments for such work performed and completed. Pursuant to Executive Order 90-01 (amended 5-8-06); the Owner will retain five percent (5%) of the Contract Price to ensure compliance with the EBE participation requirements. Upon final inspection and acceptance of the Work, and determination by the Fort Wayne Board of Public Works that the Contractor has made a good faith effort to subcontract ten percent (10%) of the Contract Price to emerging business enterprises, the Contractor will be paid in full.

In the event there is a determination that good faith compliance with these EBE participation requirements has not occurred, appropriate reduction in the final payment pursuant to paragraph 9.03.E will be made.

If the Contract Price is in excess of \$200,000, the contract will be subject to the standard Board of Public Works escrow agreement. However, payments to the Contractor are not to exceed 95% of the total Contract Price until the Owner has verified that the Contractor has made good faith efforts to attain the 10% EBE goal stipulated in here within. Payment of the final 5% of the total Contract Price will be dependent upon acceptance of the Work, in accordance with Paragraph 15.06 of the General Conditions, and good faith efforts to comply with these EBE participation requirements; subject to reduction in the event of non-compliance as provided in paragraph 9.03.E.

- A. Request for Waiver – If, at the time final payment application is made, Contractor has not attained the ten percent (10%) EBE goal, Contractor shall file with the final payment application a “Request for Waiver.” Said Request for Waiver shall contain a written description of the efforts taken by Contractor to attain the ten percent (10%) EBE goal.
- B. Determination of Waiver Requests – The Vendor Compliance Department of the City of Fort Wayne shall examine all Requests for Waiver to determine if Contractor’s efforts constitute good faith efforts to attain such goal and shall submit recommendations concerning said requests for Waiver for the final determination of the Board of Public Works of the City of Fort Wayne.
- C. Good Faith Efforts. – In determining whether or not the Contractor used “good faith” efforts, the following shall be considered:

1. Whether the contract can be subdivided as determined by the Engineer and Administrator of Contract Compliance;
 2. Availability of certified EBE businesses to participate as subcontractors;
 3. Non-competitive price quotes received from EBE firms. The Board of Public Works' determination for granting a reduction or waiver of the goal because of higher quotes from EBE firms will be based on factors that include, but are not limited to the following:
 - a. The Engineer's estimate for the work under a specific contract;
 - b. The Contractor's own estimate for the work under the subcontract;
 - c. An average of the valid prices quoted for the subcontract;
 - d. Demonstrated increase in other contract costs as a result of sub-contracting to EBE firm(s).
 4. Documented measures taken by the Contractor to comply with the EBE participation goal;
 5. EBE subcontractor failed to fulfill their obligation in regard to the time delivery of goods and/or services. Also in regards to the quality of the goods and/or services set forth in the bid specifications.
 6. Such other matters as the Board of Public Works deems relevant.
- D. Consequences of Noncompliance – In the event the Board of Public Works approves a recommendation that Contractor failed to make good faith efforts at compliance, the Contract Price shall be reduced by the amount calculated as the difference between the EBE participation goal of 10% and the actual participation level met by the Contractor, but in no case shall it be reduced by more than 5%. Said amount shall be added to the City of Fort Wayne EBE Bond Guarantee Fund and Contractor agrees to accept the reduced amount as full payment under the terms of his/her Contract.
- E. Waiver Approved – In the event the Board of Public Works determines that a good faith effort to comply with these EBE participation requirements has been made, the Contract Price shall not be reduced, and the balance owing to the Contractor shall be paid in full.

ACKNOWLEDGMENT

STATE OF INDIANA)
SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named _____ who being by me first duly sworn upon his oath says that he is the _____ of _____ and as such duly authorized to execute the foregoing instrument and acknowledged the same as the voluntary act and deed of _____ for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

ACKNOWLEDGMENT

STATE OF INDIANA)
SS:)
COUNTY OF ALLEN)

BEFORE ME, a Notary Public, in and for said County and State, this ____ day of _____, 20__, personally appeared the within named **Sharon Tucker, Shan Gunawardena, Kumar Menon, Chris Guerrero, and Michelle Fulk-Vondran**, by me personally known, who being by me duly sworn said that they are respectively the **Mayor of the City of Fort Wayne**, and **Chairman, Members, and Clerk of the Board of Public Works of the City of Fort Wayne, Indiana**, and that they signed said instrument on behalf of the City of Fort Wayne, Indiana, with full authority so to do and acknowledge said instrument to be in the voluntary act and deed of said **City** for the uses and purposes therein set forth.

IN WITNESS WHEREOF, hereunto subscribed my name, affixed my official seal.

Notary Public

Printed Name of Notary

My Commission Expires:

Resident of _____ County.

IN WITNESS WHEREOF, Owner and Contractor have signed this Agreement (Contract/Resolution Number **0721C**).

This Agreement will be effective on _____ (which is the Effective Date of the Agreement).

CONTRACTOR

Malott Contracting, Inc.

OWNER

CITY OF FORT WAYNE

BY: _____

Print Name _____

BY: _____

SHARON TUCKER, MAYOR

TITLE: _____

BOARD OF PUBLIC WORKS

DATE: _____

(Date signed by Contractor)

BY: _____

SHAN GUNAWARDENA, CHAIR

Address for giving notices:

BY: _____

KUMAR MENON, MEMBER

BY: _____

CHRIS GUERRERO, MEMBER

ATTEST: _____

MICHELLE FULK-VONDRAN, CLERK

DATE: _____

(Date signed by Board)

0721C - Community Crossings Grant 2025 (#9687333)
Owner: Public Works
Solicitor: Fort Wayne IN, City of
05/29/2025 02:00 PM EDT

Section Title	Line Item	Item Code	Item Description	UoM	Quantity	Malott Contracting, Inc.	
						Unit Price	Extension
0721C - 2025 Commun							\$6,530,662.37
	1	105-06845 LINE A KIMBERTON	CONSTRUCTION ENGINEERING	LS	1	\$2,553.50	\$2,553.50
	2	110-01001 LINE A KIMBERTON	MOBILIZATION AND DEMOBILIZATION	LS	1	\$5,693.50	\$5,693.50
	3	201-02255 LINE A KIMBERTON	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,359.00	\$1,359.00
	4	201-02260 LINE A KIMBERTON	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	5	\$1,430.00	\$7,150.00
	5	201-02265 LINE A KIMBERTON	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
	6	201-02270 LINE A KIMBERTON	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
	7	202-02240 LINE A KIMBERTON	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	2180	\$12.71	\$27,707.80
	8	202-93615 LINE A KIMBERTON	CONCRETE REMOVE	SYS	520	\$16.06	\$8,351.20
	9	203-02000 LINE A KIMBERTON	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	5	\$38.67	\$193.35
	10	205-06933 LINE A KIMBERTON	TEMPORARY INLET PROTECTION	EACH	1	\$102.00	\$102.00
	11	214-11796 LINE A KIMBERTON	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	260	\$8.36	\$2,173.60
	12	301-FWR03 LINE A KIMBERTON	COMPATED AGGREGATE NO. 53	TON	734.3	\$34.54	\$25,362.72
	13	304-07490 LINE A KIMBERTON	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
	14	502-FWR01 LINE A KIMBERTON	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	2180	\$47.00	\$102,460.00
	15	502-11564 LINE A KIMBERTON	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
	16	604-FWR01 LINE A KIMBERTON	DETECTABLE WARNING SURFACES	EACH	2	\$250.00	\$500.00
	17	604-06070 LINE A KIMBERTON	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	240	\$58.00	\$13,920.00
	18	604-08086 LINE A KIMBERTON	CURB RAMP, CONCRETE	SYS	8	\$110.00	\$880.00
	19	605-06120 LINE A KIMBERTON	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
	20	610-07713 LINE A KIMBERTON	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
	21	610-08446 LINE A KIMBERTON	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	280	\$68.00	\$19,040.00
	22	611-08233 LINE A KIMBERTON	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
	23	621-FWR01 LINE A KIMBERTON	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1100	\$2.53	\$2,783.00
	24	621-FWR19 LINE A KIMBERTON	TOPSOIL	TON	60	\$51.00	\$3,060.00
	25	715-FWR27 LINE A KIMBERTON	PIPE - 12" CMP	LFT	30	\$78.71	\$2,361.30
	26	715-FWR39 LINE A KIMBERTON	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1420	\$9.74	\$13,830.80
	27	715-94530 LINE A KIMBERTON	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
	28	720-FWR10 LINE A KIMBERTON	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$203.50	\$0.00
	29	720-FWR31 LINE A KIMBERTON	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$660.00	\$0.00
	30	720-FWR37 LINE A KIMBERTON	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH		\$858.00	\$0.00
	31	801-FWR01 LINE A KIMBERTON	MAINTENANCE OF TRAFFIC	LS	1	\$6,000.00	\$6,000.00
	32	808-10033 LINE A KIMBERTON	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
	33	808-10034 LINE A KIMBERTON	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
	34	808-10036 LINE A KIMBERTON	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
	35	808-10037 LINE A KIMBERTON	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
	36	808-10051 LINE A KIMBERTON	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
	37	808-10052 LINE A KIMBERTON	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
	38	808-10053 LINE A KIMBERTON	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
	39	808-10056 LINE A KIMBERTON	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
	40	808-10077 LINE A KIMBERTON	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
	41	105-06845 LINE B DOWNINGTOWN D	CONSTRUCTION ENGINEERING	LS	1	\$2,702.00	\$2,702.00
	42	110-01001 LINE B DOWNINGTOWN D	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,040.00	\$6,040.00
	43	201-02255 LINE B DOWNINGTOWN D	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
	44	201-02260 LINE B DOWNINGTOWN D	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
	45	201-02265 LINE B DOWNINGTOWN D	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
	46	201-02270 LINE B DOWNINGTOWN D	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
	47	202-02240 LINE B DOWNINGTOWN D	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	5120	\$12.71	\$65,075.20
	48	202-93615 LINE B DOWNINGTOWN D	CONCRETE REMOVE	SYS	960	\$17.22	\$16,531.20
	49	203-02000 LINE B DOWNINGTOWN D	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	10	\$38.61	\$386.10
	50	205-06933 LINE B DOWNINGTOWN D	TEMPORARY INLET PROTECTION	EACH	6	\$102.00	\$612.00
	51	214-11796 LINE B DOWNINGTOWN D	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	2060	\$8.36	\$17,221.60
	52	301-FWR03 LINE B DOWNINGTOWN D	COMPATED AGGREGATE NO. 53	TON	1418.1	\$35.75	\$50,697.08
	53	304-07490 LINE B DOWNINGTOWN D	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
	54	502-FWR01 LINE B DOWNINGTOWN D	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	5120	\$48.00	\$245,760.00
	55	502-11564 LINE B DOWNINGTOWN D	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
	56	604-FWR01 LINE B DOWNINGTOWN D	DETECTABLE WARNING SURFACES	EACH	6	\$250.00	\$1,500.00
	57	604-06070 LINE B DOWNINGTOWN D	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	580	\$58.00	\$33,640.00
	58	604-08086 LINE B DOWNINGTOWN D	CURB RAMP, CONCRETE	SYS	26	\$110.00	\$2,860.00
	59	605-06120 LINE B DOWNINGTOWN D	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
	60	610-07713 LINE B DOWNINGTOWN D	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
	61	610-08446 LINE B DOWNINGTOWN D	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	344	\$68.00	\$23,392.00
	62	611-08233 LINE B DOWNINGTOWN D	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
	63	621-FWR01 LINE B DOWNINGTOWN D	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1500	\$2.53	\$3,795.00
	64	621-FWR19 LINE B DOWNINGTOWN D	TOPSOIL	TON	20	\$51.00	\$1,020.00
	65	715-FWR27 LINE B DOWNINGTOWN D	PIPE - 12" CMP	LFT		\$78.71	\$0.00
	66	715-FWR39 LINE B DOWNINGTOWN D	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	3500	\$9.63	\$33,705.00
	67	715-94530 LINE B DOWNINGTOWN D	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	EACH	6	\$203.50	\$1,221.00
	68	720-FWR10 LINE B DOWNINGTOWN D	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
	69	720-FWR31 LINE B DOWNINGTOWN D	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	4	\$660.00	\$2,640.00
	70	720-FWR37 LINE B DOWNINGTOWN D	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
	71	801-FWR01 LINE B DOWNINGTOWN D	MAINTENANCE OF TRAFFIC	LS	1	\$7,000.00	\$7,000.00
	72	808-10033 LINE B DOWNINGTOWN D	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
	73	808-10034 LINE B DOWNINGTOWN D	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
	74	808-10036 LINE B DOWNINGTOWN D	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
	75	808-10037 LINE B DOWNINGTOWN D	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
	76	808-10051 LINE B DOWNINGTOWN D	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
	77	808-10052 LINE B DOWNINGTOWN D	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
	78	808-10053 LINE B DOWNINGTOWN D	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
	79	808-10056 LINE B DOWNINGTOWN D	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
	80	808-10077 LINE B DOWNINGTOWN D	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
	81	105-06845 LINE C BERWYN LN	CONSTRUCTION ENGINEERING	LS	1	\$2,548.00	\$2,548.00
	82	110-01001 LINE C BERWYN LN	MOBILIZATION AND DEMOBILIZATION	LS	1	\$5,693.50	\$5,693.50
	83	201-02255 LINE C BERWYN LN	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	2	\$1,358.50	\$2,717.00
	84	201-02260 LINE C BERWYN LN	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
	85	201-02265 LINE C BERWYN LN	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
	86	201-02270 LINE C BERWYN LN	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
	87	202-02240 LINE C BERWYN LN	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	1300	\$12.71	\$16,523.00
	88	202-93615 LINE C BERWYN LN	CONCRETE REMOVE	SYS	270	\$15.73	\$4,247.10
	89	203-02000 LINE C BERWYN LN	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	5	\$38.67	\$193.35
	90	205-06933 LINE C BERWYN LN	TEMPORARY INLET PROTECTION	EACH		\$102.00	\$0.00
	91	214-11796 LINE C BERWYN LN	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	530	\$8.36	\$4,430.80

92	301-FWR03 LINE C BERWYN LN	COMPATED AGGREGATE NO. 53	TON	504.1	\$33.44	\$16,857.10
93	304-07490 LINE C BERWYN LN	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
94	502-FWR01 LINE C BERWYN LN	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	1300	\$48.00	\$62,400.00
95	502-11564 LINE C BERWYN LN	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
96	604-FWR01 LINE C BERWYN LN	DETECTABLE WARNING SURFACES	EACH	4	\$250.00	\$1,000.00
97	604-06070 LINE C BERWYN LN	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	130	\$58.00	\$7,540.00
98	604-08086 LINE C BERWYN LN	CURB RAMP, CONCRETE	SYS	22	\$110.00	\$2,420.00
99	605-06120 LINE C BERWYN LN	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
100	610-07713 LINE C BERWYN LN	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
101	610-08446 LINE C BERWYN LN	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	108	\$68.00	\$7,344.00
102	611-08233 LINE C BERWYN LN	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
103	621-FWR01 LINE C BERWYN LN	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	620	\$2.53	\$1,568.60
104	621-FWR19 LINE C BERWYN LN	TOPSOIL	TON	30	\$51.00	\$1,530.00
105	715-FWR27 LINE C BERWYN LN	PIPE - 12" CMP	LFT	30	\$77.00	\$2,310.00
106	715-FWR39 LINE C BERWYN LN	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	830	\$10.18	\$8,449.40
107	715-94530 LINE C BERWYN LN	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
108	720-FWR10 LINE C BERWYN LN	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$240.00	\$0.00
109	720-FWR31 LINE C BERWYN LN	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$760.00	\$0.00
110	720-FWR37 LINE C BERWYN LN	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
111	801-FWR01 LINE C BERWYN LN	MAINTENANCE OF TRAFFIC	LS	1	\$6,000.00	\$6,000.00
112	808-10033 LINE C BERWYN LN	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
113	808-10034 LINE C BERWYN LN	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
114	808-10036 LINE C BERWYN LN	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
115	808-10037 LINE C BERWYN LN	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
116	808-10051 LINE C BERWYN LN	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
117	808-10052 LINE C BERWYN LN	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
118	808-10053 LINE C BERWYN LN	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
119	808-10056 LINE C BERWYN LN	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
120	808-10077 LINE C BERWYN LN	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
121	105-06845 LINE D CHATHAM DR.	CONSTRUCTION ENGINEERING	LS	1	\$2,702.00	\$2,702.00
122	110-01001 LINE D CHATHAM DR.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,029.00	\$6,029.00
123	201-02255 LINE D CHATHAM DR.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	12	\$1,358.50	\$16,302.00
124	201-02260 LINE D CHATHAM DR.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
125	201-02265 LINE D CHATHAM DR.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
126	201-02270 LINE D CHATHAM DR.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
127	202-02240 LINE D CHATHAM DR.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	3770	\$12.65	\$47,690.50
128	202-93615 LINE D CHATHAM DR.	CONCRETE REMOVE	SYS	1000	\$14.85	\$14,850.00
129	203-02000 LINE D CHATHAM DR.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	10	\$38.61	\$386.10
130	205-06933 LINE D CHATHAM DR.	TEMPORARY INLET PROTECTION	EACH		\$102.00	\$0.00
131	214-11796 LINE D CHATHAM DR.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	1500	\$8.36	\$12,540.00
132	301-FWR03 LINE D CHATHAM DR.	COMPATED AGGREGATE NO. 53	TON	1023.3	\$36.41	\$37,258.35
133	304-07490 LINE D CHATHAM DR.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
134	502-FWR01 LINE D CHATHAM DR.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	3770	\$48.00	\$180,960.00
135	502-11564 LINE D CHATHAM DR.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
136	604-FWR01 LINE D CHATHAM DR.	DETECTABLE WARNING SURFACES	EACH	6	\$250.00	\$1,500.00
137	604-06070 LINE D CHATHAM DR.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	590	\$58.00	\$34,220.00
138	604-08086 LINE D CHATHAM DR.	CURB RAMP, CONCRETE	SYS	30	\$110.00	\$3,300.00
139	605-06120 LINE D CHATHAM DR.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
140	610-07713 LINE D CHATHAM DR.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
141	610-08446 LINE D CHATHAM DR.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	380	\$68.00	\$25,840.00
142	611-08233 LINE D CHATHAM DR.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
143	621-FWR01 LINE D CHATHAM DR.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1500	\$2.53	\$3,795.00
144	621-FWR19 LINE D CHATHAM DR.	TOPSOIL	TON	40	\$51.00	\$2,040.00
145	715-FWR27 LINE D CHATHAM DR.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
146	715-FWR39 LINE D CHATHAM DR.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	2400	\$9.90	\$23,760.00
147	715-94530 LINE D CHATHAM DR.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
148	720-FWR10 LINE D CHATHAM DR.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
149	720-FWR31 LINE D CHATHAM DR.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$760.00	\$0.00
150	720-FWR37 LINE D CHATHAM DR.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
151	801-FWR01 LINE D CHATHAM DR.	MAINTENANCE OF TRAFFIC	LS	1	\$6,000.00	\$6,000.00
152	808-10033 LINE D CHATHAM DR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
153	808-10034 LINE D CHATHAM DR.	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
154	808-10036 LINE D CHATHAM DR.	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
155	808-10037 LINE D CHATHAM DR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
156	808-10051 LINE D CHATHAM DR.	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
157	808-10052 LINE D CHATHAM DR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
158	808-10053 LINE D CHATHAM DR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
159	808-10056 LINE D CHATHAM DR.	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
160	808-10077 LINE D CHATHAM DR.	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
161	105-06845 LINE E LANDSDOWNE DR.	CONSTRUCTION ENGINEERING	LS	1	\$2,625.00	\$2,625.00
162	110-01001 LINE E LANDSDOWNE DR.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,700.00	\$6,700.00
163	201-02255 LINE E LANDSDOWNE DR.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
164	201-02260 LINE E LANDSDOWNE DR.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	5	\$1,430.00	\$7,150.00
165	201-02265 LINE E LANDSDOWNE DR.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
166	201-02270 LINE E LANDSDOWNE DR.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
167	202-02240 LINE E LANDSDOWNE DR.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	4240	\$12.71	\$53,890.40
168	202-93615 LINE E LANDSDOWNE DR.	CONCRETE REMOVE	SYS	850	\$17.16	\$14,586.00
169	203-02000 LINE E LANDSDOWNE DR.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	5	\$38.61	\$193.05
170	205-06933 LINE E LANDSDOWNE DR.	TEMPORARY INLET PROTECTION	EACH	5	\$102.00	\$510.00
171	214-11796 LINE E LANDSDOWNE DR.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	1690	\$8.36	\$14,128.40
172	301-FWR03 LINE E LANDSDOWNE DR.	COMPATED AGGREGATE NO. 53	TON	1230	\$35.09	\$43,160.70
173	304-07490 LINE E LANDSDOWNE DR.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
174	502-FWR01 LINE E LANDSDOWNE DR.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	4240	\$48.25	\$204,580.00
175	502-11564 LINE E LANDSDOWNE DR.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
176	604-FWR01 LINE E LANDSDOWNE DR.	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
177	604-06070 LINE E LANDSDOWNE DR.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	440	\$58.00	\$25,520.00
178	604-08086 LINE E LANDSDOWNE DR.	CURB RAMP, CONCRETE	SYS		\$120.00	\$0.00
179	605-06120 LINE E LANDSDOWNE DR.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
180	610-07713 LINE E LANDSDOWNE DR.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
181	610-08446 LINE E LANDSDOWNE DR.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	410	\$68.00	\$27,880.00
182	611-08233 LINE E LANDSDOWNE DR.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
183	621-FWR01 LINE E LANDSDOWNE DR.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	2025	\$2.53	\$5,123.25
184	621-FWR19 LINE E LANDSDOWNE DR.	TOPSOIL	TON	80	\$51.00	\$4,080.00
185	715-FWR27 LINE E LANDSDOWNE DR.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
186	715-FWR39 LINE E LANDSDOWNE DR.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	2800	\$9.63	\$26,964.00
187	715-94530 LINE E LANDSDOWNE DR.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	3	\$203.50	\$610.50
188	720-FWR10 LINE E LANDSDOWNE DR.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$250.00	\$0.00
189	720-FWR31 LINE E LANDSDOWNE DR.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$760.00	\$0.00
190	720-FWR37 LINE E LANDSDOWNE DR.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	5	\$858.00	\$4,290.00

191	801-FWR01 LINE E LANDSDOWNE DR	MAINTENANCE OF TRAFFIC	LS	1	\$8,000.00	\$8,000.00
192	808-10033 LINE E LANDSDOWNE DR	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
193	808-10034 LINE E LANDSDOWNE DR	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
194	808-10036 LINE E LANDSDOWNE DR	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
195	808-10037 LINE E LANDSDOWNE DR	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
196	808-10051 LINE E LANDSDOWNE DR	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
197	808-10052 LINE E LANDSDOWNE DR	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
198	808-10053 LINE E LANDSDOWNE DR	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
199	808-10056 LINE E LANDSDOWNE DR	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
200	808-10077 LINE E LANDSDOWNE DR	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
201	105-06845 LINE F CHADDSFORD DR.	CONSTRUCTION ENGINEERING	LS	1	\$2,999.00	\$2,999.00
202	110-01001 LINE F CHADDSFORD DR.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$7,376.50	\$7,376.50
203	201-02255 LINE F CHADDSFORD DR.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	5	\$1,358.50	\$6,792.50
204	201-02260 LINE F CHADDSFORD DR.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	2	\$1,430.00	\$2,860.00
205	201-02265 LINE F CHADDSFORD DR.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
206	201-02270 LINE F CHADDSFORD DR.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
207	202-02240 LINE F CHADDSFORD DR.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	7250	\$12.71	\$92,147.50
208	202-93615 LINE F CHADDSFORD DR.	CONCRETE REMOVE	SYS	835	\$17.49	\$14,604.15
209	203-02000 LINE F CHADDSFORD DR.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS	5	\$38.67	\$193.35
210	205-06933 LINE F CHADDSFORD DR.	TEMPORARY INLET PROTECTION	EACH	5	\$102.00	\$510.00
211	214-11796 LINE F CHADDSFORD DR.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	1820	\$8.36	\$15,215.20
212	301-FWR03 LINE F CHADDSFORD DR.	COMPATED AGGREGATE NO. 53	TON	1905	\$36.03	\$68,637.15
213	304-07490 LINE F CHADDSFORD DR.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
214	502-FWR01 LINE F CHADDSFORD DR.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	7250	\$47.00	\$340,750.00
215	502-11564 LINE F CHADDSFORD DR.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
216	604-FWR01 LINE F CHADDSFORD DR.	DETECTABLE WARNING SURFACES	EACH	2	\$250.00	\$500.00
217	604-06070 LINE F CHADDSFORD DR.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	800	\$58.00	\$46,400.00
218	604-08086 LINE F CHADDSFORD DR.	CURB RAMP, CONCRETE	SYS	20	\$110.00	\$2,200.00
219	605-06120 LINE F CHADDSFORD DR.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
220	610-07713 LINE F CHADDSFORD DR.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
221	610-08446 LINE F CHADDSFORD DR.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	375	\$68.00	\$25,500.00
222	611-08233 LINE F CHADDSFORD DR.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
223	621-FWR01 LINE F CHADDSFORD DR.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	3500	\$2.53	\$8,855.00
224	621-FWR19 LINE F CHADDSFORD DR.	TOPSOIL	TON	100	\$51.00	\$5,100.00
225	715-FWR27 LINE F CHADDSFORD DR.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
226	715-FWR39 LINE F CHADDSFORD DR.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	4840	\$10.01	\$48,448.40
227	715-94530 LINE F CHADDSFORD DR.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	EACH	5	\$203.50	\$1,017.50
228	720-FWR10 LINE F CHADDSFORD DR.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
229	720-FWR31 LINE F CHADDSFORD DR.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$660.00	\$660.00
230	720-FWR37 LINE F CHADDSFORD DR.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	5	\$858.00	\$4,290.00
231	801-FWR01 LINE F CHADDSFORD DR.	MAINTENANCE OF TRAFFIC	LS	1	\$8,000.00	\$8,000.00
232	808-10033 LINE F CHADDSFORD DR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
233	808-10034 LINE F CHADDSFORD DR.	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
234	808-10036 LINE F CHADDSFORD DR.	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
235	808-10037 LINE F CHADDSFORD DR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
236	808-10051 LINE F CHADDSFORD DR.	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
237	808-10052 LINE F CHADDSFORD DR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
238	808-10053 LINE F CHADDSFORD DR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
239	808-10056 LINE F CHADDSFORD DR.	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
240	808-10077 LINE F CHADDSFORD DR.	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
241	105-06845 LINE G BURNS BLVD.	CONSTRUCTION ENGINEERING	LS	1	\$2,130.00	\$2,130.00
242	110-01001 LINE G BURNS BLVD.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$4,681.50	\$4,681.50
243	201-02255 LINE G BURNS BLVD.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
244	201-02260 LINE G BURNS BLVD.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
245	201-02265 LINE G BURNS BLVD.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
246	201-02270 LINE G BURNS BLVD.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
247	202-02240 LINE G BURNS BLVD.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	550	\$13.20	\$7,260.00
248	202-93615 LINE G BURNS BLVD.	CONCRETE REMOVE	SYS	45	\$15.57	\$700.65
249	203-02000 LINE G BURNS BLVD.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
250	205-06933 LINE G BURNS BLVD.	TEMPORARY INLET PROTECTION	EACH	2	\$102.00	\$204.00
251	214-11796 LINE G BURNS BLVD.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	130	\$8.36	\$1,086.80
252	301-FWR03 LINE G BURNS BLVD.	COMPATED AGGREGATE NO. 53	TON	360.7	\$30.69	\$11,069.88
253	304-07490 LINE G BURNS BLVD.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
254	502-FWR01 LINE G BURNS BLVD.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	550	\$47.00	\$25,850.00
255	502-11564 LINE G BURNS BLVD.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
256	604-FWR01 LINE G BURNS BLVD.	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
257	604-06070 LINE G BURNS BLVD.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	30	\$58.00	\$1,740.00
258	604-08086 LINE G BURNS BLVD.	CURB RAMP, CONCRETE	SYS		\$120.00	\$0.00
259	605-06120 LINE G BURNS BLVD.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
260	610-07713 LINE G BURNS BLVD.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
261	610-08446 LINE G BURNS BLVD.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	15	\$68.00	\$1,020.00
262	611-08233 LINE G BURNS BLVD.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
263	621-FWR01 LINE G BURNS BLVD.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	100	\$2.53	\$253.00
264	621-FWR19 LINE G BURNS BLVD.	TOPSOIL	TON	20	\$51.00	\$1,020.00
265	715-FWR27 LINE G BURNS BLVD.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
266	715-FWR39 LINE G BURNS BLVD.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	360	\$12.60	\$4,536.00
267	715-94530 LINE G BURNS BLVD.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	EACH	3	\$203.50	\$610.50
268	720-FWR10 LINE G BURNS BLVD.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$250.00	\$0.00
269	720-FWR31 LINE G BURNS BLVD.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
270	720-FWR37 LINE G BURNS BLVD.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH		\$960.00	\$0.00
271	801-FWR01 LINE G BURNS BLVD.	MAINTENANCE OF TRAFFIC	LS	1	\$5,000.00	\$5,000.00
272	808-10033 LINE G BURNS BLVD.	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
273	808-10034 LINE G BURNS BLVD.	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
274	808-10036 LINE G BURNS BLVD.	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
275	808-10037 LINE G BURNS BLVD.	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
276	808-10051 LINE G BURNS BLVD.	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
277	808-10052 LINE G BURNS BLVD.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
278	808-10053 LINE G BURNS BLVD.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
279	808-10056 LINE G BURNS BLVD.	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
280	808-10077 LINE G BURNS BLVD.	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
281	105-06845 LINE Q NEWTON SQ.	CONSTRUCTION ENGINEERING	LS	1	\$2,405.00	\$2,405.00
282	110-01001 LINE Q NEWTON SQ.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$5,022.50	\$5,022.50
283	201-02255 LINE Q NEWTON SQ.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
284	201-02260 LINE Q NEWTON SQ.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
285	201-02265 LINE Q NEWTON SQ.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
286	201-02270 LINE Q NEWTON SQ.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
287	202-02240 LINE Q NEWTON SQ.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	830	\$12.65	\$10,499.50
288	202-93615 LINE Q NEWTON SQ.	CONCRETE REMOVE	SYS	197.2	\$15.07	\$2,971.80
289	203-02000 LINE Q NEWTON SQ.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00

290	205-06933 LINE Q NEWTON SQ.	TEMPORARY INLET PROTECTION	EACH	2	\$102.00	\$204.00
291	214-11796 LINE Q NEWTON SQ.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	170	\$8.36	\$1,421.20
292	301-FWR03 LINE Q NEWTON SQ.	COMPATED AGGREGATE NO. 53	TON	423	\$32.12	\$13,586.76
293	304-07490 LINE Q NEWTON SQ.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
294	502-FWR01 LINE Q NEWTON SQ.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	830	\$47.00	\$39,010.00
295	502-11564 LINE Q NEWTON SQ.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
296	604-FWR01 LINE Q NEWTON SQ.	DETECTABLE WARNING SURFACES	EACH	2	\$250.00	\$500.00
297	604-06070 LINE Q NEWTON SQ.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	117.2	\$58.00	\$6,797.60
298	604-08086 LINE Q NEWTON SQ.	CURB RAMP, CONCRETE	SYS	32	\$110.00	\$3,520.00
299	605-06120 LINE Q NEWTON SQ.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
300	610-07713 LINE Q NEWTON SQ.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
301	610-08446 LINE Q NEWTON SQ.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	48	\$68.00	\$3,264.00
302	611-08233 LINE Q NEWTON SQ.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
303	621-FWR01 LINE Q NEWTON SQ.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	100	\$2.53	\$253.00
304	621-FWR19 LINE Q NEWTON SQ.	TOPSOIL	TON	2	\$51.00	\$102.00
305	715-FWR27 LINE Q NEWTON SQ.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
306	715-FWR39 LINE Q NEWTON SQ.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	400	\$11.44	\$4,576.00
307	715-94530 LINE Q NEWTON SQ.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50
308	720-FWR10 LINE Q NEWTON SQ.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$250.00	\$0.00
309	720-FWR31 LINE Q NEWTON SQ.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
310	720-FWR37 LINE Q NEWTON SQ.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	1	\$858.00	\$858.00
311	801-FWR01 LINE Q NEWTON SQ.	MAINTENANCE OF TRAFFIC	LS	1	\$6,000.00	\$6,000.00
312	808-10033 LINE Q NEWTON SQ.	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
313	808-10034 LINE Q NEWTON SQ.	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
314	808-10036 LINE Q NEWTON SQ.	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
315	808-10037 LINE Q NEWTON SQ.	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
316	808-10051 LINE Q NEWTON SQ.	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
317	808-10052 LINE Q NEWTON SQ.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
318	808-10053 LINE Q NEWTON SQ.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
319	808-10056 LINE Q NEWTON SQ.	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
320	808-10077 LINE Q NEWTON SQ.	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
321	105-06845 LINE R PICADILLY CIR.	CONSTRUCTION ENGINEERING	LS	1	\$2,251.00	\$2,251.00
322	110-01001 LINE R PICADILLY CIR.	MOBILIZATION AND DEMOBILIZATION	LS	1	\$4,681.50	\$4,681.50
323	201-02255 LINE R PICADILLY CIR.	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
324	201-02260 LINE R PICADILLY CIR.	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
325	201-02265 LINE R PICADILLY CIR.	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
326	201-02270 LINE R PICADILLY CIR.	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
327	202-02240 LINE R PICADILLY CIR.	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	632	\$12.65	\$7,994.80
328	202-93615 LINE R PICADILLY CIR.	CONCRETE REMOVE	SYS	120	\$15.02	\$1,802.40
329	203-02000 LINE R PICADILLY CIR.	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
330	205-06933 LINE R PICADILLY CIR.	TEMPORARY INLET PROTECTION	EACH	2	\$102.00	\$204.00
331	214-11796 LINE R PICADILLY CIR.	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	150	\$8.36	\$1,254.00
332	301-FWR03 LINE R PICADILLY CIR.	COMPATED AGGREGATE NO. 53	TON	352	\$31.63	\$11,133.76
333	304-07490 LINE R PICADILLY CIR.	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
334	502-FWR01 LINE R PICADILLY CIR.	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	632	\$47.00	\$29,704.00
335	502-11564 LINE R PICADILLY CIR.	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
336	604-FWR01 LINE R PICADILLY CIR.	DETECTABLE WARNING SURFACES	EACH	2	\$250.00	\$500.00
337	604-06070 LINE R PICADILLY CIR.	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	18	\$58.00	\$1,044.00
338	604-08086 LINE R PICADILLY CIR.	CURB RAMP, CONCRETE	SYS	32	\$110.00	\$3,520.00
339	605-06120 LINE R PICADILLY CIR.	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
340	610-07713 LINE R PICADILLY CIR.	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
341	610-08446 LINE R PICADILLY CIR.	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	70	\$68.00	\$4,760.00
342	611-08233 LINE R PICADILLY CIR.	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
343	621-FWR01 LINE R PICADILLY CIR.	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	100	\$2.53	\$253.00
344	621-FWR19 LINE R PICADILLY CIR.	TOPSOIL	TON	2	\$51.00	\$102.00
345	715-FWR27 LINE R PICADILLY CIR.	PIPE - 12" CMP	LFT		\$80.00	\$0.00
346	715-FWR39 LINE R PICADILLY CIR.	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	290	\$11.11	\$3,221.90
347	715-94530 LINE R PICADILLY CIR.	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50
348	720-FWR10 LINE R PICADILLY CIR.	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$250.00	\$0.00
349	720-FWR31 LINE R PICADILLY CIR.	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
350	720-FWR37 LINE R PICADILLY CIR.	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	1	\$858.00	\$858.00
351	801-FWR01 LINE R PICADILLY CIR.	MAINTENANCE OF TRAFFIC	LS	1	\$5,000.00	\$5,000.00
352	808-10033 LINE R PICADILLY CIR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
353	808-10034 LINE R PICADILLY CIR.	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
354	808-10036 LINE R PICADILLY CIR.	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
355	808-10037 LINE R PICADILLY CIR.	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
356	808-10051 LINE R PICADILLY CIR.	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
357	808-10052 LINE R PICADILLY CIR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
358	808-10053 LINE R PICADILLY CIR.	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
359	808-10056 LINE R PICADILLY CIR.	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
360	808-10077 LINE R PICADILLY CIR.	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
361	105-06845 LINE H BRADBURY	CONSTRUCTION ENGINEERING	LS	1	\$2,251.00	\$2,251.00
362	110-01001 LINE H BRADBURY	MOBILIZATION AND DEMOBILIZATION	LS	1	\$3,801.50	\$3,801.50
363	201-02255 LINE H BRADBURY	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
364	201-02260 LINE H BRADBURY	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
365	201-02265 LINE H BRADBURY	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
366	201-02270 LINE H BRADBURY	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
367	202-02240 LINE H BRADBURY	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	720	\$12.76	\$9,187.20
368	202-93615 LINE H BRADBURY	CONCRETE REMOVE	SYS	296.3	\$14.58	\$4,320.05
369	203-02000 LINE H BRADBURY	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
370	205-06933 LINE H BRADBURY	TEMPORARY INLET PROTECTION	EACH	1	\$102.00	\$102.00
371	214-11796 LINE H BRADBURY	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	150	\$8.36	\$1,254.00
372	301-FWR03 LINE H BRADBURY	COMPATED AGGREGATE NO. 53	TON	390	\$32.34	\$12,612.60
373	304-07490 LINE H BRADBURY	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	1	\$302.50	\$302.50
374	502-FWR01 LINE H BRADBURY	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	720	\$47.00	\$33,840.00
375	502-11564 LINE H BRADBURY	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
376	604-FWR01 LINE H BRADBURY	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
377	604-06070 LINE H BRADBURY	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	224.5	\$58.00	\$13,021.00
378	604-08086 LINE H BRADBURY	CURB RAMP, CONCRETE	SYS	32	\$110.00	\$3,520.00
379	605-06120 LINE H BRADBURY	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
380	610-07713 LINE H BRADBURY	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
381	610-08446 LINE H BRADBURY	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	39.8	\$68.00	\$2,706.40
382	611-08233 LINE H BRADBURY	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
383	621-FWR01 LINE H BRADBURY	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	318	\$2.53	\$804.54
384	621-FWR19 LINE H BRADBURY	TOPSOIL	TON	5	\$51.00	\$255.00
385	715-FWR27 LINE H BRADBURY	PIPE - 12" CMP	LFT		\$80.00	\$0.00
386	715-FWR39 LINE H BRADBURY	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	474	\$10.62	\$5,033.88
387	715-94530 LINE H BRADBURY	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	3	\$203.50	\$610.50
388	720-FWR10 LINE H BRADBURY	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50

389	720-FWR31 LINE H BRADBURY	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$760.00	\$0.00
390	720-FWR37 LINE H BRADBURY	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
391	801-FWR01 LINE H BRADBURY	MAINTENANCE OF TRAFFIC	LS	1	\$4,000.00	\$4,000.00
392	808-10033 LINE H BRADBURY	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
393	808-10034 LINE H BRADBURY	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
394	808-10036 LINE H BRADBURY	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
395	808-10037 LINE H BRADBURY	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
396	808-10051 LINE H BRADBURY	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
397	808-10052 LINE H BRADBURY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
398	808-10053 LINE H BRADBURY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
399	808-10056 LINE H BRADBURY	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
400	808-10077 LINE H BRADBURY	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
401	105-06845 LINE I BEATY	CONSTRUCTION ENGINEERING	LS	1	\$2,405.00	\$2,405.00
402	110-01001 LINE I BEATY	MOBILIZATION AND DEMOBILIZATION	LS	1	\$5,022.50	\$5,022.50
403	201-02255 LINE I BEATY	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
404	201-02260 LINE I BEATY	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,430.00	\$1,430.00
405	201-02265 LINE I BEATY	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
406	201-02270 LINE I BEATY	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
407	202-02240 LINE I BEATY	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	804	\$12.82	\$10,307.28
408	202-93615 LINE I BEATY	CONCRETE REMOVE	SYS	79	\$16.28	\$1,286.12
409	203-02000 LINE I BEATY	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
410	205-06933 LINE I BEATY	TEMPORARY INLET PROTECTION	EACH	1	\$102.00	\$102.00
411	214-11796 LINE I BEATY	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	322	\$8.36	\$2,691.92
412	301-FWR03 LINE I BEATY	COMPACT AGGREGATE NO. 53	TON	485.5	\$31.02	\$15,060.21
413	304-07490 LINE I BEATY	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	2	\$302.50	\$605.00
414	502-FWR01 LINE I BEATY	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	804	\$48.25	\$38,793.00
415	502-11564 LINE I BEATY	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
416	604-FWR01 LINE I BEATY	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
417	604-06070 LINE I BEATY	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	47	\$58.00	\$2,726.00
418	604-08086 LINE I BEATY	CURB RAMP, CONCRETE	SYS		\$120.00	\$0.00
419	605-06120 LINE I BEATY	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
420	610-07713 LINE I BEATY	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$90.00	\$0.00
421	610-08446 LINE I BEATY	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	32	\$68.00	\$2,176.00
422	611-08233 LINE I BEATY	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH		\$250.00	\$0.00
423	621-FWR01 LINE I BEATY	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	322	\$2.53	\$814.66
424	621-FWR19 LINE I BEATY	TOPSOIL	TON	5	\$51.00	\$255.00
425	715-FWR27 LINE I BEATY	PIPE - 12" CMP	LFT		\$80.00	\$0.00
426	715-FWR39 LINE I BEATY	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	488	\$11.22	\$5,475.36
427	715-94530 LINE I BEATY	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH		\$250.00	\$0.00
428	720-FWR10 LINE I BEATY	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50
429	720-FWR31 LINE I BEATY	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$660.00	\$660.00
430	720-FWR37 LINE I BEATY	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH		\$960.00	\$0.00
431	801-FWR01 LINE I BEATY	MAINTENANCE OF TRAFFIC	LS	1	\$5,000.00	\$5,000.00
432	808-10033 LINE I BEATY	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
433	808-10034 LINE I BEATY	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
434	808-10036 LINE I BEATY	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
435	808-10037 LINE I BEATY	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
436	808-10051 LINE I BEATY	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
437	808-10052 LINE I BEATY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
438	808-10053 LINE I BEATY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
439	808-10056 LINE I BEATY	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
440	808-10077 LINE I BEATY	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
441	105-06845 LINE J ST. LOUIS	CONSTRUCTION ENGINEERING	LS	1	\$2,625.00	\$2,625.00
442	110-01001 LINE J ST. LOUIS	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,370.00	\$6,370.00
443	201-02255 LINE J ST. LOUIS	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,358.50	\$1,358.50
444	201-02260 LINE J ST. LOUIS	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
445	201-02265 LINE J ST. LOUIS	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
446	201-02270 LINE J ST. LOUIS	TREE 60 IN., REMOVE	EACH	1	\$3,146.00	\$3,146.00
447	202-02240 LINE J ST. LOUIS	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	3864	\$12.76	\$49,304.64
448	202-93615 LINE J ST. LOUIS	CONCRETE REMOVE	SYS	739	\$15.68	\$11,587.52
449	203-02000 LINE J ST. LOUIS	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
450	205-06933 LINE J ST. LOUIS	TEMPORARY INLET PROTECTION	EACH	8	\$102.00	\$816.00
451	214-11796 LINE J ST. LOUIS	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	1546	\$8.36	\$12,924.56
452	301-FWR03 LINE J ST. LOUIS	COMPACT AGGREGATE NO. 53	TON	1130	\$35.20	\$39,776.00
453	304-07490 LINE J ST. LOUIS	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	3	\$302.50	\$907.50
454	502-FWR01 LINE J ST. LOUIS	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	3864	\$48.25	\$186,438.00
455	502-11564 LINE J ST. LOUIS	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
456	604-FWR01 LINE J ST. LOUIS	DETECTABLE WARNING SURFACES	EACH	3	\$250.00	\$750.00
457	604-06070 LINE J ST. LOUIS	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	441	\$58.00	\$25,578.00
458	604-08086 LINE J ST. LOUIS	CURB RAMP, CONCRETE	SYS	44	\$110.00	\$4,840.00
459	605-06120 LINE J ST. LOUIS	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
460	610-07713 LINE J ST. LOUIS	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT	30	\$74.00	\$2,220.00
461	610-08446 LINE J ST. LOUIS	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	224	\$68.00	\$15,232.00
462	611-08233 LINE J ST. LOUIS	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	14	\$220.00	\$3,080.00
463	621-FWR01 LINE J ST. LOUIS	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1727	\$2.53	\$4,369.31
464	621-FWR19 LINE J ST. LOUIS	TOPSOIL	TON	120	\$51.00	\$6,120.00
465	715-FWR27 LINE J ST. LOUIS	PIPE - 12" CMP	LFT		\$80.00	\$0.00
466	715-FWR39 LINE J ST. LOUIS	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	2590	\$10.78	\$27,920.20
467	715-94530 LINE J ST. LOUIS	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	3	\$203.50	\$610.50
468	720-FWR10 LINE J ST. LOUIS	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH		\$250.00	\$0.00
469	720-FWR31 LINE J ST. LOUIS	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
470	720-FWR37 LINE J ST. LOUIS	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	7	\$858.00	\$6,006.00
471	801-FWR01 LINE J ST. LOUIS	MAINTENANCE OF TRAFFIC	LS	1	\$6,000.00	\$6,000.00
472	808-10033 LINE J ST. LOUIS	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
473	808-10034 LINE J ST. LOUIS	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
474	808-10036 LINE J ST. LOUIS	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
475	808-10037 LINE J ST. LOUIS	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
476	808-10051 LINE J ST. LOUIS	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
477	808-10052 LINE J ST. LOUIS	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
478	808-10053 LINE J ST. LOUIS	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
479	808-10056 LINE J ST. LOUIS	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
480	808-10077 LINE J ST. LOUIS	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
481	105-06845 LINE K WESTWARD	CONSTRUCTION ENGINEERING	LS	1	\$2,850.50	\$2,850.50
482	110-01001 LINE K WESTWARD	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,700.00	\$6,700.00
483	201-02255 LINE K WESTWARD	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
484	201-02260 LINE K WESTWARD	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	3	\$1,430.00	\$4,290.00
485	201-02265 LINE K WESTWARD	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	2	\$1,573.00	\$3,146.00
486	201-02270 LINE K WESTWARD	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
487	202-02240 LINE K WESTWARD	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	4728	\$12.71	\$60,092.88

488	202-93615 LINE K WESTWARD	CONCRETE REMOVE	SYS	570	\$17.38	\$9,906.60
489	203-02000 LINE K WESTWARD	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
490	205-06933 LINE K WESTWARD	TEMPORARY INLET PROTECTION	EACH	7	\$102.00	\$714.00
491	214-11796 LINE K WESTWARD	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	1900	\$8.36	\$15,884.00
492	301-FWR03 LINE K WESTWARD	COMPATED AGGREGATE NO. 53	TON	1301.4	\$35.31	\$45,952.43
493	304-07490 LINE K WESTWARD	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
494	502-FWR01 LINE K WESTWARD	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	4728	\$48.25	\$228,126.00
495	502-11564 LINE K WESTWARD	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
496	604-FWR01 LINE K WESTWARD	DETECTABLE WARNING SURFACES	EACH	6	\$250.00	\$1,500.00
497	604-06070 LINE K WESTWARD	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	425	\$58.00	\$24,650.00
498	604-08086 LINE K WESTWARD	CURB RAMP, CONCRETE	SYS	70	\$110.00	\$7,700.00
499	605-06120 LINE K WESTWARD	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
500	610-07713 LINE K WESTWARD	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$90.00	\$0.00
501	610-08446 LINE K WESTWARD	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	75	\$68.00	\$5,100.00
502	611-08233 LINE K WESTWARD	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	6	\$220.00	\$1,320.00
503	621-FWR01 LINE K WESTWARD	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	2100	\$2.53	\$5,313.00
504	621-FWR19 LINE K WESTWARD	TOPSOIL	TON	150	\$51.00	\$7,650.00
505	715-FWR27 LINE K WESTWARD	PIPE - 12" CMP	LFT		\$80.00	\$0.00
506	715-FWR39 LINE K WESTWARD	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	3150	\$9.90	\$31,185.00
507	715-94530 LINE K WESTWARD	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
508	720-FWR10 LINE K WESTWARD	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	4	\$203.50	\$814.00
509	720-FWR31 LINE K WESTWARD	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	5	\$660.00	\$3,300.00
510	720-FWR37 LINE K WESTWARD	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	4	\$858.00	\$3,432.00
511	801-FWR01 LINE K WESTWARD	MAINTENANCE OF TRAFFIC	LS	1	\$7,000.00	\$7,000.00
512	808-10033 LINE K WESTWARD	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
513	808-10034 LINE K WESTWARD	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
514	808-10036 LINE K WESTWARD	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
515	808-10037 LINE K WESTWARD	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
516	808-10051 LINE K WESTWARD	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
517	808-10052 LINE K WESTWARD	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
518	808-10053 LINE K WESTWARD	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
519	808-10056 LINE K WESTWARD	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
520	808-10077 LINE K WESTWARD	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
521	105-06845 LINE L MCARTHUR	CONSTRUCTION ENGINEERING	LS	1	\$3,076.00	\$3,076.00
522	110-01001 LINE L MCARTHUR	MOBILIZATION AND DEMOBILIZATION	LS	1	\$10,126.50	\$10,126.50
523	201-02255 LINE L MCARTHUR	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
524	201-02260 LINE L MCARTHUR	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,430.00	\$1,430.00
525	201-02265 LINE L MCARTHUR	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,573.00	\$1,573.00
526	201-02270 LINE L MCARTHUR	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
527	202-02240 LINE L MCARTHUR	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	7824	\$12.71	\$99,443.04
528	202-93615 LINE L MCARTHUR	CONCRETE REMOVE	SYS	1708.4	\$15.18	\$25,933.51
529	203-02000 LINE L MCARTHUR	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
530	205-06933 LINE L MCARTHUR	TEMPORARY INLET PROTECTION	EACH	12	\$102.00	\$1,224.00
531	214-11796 LINE L MCARTHUR	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	3130	\$8.36	\$26,166.80
532	301-FWR03 LINE L MCARTHUR	COMPATED AGGREGATE NO. 53	TON	2005	\$36.58	\$73,342.90
533	304-07490 LINE L MCARTHUR	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
534	502-FWR01 LINE L MCARTHUR	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	4728	\$48.15	\$227,653.20
535	502-11564 LINE L MCARTHUR	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
536	604-FWR01 LINE L MCARTHUR	DETECTABLE WARNING SURFACES	EACH	22	\$250.00	\$5,500.00
537	604-06070 LINE L MCARTHUR	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	713.4	\$58.00	\$41,377.20
538	604-08086 LINE L MCARTHUR	CURB RAMP, CONCRETE	SYS	180	\$110.00	\$19,800.00
539	605-06120 LINE L MCARTHUR	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
540	610-07713 LINE L MCARTHUR	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT	100	\$74.00	\$7,400.00
541	610-08446 LINE L MCARTHUR	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	715	\$68.00	\$48,620.00
542	611-08233 LINE L MCARTHUR	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	1	\$220.00	\$220.00
543	621-FWR01 LINE L MCARTHUR	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	3478	\$2.53	\$8,799.34
544	621-FWR19 LINE L MCARTHUR	TOPSOIL	TON	200	\$51.00	\$10,200.00
545	715-FWR27 LINE L MCARTHUR	PIPE - 12" CMP	LFT		\$80.00	\$0.00
546	715-FWR39 LINE L MCARTHUR	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	5216	\$10.01	\$52,212.16
547	715-94530 LINE L MCARTHUR	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	6	\$203.50	\$1,221.00
548	720-FWR10 LINE L MCARTHUR	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	6	\$203.50	\$1,221.00
549	720-FWR31 LINE L MCARTHUR	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
550	720-FWR37 LINE L MCARTHUR	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	14	\$858.00	\$12,012.00
551	801-FWR01 LINE L MCARTHUR	MAINTENANCE OF TRAFFIC	LS	1	\$13,000.00	\$13,000.00
552	808-10033 LINE L MCARTHUR	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
553	808-10034 LINE L MCARTHUR	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
554	808-10036 LINE L MCARTHUR	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
555	808-10037 LINE L MCARTHUR	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
556	808-10051 LINE L MCARTHUR	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT	27	\$22.00	\$594.00
557	808-10052 LINE L MCARTHUR	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
558	808-10053 LINE L MCARTHUR	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH	1	\$2,000.00	\$2,000.00
559	808-10056 LINE L MCARTHUR	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
560	808-10077 LINE L MCARTHUR	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
561	105-06845 LINE M BURNSDALE	CONSTRUCTION ENGINEERING	LS	1	\$2,702.00	\$2,702.00
562	110-01001 LINE M BURNSDALE	MOBILIZATION AND DEMOBILIZATION	LS	1	\$6,050.00	\$6,050.00
563	201-02255 LINE M BURNSDALE	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
564	201-02260 LINE M BURNSDALE	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,430.00	\$1,430.00
565	201-02265 LINE M BURNSDALE	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,573.00	\$1,573.00
566	201-02270 LINE M BURNSDALE	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
567	202-02240 LINE M BURNSDALE	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	2349	\$12.71	\$29,855.79
568	202-93615 LINE M BURNSDALE	CONCRETE REMOVE	SYS	467	\$16.12	\$7,528.04
569	203-02000 LINE M BURNSDALE	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
570	205-06933 LINE M BURNSDALE	TEMPORARY INLET PROTECTION	EACH	3	\$102.00	\$306.00
571	214-11796 LINE M BURNSDALE	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	940	\$8.36	\$7,858.40
572	301-FWR03 LINE M BURNSDALE	COMPATED AGGREGATE NO. 53	TON	768	\$34.60	\$26,572.80
573	304-07490 LINE M BURNSDALE	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON		\$350.00	\$0.00
574	502-FWR01 LINE M BURNSDALE	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	2349	\$47.00	\$110,403.00
575	502-11564 LINE M BURNSDALE	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
576	604-FWR01 LINE M BURNSDALE	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
577	604-06070 LINE M BURNSDALE	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	214	\$58.00	\$12,412.00
578	604-08086 LINE M BURNSDALE	CURB RAMP, CONCRETE	SYS		\$110.00	\$0.00
579	605-06120 LINE M BURNSDALE	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
580	610-07713 LINE M BURNSDALE	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT		\$80.00	\$0.00
581	610-08446 LINE M BURNSDALE	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	253	\$68.00	\$17,204.00
582	611-08233 LINE M BURNSDALE	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	1	\$220.00	\$220.00
583	621-FWR01 LINE M BURNSDALE	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	1044	\$2.53	\$2,641.32
584	621-FWR19 LINE M BURNSDALE	TOPSOIL	TON	40	\$51.00	\$2,040.00
585	715-FWR27 LINE M BURNSDALE	PIPE - 12" CMP	LFT		\$80.00	\$0.00
586	715-FWR39 LINE M BURNSDALE	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1566	\$9.46	\$14,814.36

587	715-94530 LINE M BURNSDALE	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
588	720-FWR10 LINE M BURNSDALE	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50
589	720-FWR31 LINE M BURNSDALE	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$660.00	\$660.00
590	720-FWR37 LINE M BURNSDALE	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
591	801-FWR01 LINE M BURNSDALE	MAINTENANCE OF TRAFFIC	LS	1	\$7,000.00	\$7,000.00
592	808-10033 LINE M BURNSDALE	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
593	808-10034 LINE M BURNSDALE	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
594	808-10036 LINE M BURNSDALE	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
595	808-10037 LINE M BURNSDALE	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
596	808-10051 LINE M BURNSDALE	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT		\$24.00	\$0.00
597	808-10052 LINE M BURNSDALE	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
598	808-10053 LINE M BURNSDALE	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
599	808-10056 LINE M BURNSDALE	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT		\$6.90	\$0.00
600	808-10077 LINE M BURNSDALE	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
601	105-06845 LINE N CHURCH	CONSTRUCTION ENGINEERING	LS	1	\$2,405.00	\$2,405.00
602	110-01001 LINE N CHURCH	MOBILIZATION AND DEMOBILIZATION	LS	1	\$8,443.50	\$8,443.50
603	201-02255 LINE N CHURCH	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
604	201-02260 LINE N CHURCH	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,430.00	\$1,430.00
605	201-02265 LINE N CHURCH	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
606	201-02270 LINE N CHURCH	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
607	202-02240 LINE N CHURCH	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	1950	\$12.82	\$24,999.00
608	202-93615 LINE N CHURCH	CONCRETE REMOVE	SYS	483	\$15.07	\$7,278.81
609	203-02000 LINE N CHURCH	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
610	205-06933 LINE N CHURCH	TEMPORARY INLET PROTECTION	EACH		\$102.00	\$0.00
611	214-11796 LINE N CHURCH	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	780	\$8.36	\$6,520.80
612	301-FWR03 LINE N CHURCH	COMPACTED AGGREGATE NO. 53	TON	670.5	\$34.10	\$22,864.05
613	304-07490 LINE N CHURCH	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	10	\$302.50	\$3,025.00
614	502-FWR01 LINE N CHURCH	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	1950	\$47.00	\$91,650.00
615	502-11564 LINE N CHURCH	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
616	604-FWR01 LINE N CHURCH	DETECTABLE WARNING SURFACES	EACH		\$300.00	\$0.00
617	604-06070 LINE N CHURCH	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	257	\$58.00	\$14,906.00
618	604-08086 LINE N CHURCH	CURB RAMP, CONCRETE	SYS	39	\$110.00	\$4,290.00
619	605-06120 LINE N CHURCH	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
620	610-07713 LINE N CHURCH	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT	141	\$74.00	\$10,434.00
621	610-08446 LINE N CHURCH	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	46	\$68.00	\$3,128.00
622	611-08233 LINE N CHURCH	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	1	\$220.00	\$220.00
623	621-FWR01 LINE N CHURCH	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	867	\$2.53	\$2,193.51
624	621-FWR19 LINE N CHURCH	TOPSOIL	TON	30	\$51.00	\$1,530.00
625	715-FWR27 LINE N CHURCH	PIPE - 12" CMP	LFT		\$80.00	\$0.00
626	715-FWR39 LINE N CHURCH	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	1300	\$10.34	\$13,442.00
627	715-94530 LINE N CHURCH	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	5	\$203.50	\$1,017.50
628	720-FWR10 LINE N CHURCH	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$203.50	\$203.50
629	720-FWR31 LINE N CHURCH	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	2	\$660.00	\$1,320.00
630	720-FWR37 LINE N CHURCH	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	2	\$858.00	\$1,716.00
631	801-FWR01 LINE N CHURCH	MAINTENANCE OF TRAFFIC	LS	1	\$9,000.00	\$9,000.00
632	808-10033 LINE N CHURCH	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
633	808-10034 LINE N CHURCH	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
634	808-10036 LINE N CHURCH	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
635	808-10037 LINE N CHURCH	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
636	808-10051 LINE N CHURCH	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT	14	\$22.00	\$308.00
637	808-10052 LINE N CHURCH	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
638	808-10053 LINE N CHURCH	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
639	808-10056 LINE N CHURCH	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT	60	\$6.60	\$396.00
640	808-10077 LINE N CHURCH	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
641	105-06845 LINE O ELZEY	CONSTRUCTION ENGINEERING	LS	1	\$2,702.00	\$2,702.00
642	110-01001 LINE O ELZEY	MOBILIZATION AND DEMOBILIZATION	LS	1	\$8,168.50	\$8,168.50
643	201-02255 LINE O ELZEY	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,600.00	\$0.00
644	201-02260 LINE O ELZEY	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$1,800.00	\$0.00
645	201-02265 LINE O ELZEY	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00
646	201-02270 LINE O ELZEY	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
647	202-02240 LINE O ELZEY	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	5805	\$12.76	\$74,071.80
648	202-93615 LINE O ELZEY	CONCRETE REMOVE	SYS	1175.4	\$14.96	\$17,563.98
649	203-02000 LINE O ELZEY	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
650	205-06933 LINE O ELZEY	TEMPORARY INLET PROTECTION	EACH	2	\$102.00	\$204.00
651	214-11796 LINE O ELZEY	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	2322	\$8.36	\$19,411.92
652	301-FWR03 LINE O ELZEY	COMPACTED AGGREGATE NO. 53	TON	1575	\$35.64	\$56,133.00
653	304-07490 LINE O ELZEY	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	5	\$302.50	\$1,512.50
654	502-FWR01 LINE O ELZEY	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS	5805	\$47.00	\$272,835.00
655	502-11564 LINE O ELZEY	PCCP, 7 IN. (PAVEMENT)	SYS		\$50.00	\$0.00
656	604-FWR01 LINE O ELZEY	DETECTABLE WARNING SURFACES	EACH	2	\$250.00	\$500.00
657	604-06070 LINE O ELZEY	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	537.4	\$58.00	\$31,169.20
658	604-08086 LINE O ELZEY	CURB RAMP, CONCRETE	SYS	113	\$110.00	\$12,430.00
659	605-06120 LINE O ELZEY	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT		\$12.50	\$0.00
660	610-07713 LINE O ELZEY	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT	301	\$74.00	\$22,274.00
661	610-08446 LINE O ELZEY	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	224	\$68.00	\$15,232.00
662	611-08233 LINE O ELZEY	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	3	\$220.00	\$660.00
663	621-FWR01 LINE O ELZEY	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	2580	\$2.53	\$6,527.40
664	621-FWR19 LINE O ELZEY	TOPSOIL	TON	200	\$51.00	\$10,200.00
665	715-FWR27 LINE O ELZEY	PIPE - 12" CMP	LFT		\$80.00	\$0.00
666	715-FWR39 LINE O ELZEY	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	3870	\$10.01	\$38,738.70
667	715-94530 LINE O ELZEY	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX)(UNDISTRIBUTED)	EACH	9	\$203.50	\$1,831.50
668	720-FWR10 LINE O ELZEY	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	7	\$203.50	\$1,424.50
669	720-FWR31 LINE O ELZEY	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	1	\$660.00	\$660.00
670	720-FWR37 LINE O ELZEY	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH	6	\$858.00	\$5,148.00
671	801-FWR01 LINE O ELZEY	MAINTENANCE OF TRAFFIC	LS	1	\$10,000.00	\$10,000.00
672	808-10033 LINE O ELZEY	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT		\$1.40	\$0.00
673	808-10034 LINE O ELZEY	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
674	808-10036 LINE O ELZEY	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT		\$1.40	\$0.00
675	808-10037 LINE O ELZEY	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT		\$2.50	\$0.00
676	808-10051 LINE O ELZEY	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT	13	\$22.00	\$286.00
677	808-10052 LINE O ELZEY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH		\$350.00	\$0.00
678	808-10053 LINE O ELZEY	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
679	808-10056 LINE O ELZEY	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT	80	\$6.60	\$528.00
680	808-10077 LINE O ELZEY	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH		\$350.00	\$0.00
681	105-06845 LINE P OLD TRAIL	CONSTRUCTION ENGINEERING	LS	1	\$3,301.50	\$3,301.50
682	110-01001 LINE P OLD TRAIL	MOBILIZATION AND DEMOBILIZATION	LS	1	\$11,226.50	\$11,226.50
683	201-02255 LINE P OLD TRAIL	TREE 18 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	2	\$1,358.50	\$2,717.00
684	201-02260 LINE P OLD TRAIL	TREE 30 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH	1	\$1,430.00	\$1,430.00
685	201-02265 LINE P OLD TRAIL	TREE 48 IN., REMOVE (INCLUDES STUMP GRINDING)	EACH		\$2,200.00	\$0.00

	686	201-02270 LINE P OLD TRAIL	TREE 60 IN., REMOVE	EACH		\$5,000.00	\$0.00
	687	202-02240 LINE P OLD TRAIL	PAVEMENT REMOVAL (INCLUDES INTEGRAL CURB and COMPOSITE PAVEMENT)	SYS	8175	\$12.65	\$103,413.75
	688	202-93615 LINE P OLD TRAIL	CONCRETE REMOVE	SYS	1451	\$16.17	\$23,462.67
	689	203-02000 LINE P OLD TRAIL	EXCAVATION, COMMON (UNDISTRIBUTED)	CYS		\$40.00	\$0.00
	690	205-06933 LINE P OLD TRAIL	TEMPORARY INLET PROTECTION	EACH	6	\$102.00	\$612.00
	691	214-11796 LINE P OLD TRAIL	GEOGRID, TYPE 1B, BX-1200 OR APPROVED EQUAL (INCLUDES EXCAVATION) (UNDISTRIBUTED)	SYS	3270	\$8.36	\$27,337.20
	692	301-FWR03 LINE P OLD TRAIL	COMPATED AGGREGATE NO. 53	TON	2100	\$35.86	\$75,306.00
	693	304-07490 LINE P OLD TRAIL	HMA PATCHING, TYPE B (UNDISTRIBUTED)	TON	2	\$302.50	\$605.00
	694	502-FWR01 LINE P OLD TRAIL	PCCP, 7" IN. WITH MONOLITHIC CURB	SYS		\$50.00	\$0.00
	695	502-11564 LINE P OLD TRAIL	PCCP, 7 IN. (PAVEMENT)	SYS	8175	\$48.00	\$392,400.00
	696	604-FWR01 LINE P OLD TRAIL	DETECTABLE WARNING SURFACES	EACH	6	\$250.00	\$1,500.00
	697	604-06070 LINE P OLD TRAIL	SIDEWALK, CONCRETE (4 IN.) (INCLUDE YARD WALKS) (UNDISTRIBUTED)	SYS	540	\$58.00	\$31,320.00
	698	604-08086 LINE P OLD TRAIL	CURB RAMP, CONCRETE	SYS	122	\$110.00	\$13,420.00
	699	605-06120 LINE P OLD TRAIL	CURB, CONCRETE (TYPE IIA, PIN CURB ON AFTER STREET POURED)	LFT	3723	\$12.50	\$46,537.50
	700	610-07713 LINE P OLD TRAIL	PCCP FPR APPROACHES, 8 IN. (COMMERCIAL APPROACHES)	LFT	521	\$74.00	\$38,554.00
	701	610-08446 LINE P OLD TRAIL	PCCP FOR APPROACHES, 6 IN. (RESIDENTIAL DRIVES) (UNDISTRIBUTED)	SYS	268	\$68.00	\$18,224.00
	702	611-08233 LINE P OLD TRAIL	MAILBOX ASSEMBLY, RESET SINGLE AND DOUBLE (INCLUDES ALL MAILBOXES AND TYPES) (IF IN CONFLICT)	EACH	3	\$220.00	\$660.00
	703	621-FWR01 LINE P OLD TRAIL	HYDROSEED, WITH HYDROSTICK TACKIFIER OR EQUIVALENT POLYMER FOR EROSION CONTROL AND STRAW MULCH	SYS	2934	\$2.53	\$7,423.02
	704	621-FWR19 LINE P OLD TRAIL	TOPSOIL	TON	160	\$51.00	\$8,160.00
	705	715-FWR27 LINE P OLD TRAIL	PIPE - 12" CMP	LFT		\$80.00	\$0.00
	706	715-FWR39 LINE P OLD TRAIL	PIPE, TYPE 4, CIRCULAR, 6 IN. W/AGGREGATE FOR UNDERDRAIN	LFT	5318	\$8.97	\$47,702.46
	707	715-94530 LINE P OLD TRAIL	ADJUST WATER VALVE TO GRADE (CURB BOX AND VALVE BOX) (UNDISTRIBUTED)	EACH	2	\$203.50	\$407.00
	708	720-FWR10 LINE P OLD TRAIL	CASTING, ADJUST TO GRADE (UNDISTRIBUTED)	EACH	22	\$203.50	\$4,477.00
	709	720-FWR31 LINE P OLD TRAIL	CASTING, 24" SOLID SANITARY MANHOLE, FURNISH AND ADJUST TO GRADE (UNDISTRIBUTED)	EACH	3	\$660.00	\$1,980.00
	710	720-FWR37 LINE P OLD TRAIL	CASTING - 2' X 2' CURB & GUTTER CASTING & ADJUST TO GRADE	EACH		\$960.00	\$0.00
	711	801-FWR01 LINE P OLD TRAIL	MAINTENANCE OF TRAFFIC	LS	1	\$21,000.00	\$21,000.00
	712	808-10033 LINE P OLD TRAIL	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	LFT	100	\$1.10	\$110.00
	713	808-10034 LINE P OLD TRAIL	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	LFT	570	\$1.10	\$627.00
	714	808-10036 LINE P OLD TRAIL	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	LFT	240	\$1.10	\$264.00
	715	808-10037 LINE P OLD TRAIL	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	LFT	50	\$2.20	\$110.00
	716	808-10051 LINE P OLD TRAIL	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	LFT	27	\$22.00	\$594.00
	717	808-10052 LINE P OLD TRAIL	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	EACH	1	\$275.00	\$275.00
	718	808-10053 LINE P OLD TRAIL	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	EACH		\$2,000.00	\$0.00
	719	808-10056 LINE P OLD TRAIL	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	LFT	120	\$6.60	\$792.00
	720	808-10077 LINE P OLD TRAIL	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION AR ROW	EACH	1	\$275.00	\$275.00
Allowance							\$150,000.00
	721	10904299	Work Allowance	DOL	150000	\$1.00	\$150,000.00
Base Bid Total:							\$6,680,662.37

Drug Policy Acknowledgement Form

Contractor acknowledges the City of Fort Wayne has in place a Drug and Alcohol Policy that applies to any Contractor doing business with the City. A copy of this policy is available for inspection on the City of Fort Wayne website at: <http://www.cityoffortwayne.org/purchasing-home.html>. As a condition of being awarded any contract, the successful bidder shall sign this Drug Policy Acknowledgement and agree to be bound by those provisions of the policy that may be applicable. A copy of this form will be retained by the City of Fort Wayne.

The undersigned, on behalf of the Contractor deposes and states that the Contractor acknowledges the City of Fort Wayne's Alcohol and Drug Policy.

Name of Company

By: _____

Name and Title

E-Verify Affidavit

Pursuant to Indiana Code 22-5-1.7, Contractor agrees and shall enroll in and verify the work eligibility status of all newly hired employees of the contractor through the E-Verify program. E-Verify means the electronic verification of work authorization program of the Illegal Immigration Reform and Immigration Responsibility Act of 1996 (P.L. 104-208). Division C, Title IV, s.403(a), as amended, operated by the United States Department of Homeland Security or a successor work authorization program designated by the United States Department of Homeland Security or other federal agency authorized to verify the work authorization status of newly hired employees under the Immigration Reform and Control Act of 1986 (P.L. 99-603). Contractor is not required to verify the work eligibility status of all newly hired employees of Contractor through the E-verify program if the E-Verify program no longer exists.

The undersigned, on behalf of the Contractor, being first duly sworn, deposes and states that the Contractor does not knowingly employ an unauthorized alien. The undersigned further affirms that, prior to entering into its contract with the City, the undersigned Contractor will enroll in and agrees to verify the work eligibility status of all its newly hired employees through the E-Verify program.

Name of Company

By: _____
Title

ACKNOWLEDGEMENT

STATE OF INDIANA)
) SS
COUNTY OF ALLEN)

Before me, a Notary Public, in and for said State and County, personally appeared the within named Company by Name, Title, who being first duly sworn upon his/her oath states that he/she is a duly authorized agent of the Contractor, and as such duly authorized to execute the foregoing Declaration, and acknowledged the same as his/her voluntary act and deed.

WITNESS my hand and seal this _____ day of _____, 20_____.

My Commission Expires: _____

Signature of Notary Public

Resident of _____ County

Printed Name

COUNCIL DIGEST SHEET

Enclosed with this introduction form is a tab sheet and related material from the vendor(s) who submitted bid(s). Public Works is providing this information to Council as an overview of this award.

Community Crossings Grant 2025

RFPs & BIDS

Bid/RFP #	0721C
Awarded To	Malott Contracting Inc
Amount	\$6,680,662.37
Conflict of interest on file?	N/A
Number of Registrants	8
Number of Bidders	3
Required Attachments	Council Digest Supplemental, Bid Tabulation, Award, Contract

EXTENSIONS

Date Last Bid Out	N/A
# Extensions Granted To Date	N/A

SPECIAL PROCUREMENT

Contract #/ID <i>(State, Federal, Piggyback--Authority)</i>	0721C
Sole Source/ Compatibility Justification	N/A

BID CRITERIA *(Take Buy Indiana requirements into consideration.)*

Most Responsible, Responsive Lowest	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>If no, explain below</i>
If not lowest, explain	N/A

COUNCIL DIGEST SHEET

COST COMPARISON

<i>Increase/decrease amount from prior years For annual purchase (if available).</i>	N/A
--------------------------------------------------------------------------------------	-----

DESCRIPTION OF PROJECT / NEED

<i>Identify need for project & describe project; attach supporting documents as necessary.</i>	Please see attached Council Digest Supplemental

REQUEST FOR SUSPENSION OF RULES

<i>Provide justification if prior approval is being requested.</i>	N/A

FUNDING SOURCE

<i>Account Information.</i>	Community Crossings Grant & LIT-ED



FW PUBLIC WORKS

Board of Public Works

In Your Neighborhood

COMMON COUNCIL DIGEST SHEET – SUPPLEMENTAL

Community Crossings Grant 2025

Action Requested:

Requesting an Ordinance approving the **Community Crossings Grant 2025** project pursuant to the Board of Public Works Resolution #0721C and an award to **Malott Contracting, Inc** in the amount of **\$6,680,662.37**.

Note: Malott Contracting was the lowest, most responsive bidder among 3 bidders. Malott Contracting's bid was just below the Engineer's Estimate for this project. \$1.5 million of this project will be paid for with the Community Crossings Grant.

Description and Scope of the Work:

Improve the Westchester Neighborhood and S.W. Waynedale Neighborhood, by the removal of the existing concrete streets and replacing with new concrete streets. The removal and replacement of select existing sidewalk and drive approaches. Removing existing curb ramps and replacing with new ADA compliant curb ramps. There will be subsurface drainage installed and the replacement and adjustment of existing castings with the restoration of disturbed areas.

BILL NO. S-25-06-07

REPORT OF COMMITTEE ON PUBLIC WORKS

June 24, 2025

Martin Bender Chair

Rohli Booker Co-Chair

All Council Members

An Ordinance approving Construction Contract – Community Crossings Grant 2025 between Malott Contracting, INC. and the City of Fort Wayne, Indiana, by and through its Board of Public Works

Involving a total cost of \$6,680,662.37

COMMITTEE ON PUBLIC WORKS HAVE HAD SAID Ordinance under consideration and beg leave to report back to the Common Council that said Ordinance

<u>COUNCIL MEMBER</u>	<u>DO PASS</u>	<u>DO NOT PASS</u>	<u>ABSTAIN</u>
<u>BENDER</u>	<u><i>M. Bender</i></u>		
<u>BOOKER</u>	<u><i>Rohli Booker</i></u>		
<u>CHAMBERS</u>			
<u>ENSLEY</u>	<u><i>R. Ensley</i></u>		
<u>FREISTROFFER</u>	<u><i>Alfred Freistroffer</i></u>		
<u>HARTMAN</u>	<u><i>Nathan Hartman</i></u>		
<u>JEHL</u>	<u><i>Tom Jehl</i></u>		
<u>MYERS</u>	<u><i>Sam Myers</i></u>		
<u>PADDOCK</u>	<u><i>Greg Paddock</i></u>		

**LANA R. KEESLING
CITY CLERK**

Lana R. Keesling

Public Hearing Date: N/A


Read the first time in full and on motion by Councilperson Bender.

Read the second time by title and referred to the Public Works Committee.

Read the third time in full and on motion by Councilperson Bender, placed on passage by the following vote:

<u>TOTAL VOTES</u>	<u>AYES</u>	<u>NAYS</u>	<u>ABSTAINED</u>	<u>ABSENT</u>
BENDER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
BOOKER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
CHAMBERS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
ENSLEY	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
FREISTROFFER	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
HARTMAN	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
JEHL	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
MYERS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
PADDOCK	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

DATED: June 24, 2025



LANA R. KEESING, CITY CLERK

Passed and adopted by the Common Council of the City of Fort Wayne, Indiana, as

Special Ordinance No. S-25-06-07 on the 24th day of June, 2025

ATTEST:




LANA R. KEESLING
CITY CLERK




PRESIDING OFFICER

Presented by me to the Mayor of the City of Fort Wayne, Indiana, on the 25th of June 2025, at the hour of 9:35 o'clock A.M. E.S.T.



LANA R. KEESLING, CITY CLERK

Approved and signed by me this 25th day of June 2025, at the hour of 4:36 o'clock p.m. E.S.T.



SHARON TUCKER, MAYOR